

**RETURN BIDS TO:**  
**RETOURNER LES SOUMISSIONS À:**  
**Public Works Government Services Canada- Bid**  
**Receiving / Réception des soumissions**  
**189 Prince William Street**  
**Room 421**  
**Saint John**  
**New Brunswick**  
**E2L 2B9**

**SOLICITATION AMENDMENT**  
**MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

**Comments - Commentaires**

**Vendor/Firm Name and Address**  
**Raison sociale et adresse du**  
**fournisseur/de l'entrepreneur**

**Issuing Office - Bureau de distribution**  
**Public Works Government Services Canada- Bid**  
**Receiving / Réception des soumissions**  
**189 Prince William Street**  
**Room 421**  
**Saint John**  
**New Bruns**  
**E2L 2B9**

<b>Title - Sujet</b> Electrical Work, GOCB, Moncton	
<b>Solicitation No. - N° de l'invitation</b> EC015-132002/A	<b>Amendment No. - N° modif.</b> 002
<b>Client Reference No. - N° de référence du client</b> R.053240.002	<b>Date</b> 2012-10-30
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWB-020-3157	
<b>File No. - N° de dossier</b> PWB-2-35087 (020)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2012-11-08</b>	<b>Time Zone</b> <b>Fuseau horaire</b> Atlantic Daylight Saving Time ADT
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Donovan, Janine PWB	<b>Buyer Id - Id de l'acheteur</b> pwb020
<b>Telephone No. - N° de téléphone</b> (506) 636-5347 ( )	<b>FAX No. - N° de FAX</b> (506) 636-4376
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b>	

**Instructions: See Herein**

**Instructions: Voir aux présentes**

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

Cette modification de l'invitation numéro deux (2) est soumise et comprend la modification numéro 2 suivante.

La modification qui suit apportée aux documents de soumission entre en vigueur dès maintenant. L'addenda fera partie des documents de contrat.

Toutes autres conditions ne changent pas.

## 1. **DEVIS**

### 1 **Specification Section 01 11 00 Summary Of Work:**

- .1 Revise Paragraph 1.8.2 to read, " Where Work involves breaking into or connecting to existing services, give the Departmental Representative 30 days notice for necessary interruption of mechanical or electrical service throughout course of work. Minimize duration of interruptions. Carry out work at times as directed by governing authorities with minimum disturbance to pedestrian, vehicular traffic and Owner operations."

### 2 **Specification Section 26 33 53 Static Uninterruptible Power Supply**

- .1 Maintenance bypass cabinet, input transformer and battery rack have been procured by the owner. The contractor shall receive these items from the owner and shall install these items as noted on the drawings.
- .2 Factory start-up testing (excluding load bank testing) for the UPS and maintenance by-pass cabinets have been pre-procured by the owner. The contractor shall assist the manufacturer's representative during factory start-up testing and shall carry all costs associated with load bank testing.

## 2. **DESSINS**

### **Drawing E-101 Electrical Plans and Details**

- .1 Maintenance bypass cabinet, input transformer and battery rack have been procured by the owner. The contractor shall receive these items from the owner and shall install these items as noted on the drawings.
- .2 Suggested Phasing - UPS Changeover: Revise step 4 to read, "Coordinate shutdown of panel "1EDPB" with data centre manager and building owner. Data centre ups#4 will be running on battery. Shutdowns to be scheduled for 15 minute durations with time in between to allow for batteries to recharge. Allow for one shutdown per night over multiple nights until task is complete."
- .3 Suggested Phasing - UPS Changeover: Delete steps 5 and 8.

- 
- .4 Suggested Phasing - UPS Changeover: Revise step 9 to read, "Test and commission UPS#6 on remote load bank."
  - .5 Suggested Phasing - UPS Changeover: Revise step 13 to read, "Coordinate shutdown of panel "1EDPC" with data centre manager and building owner. Data centre UPS's will be running on battery and the cooling system will be shut down. Both battery capacity and data centre temperature will dictate the actual length of shutdowns. Shutdowns are to be scheduled for 15 minute durations with time in between to allow for batteries to recharge. Allow for one shutdown per night over multiple nights until task is complete."
  - .6 Suggested Phasing - UPS Changeover: Revise step 14 to read, "Lock off power to panel "1EDPC" by opening and locking out the breakers in panels 1EDPA and 1EDPD that feed ATS#2."
  - .7 General Notes: Revise Note 7 to read, "Provide a sequence of work documentation for approval to the tenant (SSC) and/or the project manager (PWGSC) prior to commencement of work."