

PWGSC	North Portal, SK	Addendum No. 2
Western Region	North Portal Generator Project	July 26, 2012
Project No. R.042177.002	Generator & Utility Service Upgrade	Page 1 of 1

The following changes to the tender documents are effective immediately and will form part of the contract documents:

AMENDMENT TO DRAWINGS/SPECIFICATIONS

Questions (Q) and Answers (A):

1. **Q:** What is the route of the utilities entering the building (underground utilities, concerns)?
A: Verify all U/G utilities e.g. (gas, water, power) being affected by this project. Also see note 2 (E04)
2. **Q:** Are there any concerns regarding the patch of asphalt directly south of the international building?
A: Refer to note 6 on (E10) and note 4 on (E03).
3. **Q:** Crawl space clearance from entry point to electrical room, a slope was noted.
A: Crawl space construction to be completed under appropriate methods including confined space access. If necessary submit alternate routes for approval by PWGSC review.
4. **Q:** Where would contractors put a lunch, storage trailer?
A: Location as directed by Departmental Representative.
5. **Q:** Is the location of the generator confirmed? Although noted on the specs that it is not verified, how much wiggle room would they have?
A: Refer to note 6 (E04)
6. **Q:** Is the holding cell in the inspection garage off limits for construction?
A: Access to this site has some restrictions due to the sensitive nature of its operations. Not all areas will be accessible at all times.
7. **Q:** Wall space for new 400A SE main breaker and required CT cabinet in Vehicle Inspection Building?
A: Locate new SE breaker on outside wall in the muster room. CT cabinet is existing.
8. **Q:** Wall space for new 400A load break switch, auto transfer switch, splitter, and 3 disconnect breakers in maintenance room of International Building?
A: Designated wall is available for electrical equipment. Existing storage closet, work bench and hanging tool crib to be relocated as directed by Departmental Representative.

- END OF ADDENDUM -