

Please be advised of the following changes to the Contract Drawings and Tender Documents:

DRAWINGS

1. Drawing WWTP-A-30
 - a. Note revisions to the Room Finish Schedule as noted below. These changes are to be read in conjunction with the specification sections issued as part of this Addendum No.3:
 - i. 09 30 14, Porcelain Tiling
 - ii. 09 65 00, Resilient Flooring
 - iii. 09 91 00, Painting
 - iv. 09 96 35, Chemical Resistant Coating
 - b. Provide Chemical Resistant Coating (CRC) floor finish to the following rooms:
115 Chemical storage, 116 Tank Room, 117 Maintenance Room, 118, Membrane Room, 119 Process Blowers, 120 Brine Room, 121 Plant, 126, Evaporator Room.
 - c. Provide Concrete Floor Sealer to the following rooms:
127 Electrical Room, 129 Dirty Storage, 130 Janitor room, 201 Mechanical Room, 202 Electrical room, 203 Air Compressor.
 - d. Disregard notes listed in the "comments" column.
2. Drawing WWTP-A-34, Det 9/A-xx, Drawing WWTP-A-35, Det 1/A-34 & 2/-.
 - a. Note revisions to Section at "Checker plate and Lifting Handle for two sump pits. These changes are to be read in conjunction with the specification 08 31 00 issued as part of this Addendum No.3.
 - b. Provide heavy duty prefabricated aluminum hatch cover over sump pits in lieu of steel plate covers presently indicated.