

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Public Works and Government Services Canada
Telus Plaza North, 5th floor
10025 Jasper Avenue
Edmonton
Alberta
T5J 1S6
Bid Fax: (780) 497-3510

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada
Northern Contaminated Site Program
Telus Plaza North, 5th floor
10025 Jasper Avenue
Edmonton
Alberta
T5J 1S6

Title - Sujet Mould Remediation	
Solicitation No. - N° de l'invitation W0127-12PO09/A	Amendment No. - N° modif. 006
Client Reference No. - N° de référence du client W0127-12PO09	Date 2012-12-20
GETS Reference No. - N° de référence de SEAG PW-\$NCS-002-9615	
File No. - N° de dossier NCS-2-35286 (002)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2013-01-16	Time Zone Fuseau horaire Mountain Standard Time MST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Poot (NCS), Marc	Buyer Id - Id de l'acheteur ncs002
Telephone No. - N° de téléphone (780) 497-3520 ()	FAX No. - N° de FAX (780) 497-3842
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

SOLICITATION AMENDMENT - 006

Revision: Amended Scope of Work

STATEMENT OF WORK..... ANNEX A

1. Title:

Mould remediation services at Building 175, 1 Field Ambulance, Canadian Forces Base Edmonton.

2. Objective:

For the supply of all supervision, material, equipment, labour and transportation necessary to provide mould remediation services at Building 175, 1 Field Ambulance, Canadian Forces Base Edmonton.

3. Scope of Work: As per City of New York Guidelines on Assessment and Remediation of Fungi in Indoor Environments, Level III: (or equivalent protocol)

- (a) Setup of containment area to capture offices, rooms, and corridors;
- (b) HEPA filtered negative air unit exhausted to the exterior and decontamination chambers for personal access;
- (c) Clean and remove furniture or items that are in good condition from the rooms and store where indicated;
- (d) Dispose of water damaged shelves, cabinets, and furniture
- (e) Remove and clean light fixtures and store where indicated;
- (f) Remove and dispose of ceiling tiles / grids as required;
- (g) Remove and dispose of gypsum walls identified in the report;
- (h) Remove and dispose of all acoustic bat insulation;
- (i) All steel (i.e. studs and tracks) is to be cleaned and dried expediently;
- (j) Remove and dispose of any rusted steel (confirmation to be sought first);
- (k) Disconnect all attachments from plywood deck clean and save for re-install;
- (l) Remove affected plywood deck;
- (m) Telecom cable to be pulled back and tagged by others, tray to be supported during deck removal;
- (n) Fire alarm and sprinkler systems to be actioned as per site visit questions:
- (o) Wash floors;
- (p) Clean containment areas;
- (q) Final inspection and acceptance including viable mould testing by others prior to removal of containment structure; and,
- (r) Final work area clean-up,
- (s) All work to be completed as per scope of work and site visit questions.

**SITE VISIT QUESTIONS - B1g-175 CFB EDMONTON
6 DEC 2012**

1. What happens to the plywood roof?

The entire plywood is to be removed. The utilities on the roof shall be removed in such a manner as to be reinstalled. All disconnecting means shall be the responsibility of the contractor.

2. What about power and water?

Water is available in the janitor closet. Electrical panels are shown on the supplied print.

3. What about cabinet disposal?

Cabinet removal and disposal shall be the responsibility of the contractor.

4. What about load bearing walls?

Should not be an issue due to the removal of the roof. Should any part of a wall need to be removed, then shoring of the existing structure shall be the responsibility of the contractor.

5. What about the outside wall of the structure?

When the inside of the outside walls are opened, and it is determined that the outside wall removal is necessary, then there will be an extra cost at that time. Do not include the removal of the outside wall in the current bid.

6. What about the removal of the doors and frames?

Door and frame removal and decontamination shall be the responsibility of the contractor. Once cleaned, doors and frames can be stored on site.

7. What about the tiled wall in the janitor closet?

The tiles will all be removed as part of the remediation.

8. What about the floor tiles?

The floor will be cleaned as part of the remediation. No further action to be taken.

9. What about the fire alarm and sprinkler systems?

1. Fire Alarms - there is one signalling device. It shall be disconnected by an electrician and saved for re-install later. The Fire alarm panel will stay in a trouble state. Local permitting no cost.
2. Sprinkler System – System to be drained by others. Sprinkler technician to remove existing heads and cap. Heads to be saved for re-install. Re-pressurization of system by others. Local permitting no cost.

10. How much room must be left in hallway for passage?

The hallway must have 1.1m for passage clearance.

Solicitation No. - N° de l'invitation

W0127-12PO09/A

Amd. No. - N° de la modif.

006

Buyer ID - Id de l'acheteur

ncs002

Client Ref. No. - N° de réf. du client

W0127-12PO09

File No. - N° du dossier

NCS-2-35286

CCC No./N° CCC - FMS No/ N° VME

Drawings as requested at site visit - separate attachments