

05/09/2012

PITTSBURGH INSTITUTION
BUILDING PP85
PWGSC # R.045087.001

Questions and Answers

Question 30: NS90 is not a current and commonly manufactured specifications, can we substitute to NS75.

A30 Response: NS75 is acceptable.

Question 31: 500 MCM NS90 is not manufactured item, please advise what to use.

A31 Response: On drawing C-201, revise "2 Runs of 3-500 MCM NS90 Overhead" to "4 Runs of 3-4/O NS75".