

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving - PWGSC / Réception des soumissions -
TPSGC
11 Laurier St./11 rue Laurier
Place du Portage, Phase III
Core 0A1 / Noyau 0A1
Gatineau, Québec K1A 0S5

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires
THIS DOCUMENT CONTAINS A SECURITY
REQUIREMENT

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Construction Services Division/Division des services de
construction
11 Laurier St./11 Rue Laurier
3C2, Place du Portage
Phase III
Gatineau, Québec K1A 0S5

Title - Sujet Mess Hall Stair Renovation	
Solicitation No. - N° de l'invitation EP077-131767/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client R.019633.202	Date 2012-11-06
GETS Reference No. - N° de référence de SEAG PW-\$\$\$FG-340-61422	
File No. - N° de dossier fg340.EP077-131767	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2012-11-13	
Time Zone Fuseau horaire Eastern Daylight Saving Time EDT	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Brouillet, Richard	Buyer Id - Id de l'acheteur fg340
Telephone No. - N° de téléphone (819) 956-0457 ()	FAX No. - N° de FAX (819) 956-8335
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: Public Works and Government Services National Defence Headquarters Mess Hall 4 Queen Elizabeth Drive Ottawa, ON K1A 0S5	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation

EP077-131767/A

Client Ref. No. - N° de réf. du client

R.019633.202

Amd. No. - N° de la modif.

001

File No. - N° du dossier

fg340EP077-131767

Buyer ID - Id de l'acheteur

fg340

CCC No./N° CCC - FMS No/ N° VME

THE PURPOSE OF THIS AMENDMENT IS TO ISSUE ADDENDUM NO. 1

End of amendment

Solicitation No. - N° de l'invitation

EP077-131767/A

Client Ref. No. - N° de réf. du client

R.019633.202

Amd. No. - N° de la modif.

001

File No. - N° du dossier

fg340EP077-131767

Buyer ID - Id de l'acheteur

fg340

CCC No./N° CCC - FMS No/ N° VME

Addendum No. 1

NDHQ MESS HALL STAIR RENOVATION
Project No. R.019633.202

Page 1 of 2
DATE: November 6, 2012

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents.

ARCHITECTURAL DRAWINGS:

- .1 Drawing A300**
 - .1 DELETE** note 11 and **ADD** new note 11 to read:
ENGINEERED LAMINATED STRUCTURAL GLAZING GUARD SET IN EXTRUDED ALUMINUM SHOE. SEE SPECIFICATION.
- .2 Drawing A400**
 - .1 DELETE** note 10 and **ADD** new note 11 to read:
PROPRIETARY NYLON SPACER TO SUIT 19mm GLASS THICKNESS. HOLE TO BE DRILLED PRIOR TO LAMINATING GLASS.
 - .2 DELETE** note 11 and **ADD** new note 11 to read:
ENGINEERED LAMINATED STRUCTURAL GLAZING GUARD SET IN EXTRUDED ALUMINUM SHOE. SEE SPECIFICATION.
- .3 Drawing ME-1**
 - .1 DELETE** note 4 and **ADD** new note 4 to read:
EXISTING CHANDELIER TO BE DISCONNECTED AND PROTECTED FOR DURATION OF CONSTRUCTION. PROVIDE TEMPORARY LIGHTING FOR ALL TRADES DURING CONSTRUCTION. RE-INSTALL CHANDELIER AT COMPLETION OF CONSTRUCTION.

SPECIFICATIONS:

- .1 Section 01 00 10 General Instructions**
 - .1 1.22.4**
DELETE 1.22.4 and ADD new 1.22.4:
Carry out all work involving noise or materials that produce off gassing during "off hours" Sunday to Friday from 01:00 to 07:30 hours. Thoroughly ventilate areas painted and carpeted during "off hours".
 - .2 1.22.5**
DELETE 1.22.5 and ADD new 1.22.5:
Carry out work during "regular hours" Sunday to Friday from 07:30 to 19:30 hours.
 - .3 1.22.8**
ADD new 1.22.8:
Contractor to take control of site on January 2, 2013 for commencement of construction activities. Prior to January 2, 2013 and after contract award, contractor site access for site measurements to be coordinated with Departmental Representative. Contractor to acquire building permit prior to commencement of work. All permit fees are the responsibility of the contractor.

- .4 **1.25.3**
DELETE 1.25.3 and ADD new 1.25.3:
On public side of enclosure finish gypsum seams, paint walls, frames and doors. Refer to Section 09 21 16, part 3.4.2.1, Finishing, Level 4. Install temporary rubber base to provide finished appearance to the approval of the departmental representative.
- .5 **1.28.1**
DELETE 1.28.1 and ADD new 1.28.1:
Hire the services of the base building fire alarm contractor in support of demolition, section 21 13 13 Wet Pipe Sprinkler Systems and construction work.
- .6 **1.28.2**
ADD new 1.28.2:
Base Building Fire alarm contractor contact:

Chubb Edwards
Tineke Postma
Service Coordinator
Chubb Edwards
8 Hearst Way
Kanata Ontario K2L 2P4 Canada
T + 1 613 254 7422 ext. 321210
F + 1 613 254 7376
Email tineke.postma@chubbedwards.com
- .2 **Section 05 73 13 Glazed Decorative Metal Railing**
- .1 **1.2.1 System Description**
DELETE tempered clear glass and **ADD** laminated tempered glass.
- .2 **2.2.4. Components**
DELETE Glass: to CAN/CGSB-12.1. Type 2 - tempered. Class B - float. Thickness: 19.1 mm and;
ADD Glass: to CAN/CGSB-12.1. laminated glass. Laminated tempered glass to meet standards of Ontario Building Code and National Building Code of Canada. Total assembled thickness of laminated panels to be 19.1 mm.
- .3 **Section 09 30 13 Ceramic Tiling**
- .1 1.4 Quality Assurance **ADD** item:
- 1.4.3 Mock-ups:
- .1 Construct mock-ups in accordance with Section 01 45 00 – Quality Assurance.
- .2 Provide mock-up of removal of existing ceramic tile in area of new room 107B.
- .3 Locate where directed by the Departmental Representative.
- .4 Allow 24 Hours for inspection of mock-up before proceeding with work.
- .5 When accepted, mock-up will demonstrate minimum standard for this work.