

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Public Works Government Services Canada- Bid
Receiving / Réception des soumissions
189 Prince William Street
Room 421
Saint John
New Brunswick
E2L 2B9

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works Government Services Canada- Bid
Receiving / Réception des soumissions
189 Prince William Street
Room 421
Saint John
New Bruns
E2L 2B9

Title - Sujet 50 Bed Living Unit, Westmorland Ins	
Solicitation No. - N° de l'invitation EC016-130878/A	Amendment No. - N° modif. 016
Client Reference No. - N° de référence du client R.043929.001	Date 2012-09-14
GETS Reference No. - N° de référence de SEAG PW-\$PWB-020-3101	
File No. - N° de dossier PWB-2-35024 (020)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2012-09-19	Time Zone Fuseau horaire Atlantic Daylight Saving Time ADT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Donovan, Janine PWB	Buyer Id - Id de l'acheteur pwb020
Telephone No. - N° de téléphone (506) 636-5347 ()	FAX No. - N° de FAX (506) 636-4376
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Cette modification de l'invitation numéro 16 est soumise et comprend la modification numéro 16 suivante.

La modification qui suit apportée aux documents de soumission entre en vigueur dès maintenant. L'addenda fera partie des documents de contrat.

Toutes autres conditions ne changent pas.

Modification numéro 16

1. QUESTIONS ET RÉPONSES

Q1: Section 01 50 00 Temporary Facilities and amendment #5 states “provide temporary fence to enclose the construction area of work site”. Does the construction area just include a fence around the new building or is the access road from the entrance off the main road of the institution to the new building location also to be fenced? If this access road is to be fenced, can you please provide information on the length and layout of the access road.

A1: Construction area of work site is self-explanatory: The area of the site on which construction is going to take place. There is no requirement to fence off the full length of the access roadway.

Q2: In details 5, 8, 11 & 12/A-306, there are no anchor bolts shown to fasten the wall sill plate to the foundation. Please provide anchoring method and details for size & quantity of anchors (as per addendum #13 no explosive cartridge tools are permitted on site).

A2: Any anchors will have to be drilled or cast-in, not shot-fired.

Q3: On floor plan A-400.1, Wall Type P3 against the foundations wall and detail 4/A-310 indicates the drywall & vapor barrier wrap continuously around the corner (Grid 5-U & 21-N). There is no indication the same is true at pilasters on Grid 5-Q, 5-T, 5-U, 7-U, 10-U, 13-U, 14-U, 20-U, 21-T, 21-R, 21-N. Please provide details of how Wall Type P3 is constructed at the pilasters.

A3: Vapour barrier is continuous across front face of pilasters throughout. Normal building Best Practice should be followed

Q4: Partition P1.4 & P2.4 are to have plywood sheathing on the washroom side of walls. Washroom #105, 106, 204, 205 & Urineanalysis #117 do not have those wall types, however, they still have WR Accessories to be mounted on the walls. Please clarify if these washrooms are to have 2440mm height plywood backing.

A4: Only inmate washrooms to have continuous plywood. Other washrooms will have localized blocking to support accessories.

Q5: Re drawing # A-008 - per Answer 27 in Amendment #13 there is no such drawing, however in the tender documents we received it certainly exists and is titled "Floor and Wall Finishes Legend", which agrees with the list of drawings on the cover sheet.

A5: Our mistake. The drawings were re-numbered shortly before they went out to tender. Drawing A-008 is the correct reference and it does exist.

2. **DEVIS**

.1 Reference Specification Section 09 65 19 Resilient Flooring

**1. Amend Specification Paragraph 2.1.1 to read:
Resilient vinyl Tile to ASTM F1066, Class 2, smooth surface, through
pattern. 3.2mm Thickness**