

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving - PWGSC / Réception des soumissions -
TPSGC
11 Laurier St./11 rue Laurier
Place du Portage, Phase III
Core 0A1 / Noyau 0A1
Gatineau, Québec K1A 0S5

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires
THIS DOCUMENT CONTAINS A SECURITY
REQUIREMENT

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Construction Services Division/Division des services de
construction
11 Laurier St./11 Rue Laurier
3C2, Place du Portage
Phase III
Gatineau, Québec K1A 0S5

Title - Sujet Base Building Upgrades	
Solicitation No. - N° de l'invitation EP777-133648/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client 20133648	Date 2013-05-07
GETS Reference No. - N° de référence de SEAG PW-\$\$FG-340-62613	
File No. - N° de dossier fg340.EP777-133648	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2013-05-14	
Time Zone Fuseau horaire Eastern Daylight Saving Time EDT	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Brouillet, Richard	Buyer Id - Id de l'acheteur fg340
Telephone No. - N° de téléphone (819) 956-0457 ()	FAX No. - N° de FAX (819) 956-8335
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: Department of Public Works and Government Services Canada 79 Sparks Street Ottawa, ON K1A 0S5	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation

EP777-133648/A

Amd. No. - N° de la modif.

001

Buyer ID - Id de l'acheteur

fg340

Client Ref. No. - N° de réf. du client

20133648

File No. - N° du dossier

fg340EP777-133648

CCC No./N° CCC - FMS No/ N° VME

ADDENDUM N° 1

79 Sparks Street Base Building Upgrades
Project No. R.061273.001

Page 1 of 2
DATE: May 07, 2013

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents.

SPECIFICATIONS:

- .1 DELETE** Project No. R.011954.101 and **ADD** new PWGSC Project No. R.061273.001.
- .2 Section 01 00 10**
 - .1 ADD** new Item 1.19.2 to read:
 - .2 Access through the archway adjacent to the new door opening at the north side of the space is to be maintained at all times. It is not permitted to impede the exit with scaffolding and equipment.
 - .2 ADD** new Item 1.19.3 to read:
 - .3 Access through the west door is prohibited, door to be used as an emergency exit only.
 - .3 ADD** new Item 1.26 to read:
 - 1.26 DUST CONTROL AND TEMPORARY CONSTRUCTION ENCLOSURE**
 - .1 Provide dust tight screens or partitions to localize dust generating activities, and for protection of workers, finished areas of work.
 - .2 Completely enclose limits of site with temporary dust and vision proof construction enclosure constructed using 16 mm cement board, 0.15mm polyethylene sheet on 92 mm steel studs spaced at 600 mm on center. Temporary construction enclosures are to be constructed from floor to underside of concrete slab above, completely closing off the ceiling plenum.
 - .3 Do not fasten into existing surfaces to remain. At completion of work remove enclosures, vacuum and clean, reinstate all surfaces to the approval of the Departmental Representative.
 - .4 Maintain and relocate protection for phasing until such work is complete.
 - .4 ADD** new Item 1.27 to read:
 - 1.27 SECURITY ESCORT**
 - .1 All personnel employed on this project shall be escorted when executing work in the basement and in the exterior north courtyard.

79 Sparks Street Base Building Upgrades
Project No. R.061273.001

Page 2 of 2
DATE: May 07, 2013

- .2 Submit an escort request to Departmental Representative at least 5 working days before the service is needed. For requests submitted within the time mentioned above, the costs of the security escort will be paid for by the Departmental Representative. The cost incurred by a late request will be charged to the Contractor.
- .3 Any escort request may be cancelled free of charge if notification of cancellation is given at least the day before the scheduled time of the escort before 13:30. The cost incurred by a late cancellation will be charged to the Contractor.
- .4 The calculation of costs will be based on the average hourly rate of a security officer for a minimum of eight hours per day for a late service request and of four hours for late cancellations.

.3 Section 08 71 10

.1 DELETE Item 2.2.3 and **ADD** new Item 2.2.3 to read:

- .3 Mortise locks and latches: to ANSI/BHMA A156.13.
 - .1 Series 1000 mortised lock, grade 1, designed for function.
 - .2 Lever handles: round tubular design complete with return to door.
 - .3 Roses: round plain design.
 - .4 Locks to be supplied complete with keyed cylinder and keyed as directed.
 - .5 Normal strikes: box type, lip projection not beyond jamb.
 - .6 Finish: as noted in the Hardware Schedule.

.2 DELETE Item 2.2.8 and **ADD** new Item 2.2.8 to read:

- .8 High Security Cylinders to ANSI/BHMA A156.30 and ANSI/BHMA A156.5, for installation in all locksets, deadlocks and exit devices unless specified otherwise in the attached schedule. All keyed cylinders are to be compatible with the existing high security cylinders in the building and are to be keyed into an existing master key system

DRAWINGS:

- .1 DELETE** Project No. R.011954.101 and **ADD** new PWGSC Project No. R.061273.001.