

PROJECT:

Public Works and Government Services Canada – Lead Decontamination Project at the RCMP Calgary Post Garage; 920 – 16 Avenue NE, Calgary, Alberta.

SCOPE OF WORK

Rooms 101 and 103

1. Prior to the commencement of lead abatement activities, remove and dispose of any and all ceiling tiles, ceiling tile grid, lighting fixtures and ventilation duct work from the Rooms as lead-containing waste, as necessary.
2. All surfaces inside Rooms 101 and 103 including concrete floors, drywall wall surfaces, cinder block walls, steel I-beams and concrete ceiling decks will be cleaned by HEPA vacuuming of all surfaces, washing of all surfaces with a lead-specific cleaning agent, and rinsing of all surfaces with clean water. Any cleaning agent or water remaining in the area following cleaning activities will be HEPA-vacuumed and disposed of as lead waste. Ductwork in Rooms 101 and 103 will be removed and disposed of as lead-containing waste.
3. Seal exposed concrete surfaces using concrete sealant in accordance with manufacturer's instructions.

COMPLETION DATES

The work must be coordinated with the Building Owner and Departmental Representative. The work is scheduled to start once the building is vacated and unoccupied, currently slated for February 1, 2013.

END OF SECTION