

**RETURN BIDS TO:**  
**RETOURNER LES SOUMISSIONS À:**  
**Public Works Government Services Canada- Bid**  
**Receiving / Réception des soumissions**  
**189 Prince William Street**  
**Room 421**  
**Saint John**  
**New Brunswick**  
**E2L 2B9**

**SOLICITATION AMENDMENT**  
**MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

**Comments - Commentaires**

**Vendor/Firm Name and Address**  
**Raison sociale et adresse du**  
**fournisseur/de l'entrepreneur**

**Issuing Office - Bureau de distribution**  
**Public Works Government Services Canada- Bid**  
**Receiving / Réception des soumissions**  
**189 Prince William Street**  
**Room 421**  
**Saint John**  
**New Bruns**  
**E2L 2B9**

<b>Title - Sujet</b> 50 Bed Living Unit, Westmorland Ins	
<b>Solicitation No. - N° de l'invitation</b> EC016-130878/A	<b>Amendment No. - N° modif.</b> 016
<b>Client Reference No. - N° de référence du client</b> R.043929.001	<b>Date</b> 2012-09-14
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWB-020-3101	
<b>File No. - N° de dossier</b> PWB-2-35024 (020)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2012-09-19</b>	<b>Time Zone</b> <b>Fuseau horaire</b> Atlantic Daylight Saving Time ADT
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Donovan, Janine PWB	<b>Buyer Id - Id de l'acheteur</b> pwb020
<b>Telephone No. - N° de téléphone</b> (506) 636-5347 ( )	<b>FAX No. - N° de FAX</b> (506) 636-4376
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b>	

**Instructions: See Herein**

**Instructions: Voir aux présentes**

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

This Tender Amendment Number 16 is raised to include the following **Addendum No. 16.**

The following Addendum to the tender documents is effective immediately. This Addendum shall form part of the contract documents.

**All other terms and conditions remain the same.**

## **Addendum No. 16**

### **1. QUESTIONS AND ANSWERS**

**Q1:** Section 01 50 00 Temporary Facilities and amendment #5 states “provide temporary fence to enclose the construction area of work site”. Does the construction area just include a fence around the new building or is the access road from the entrance off the main road of the institution to the new building location also to be fenced? If this access road is to be fenced, can you please provide information on the length and layout of the access road.

**A1:** Construction area of work site is self-explanatory: The area of the site on which construction is going to take place. There is no requirement to fence off the full length of the access roadway.

**Q2:** In details 5, 8, 11 & 12/A-306, there are no anchor bolts shown to fasten the wall sill plate to the foundation. Please provide anchoring method and details for size & quantity of anchors (as per addendum #13 no explosive cartridge tools are permitted on site).

**A2:** Any anchors will have to be drilled or cast-in, not shot-fired.

**Q3:** On floor plan A-400.1, Wall Type P3 against the foundations wall and detail 4/A-310 indicates the drywall & vapor barrier wrap continuously around the corner (Grid 5-U & 21-N). There is no indication the same is true at pilasters on Grid 5-Q, 5-T, 5-U, 7-U, 10-U, 13-U, 14-U, 20-U, 21-T, 21-R, 21-N. Please provide details of how Wall Type P3 is constructed at the pilasters.

**A3:** Vapour barrier is continuous across front face of pilasters throughout. Normal building Best Practice should be followed

**Q4:** Partition P1.4 & P2.4 are to have plywood sheathing on the washroom side of walls. Washroom #105, 106, 204, 205 & Urineanalysis #117 do not have those wall types, however, they still have WR Accessories to be mounted on the walls. Please clarify if these washrooms are to have 2440mm height plywood backing.

**A4:** Only inmate washrooms to have continuous plywood. Other washrooms will have localized blocking to support accessories.

---

**Q5:** Re drawing # A-008 - per Answer 27 in Amendment #13 there is no such drawing, however in the tender documents we received it certainly exists and is titled "Floor and Wall Finishes Legend", which agrees with the list of drawings on the cover sheet.

**A5:** Our mistake. The drawings were re-numbered shortly before they went out to tender. Drawing A-008 is the correct reference and it does exist.

## **2. SPECIFICATIONS**

### **.1 Reference Specification Section 09 65 19 Resilient Flooring**

**1. Amend Specification Paragraph 2.1.1 to read:  
Resilient vinyl Tile to ASTM F1066, Class 2, smooth surface, through  
pattern. 3.2mm Thickness**