

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Public Works Government Services Canada- Bid
Receiving / Réception des soumissions
189 Prince William Street
Room 421
Saint John
New Brunswick
E2L 2B9

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works Government Services Canada- Bid
Receiving / Réception des soumissions
189 Prince William Street
Room 421
Saint John
New Bruns
E2L 2B9

Title - Sujet Structural Investigation Saint John		
Solicitation No. - N° de l'invitation E0227-132610/A		Amendment No. - N° modif. 002
Client Reference No. - N° de référence du client R.052150.001		Date 2013-01-07
GETS Reference No. - N° de référence de SEAG PW-\$PWB-004-3184		
File No. - N° de dossier PWB-2-35121 (004)	CCC No./N° CCC - FMS No./N° VME	
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2013-01-10		Time Zone Fuseau horaire Atlantic Standard Time AST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/>		
Address Enquiries to: - Adresser toutes questions à: Doucet, Gisele PWB		Buyer Id - Id de l'acheteur pwb004
Telephone No. - N° de téléphone (506) 636-4541 ()		FAX No. - N° de FAX (506) 636-4376
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:		

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This Tender Amendment No. Two (2) is raised to include the following revisions.

The following Addendum to the tender is effective immediately. This addendum shall form part of the contract documents.

All other terms and conditions remain the same.

Addendum No. 2.

ARCHITECTURAL ADDENDUM

ARCHITECTURAL SPECIFICATIONS:

1.1 SECTION 01 50 00 – TEMPORARY FACILITIES

- .1 Clarification: 1.9 – Power: Power supply may be available through arrangement with the Departmental Representative and through coordination with the Building Operators. Power supply may be available via the penthouse.
- .2 Clarification: 1.11 – Scaffolding: If the scaffolding is supported by the canopy, adequacy to be confirmed by Contractor's scaffolding design engineer, or shored from below.

ARCHITECTURAL DRAWINGS:

2.1 DRAWING A0 – KEY PLAN, SITE PLAN, DETAILS, NOTES AND LEGEND:

- .1 Clarification: 2/A0 - Site Plan: Change "Contractors Protected Area of Operations" from east side of Customs Building Parking Lot shown dashed to North / West corner of parking lot adjacent to existing planters, between the loading dock area and the Water Street sidewalk as designated by Departmental Representative.
- .2 Clarification: The Customs Building Parking Lot is required for "Off-Hours" use by Tenants. A portion(s) of the parking lot area may be made available for Contractors use during "Off-Hours" use only by prior arrangement with Departmental Representative.

STRUCTURAL ADDENDUM

STRUCTURAL DRAWINGS:

3.1 DRAWING S1 – ELEVATIONS:

- .1 Clarification: No Work is required on the East Elevation.

3.2 DRAWING S3 – SANDSTONE CLADDING ANCHOR DETAILS:

- .1 Clarification: Details 4, 5, 6 & 7/S3 show existing conditions and are included to show Work required for disassembly and re-instatement of salvaged materials to match existing conditions as shown.

- .2 Clarification: The intent is to salvage and reuse the existing connector plates and pins. Reinstallation of salvaged connectors to be inspected and approved by Departmental Representative prior to re-installation. Note: all existing connectors and pins are stainless steel as indicated.
- .3 Clarification: There is no requirement within the intended scope of Work to remove existing brick back-up masonry.
- .4 Clarification: Detail 7/S3 - delete the words "new parging" and replace with "existing parging". The intent is that the existing parging is to remain in place.

3.3 **DRAWING S4 – SANDSTONE CLADDING ANCHOR DETAILS:**

- .1 Clarification: Details 1 - 10/S4 show existing conditions and are included to show Work required for disassembly and re-instatement of salvaged materials to match existing conditions as shown.
- .2 Clarification: The intent is to salvage and reuse the existing connector plates and pins. Reinstallation of salvaged connectors to be inspected and approved by Departmental Representative.
- .3 Clarification: There is no requirement within the intended scope of Work to remove existing brick back-up masonry.
- .4 Clarification: Details 1 & 3/S4 – Existing stone veneer cladding thickness varies significantly, approximate thickness as indicated 127 mm +/-