

The following changes to the tender documents are effective immediately and will form part of the contract documents:

SPECIFICATION

- 1) Section 01 11 00 – Page 5 of 10, Item 1.9.1.12

Add: “Rip Rap installed in the drainage swale shall be OPSS 1004 R-10 Rip Rap or equivalent.

Low Permeability Earth to be used along the upper reach portion of the swale (i.e. portion of swale located on top of former landfill) shall consist of silty clay fill from on site. Silty clay shall have more than 50 percent of particles between 5 and 75 micrometres in size, and shall be free of organic and foreign material, such as wood, cobbles, boulders, concrete, brick, plastic, wire, etc. The Low Permeability Earth material along the swales shall have a thickness of not less than 0.5 metres, and shall be compacted in maximum 250 millimetre thick lifts to at least 95 percent of the standard Proctor dry density value. The low permeability earth shall be placed on Terrafix 400R non-woven geotextile or equivalent lining the base of the swale.”

- 2) Section 01 32 16 – Page 1 of 4, Part 1, Item .1

Delete: “...project works as described herein must be completed by October 31, 2012”.

Add: “...project works as described herein must be completed by December 7, 2012”

- END -