

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Public Works Government Services Canada- Bid
Receiving / Réception des soumissions
189 Prince William Street
Room 421
Saint John
New Brunswick
E2L 2B9

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works Government Services Canada- Bid
Receiving / Réception des soumissions
189 Prince William Street
Room 421
Saint John
New Bruns
E2L 2B9

Title - Sujet Parking Lot Exp, Springhill Ins.,NS	
Solicitation No. - N° de l'invitation EC016-130608/A	Amendment No. - N° modif. 006
Client Reference No. - N° de référence du client R.043943.001	Date 2012-07-09
GETS Reference No. - N° de référence de SEAG PW-\$PWB-007-3088	
File No. - N° de dossier PWB-2-35019 (007)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2012-07-12	Time Zone Fuseau horaire Atlantic Daylight Saving Time ADT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Ellis-Herring , Alison PWB	Buyer Id - Id de l'acheteur pwb007
Telephone No. - N° de téléphone (506) 636-3908 ()	FAX No. - N° de FAX (506) 636-4376
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This Solicitation Amendment Six (6) is raised to include the following addendum.

The following addendum to the tender documents is effective immediately. This addendum shall form part of the contract documents.

All other terms and conditions remain the same.

Addendum No. 6.

1. BID AND ACCEPTANCE FORM - APPENDIX 1 COMBINED PRICE FORM

REMOVE Appendix 1 Combined Price Form in its entirety and **REPLACE WITH** attached Revised Appendix 1 Combined Price Form dated July 9, 2012.

2. SPECIFICATION

REMOVE Specification Section 01 22 16 **and replace with** attached revised Specification Section 01 22 16 dated July 9, 2012.

3. QUESTIONS AND ANSWERS

Q1. Is it possible to obtain the CAD file to assist with quantity takeoffs?

A1. No, not for bidding purposes.

Q2. Please clarify which pages and/or documents are to be submitted with our bid.

A2. Refer to GI20 of R2710T of the General Instructions to Bidders which reads:

GI02 (2011-05-16) Completion of Bid

1. The bid shall be

- a. submitted on the Bid and Acceptance Form provided through the Government Electronic Tendering Service (GETS) or on a clear and legible reproduced copy of such Bid and Acceptance Form that must be identical in content and format to the Bid and Acceptance Form provided through GETS;
- b. based on the Bid Documents listed in the Special Instructions to Bidders;
- c. correctly completed in all respects;
- d. signed by a duly authorized representative of the Bidder; and
- e. accompanied by
 - i. bid security as specified in GI09; and

-
- ii. any other document or documents specified elsewhere in the solicitation where it is stipulated that said documents are to accompany the bid.
2. Subject to paragraph 6) of GI12, any alteration to the pre-printed or pre-typed sections of the Bid and Acceptance Form, or any condition or qualification placed upon the bid shall be cause for disqualification. Alterations, corrections, changes or erasures made to statements or figures entered on the Bid and Acceptance Form by the Bidder shall be initialed by the person or persons signing the bid. Initials shall be original(s). Alterations, corrections, changes or erasures that are not initialed shall be deemed void and without effect.
3. Unless otherwise noted elsewhere in the Bid Documents, facsimile copies of bids are not acceptable.
- Q3. Please clarify the method of measurement for item 24 - Pavement Markings (Please note that the numbering used for Section 01 22 16 - Measurement and Payment does not match that of the unit price table).
- A3. Pavement markings are by square meter. Numbering has been corrected in attached Revised Section 01 22 16 and attached Revised Unit Price Table date July 9, 2012.
- Q4. Pay item 4.2 states 400mm PVC storm pipe but the drawings indicate 375mm dia. PVC DR35 pipe is available in 375mm dia. but not 400mm. Is it safe to assume pay item 4.2 should read "Storm Pipe 375mm dia. PVC"?
- A4. Refer to item 3.2 (previously item 4.2) of attached revised Combined Price Form which now reads 375 mm dia. PVC.
- Q5. Pay item 7 has a quantity of 90 lineal meters for catch basin pipe but it appears there is only 65 lineal meters on the drawings. Where is the other 25 meters?
- A5. Refer to item 6 (previously item 7) of attached revised Combined Price Form. Quantity is now 70 lineal meters.
- Q6. Pay item 9 has a quantity of 4 precast concrete headwalls but pay item 10 has 7 new metal grates. Are 3 of these to be installed on existing headwalls?
- A6. There are 4 metal grates to be installed on the new precast headwalls and 3 metal grates to be installed on existing headwalls.

-
- Q7. Estimated quantity for culverts (pay item 8) is 53 lineal meters but I could only find 39 meters on the drawings - one which discharges from CBMH-1 and one at approx. STA 0+350 of the new PID road. Is there another culvert somewhere else?
- A7. Refer to item 7 (previously item 8) of attached revised Combined Price Form. Quantity is now 45 lineal meters.
- Q8. I would like to submit the following light fixture and pole information for approval.
Light fixture P1 and P2 :

Lumec lighting, Roadstar series cat. number GPLM-180W-98LED-4K-ESLE4

Pole standard for light fixtures P1 and P2 :
USS Pole manufacturing cat. no. USS-60C30ABSQ-COLOR
- Q9. Can we use the side entrance off of Herrett St. to access the site and to import / export material?
- A9. No, the Herritt Entrance will not be available for this project.
- Q10. Is there any disposal location on the property for the excavated material?
- A10. Clean fill will be accepted in a designated area provided that it will be levelled to match the surrounding area and ready for hydro seeding. Pavement concrete, other debris, etc., will not be allowed.
- Q11. Does the topsoil need to be stockpiled on site for reuse? Does it need to be screened?
- A11. Topsoil may be stockpiled for reuse. Screening will not be required if materials are less than 3/4".

Solicitation No. - N° de l'invitation
EC016-130608/A
Client Ref. No. - N° de réf. du client
R.043943.001

Amd. No. - N° de la modif.
006
File No. - N° du dossier
PWB-2-35019

Buyer ID - Id de l'acheteur
pwb007
CCC No./N° CCC - FMS No/ N° VME

APPENDIX 1 - COMBINED PRICE FORM (4 pages) *REVISED JULY 9, 2012*

- 1) The prices per unit shall govern in establishing the Total Extended Amount. Any arithmetical errors in this Appendix will be corrected by Canada.
- 2) Canada may reject the bid if any of the prices submitted do not reasonably reflect the cost of performing the part of the work to which that price applies.

LUMP SUM

The Lump Sum Amount designates Work to which a Lump Sum Arrangement applies.

- (a) Work included in the Lump Sum Amount represents all work not included in the unit price table.

LUMP SUM AMOUNT (LSA) Excluding GST / HST	Not applicable
---	-----------------------

UNIT PRICE TABLE

The Unit Price Table designates Work to which a Unit Price Arrangement applies.

- (a) Work included in each item is as described in the referenced specification section.
- (b) The Price per Unit shall not include any amounts for Work that is not included in that unit price Item.

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity (EQ)	Price per Unit GST/HST extra (PU)	Extended amount (EQ x PU) GST/HST extra
1.	Division 26	Electrical	Lump sum	1		
2.	31 23 33.01	Common excavation	Cubic metre	13500		
3.1	33 41 00	Storm Pipe 450mm dia. PVC	Linear metre	40		
3.2	33 41 00	Storm Pipe 375 mm dia. PVC	Linear metre	40		
3.3	33 41 00	Storm Pipe 300mm dia. PVC	Linear metre	50		
4.1	33 05 13	Catchbasin/Manholes 1200mm dia. Concrete	each	2		
4.2	33 05 13	Catchbasin/Manholes 1500mm dia. Concrete	each	3		
5.	33 05 13	Catchbasins	each	5		

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity (EQ)	Price per Unit GST/HST extra (PU)	Extended amount (EQ x PU) GST/HST extra
6.	33 41 00	Catchbasin Pipe	Linear metre	70		
7.	33 41 00	Culverts	Linear metre	45		
8.	33 05 13	Precast Concrete Headwalls	each	4		
9.	33 05 13	Metal Grating	each	7		
10.	31 37 00	Rip-Rap Mats	Square metre	180		
11.	31 32 19.01	Geotextile Fabric (at Rip-Rap Mats)	square metre	180		
12.	33 11 16	Relocate Hydrant	each	1		
13.	33 05 13	Existing Catchbasin Grade Adjustment	each	2		
14.	33 11 16	Existing Water Valve Grade Adjustment	each	6		
15.	02 41 13	Removal of Existing Concrete Pipe and Headwall	Linear metre	15		
16.	32 11 16.01	Granular Subbase Type 2	Metric tonne	15000		
17.	32 11 23	Granular Base Type 1	Metric tonne	11000		
18.	02 41 13	Concrete Curb Removal	Linear metre	200		
19.	02 41 13	Cold Milled Asphalt	Square metre	12000		
20.	32 12 16	Hot Mixed Asphalt Concrete	metric tonne	4200		
21.	32 16 15	Concrete Curb & Gutter	Linear metre	750		
22.	32 16 15	Concrete Sidewalk	square metre	800		

Solicitation No. - N° de l'invitation

EC016-130608/A

Client Ref. No. - N° de réf. du client

R.043943.001

Amd. No. - N° de la modif.

006

File No. - N° du dossier

PWB-2-35019

Buyer ID - Id de l'acheteur

pwb007

CCC No./N° CCC - FMS No/ N° VME

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity (EQ)	Price per Unit GST/HST extra (PU)	Extended amount (EQ x PU) GST/HST extra
23.	32 17 23	Pavement Markings	Square metre	1500		
24.	32 12 13.16	Tack Coat	litres	1500		
25.	31 32 19.01	Geotextile Fabric (pavement structure)	Square metre	3000		
26.	32 16 15	Concrete Bollards	each	8		
27.	32 94 21 32 92 21	Topsoil/Hydroseeding	Square metre	600		
28.	32 91 21 32 92 23	Topsoil/Sodding	Square metre	2980		
29.	32 37 00	Flagpole	each	1		
30.	32 37 00	Benches	each	4		
31.	32 37 00	Garbage Receptacle	each	1		
32.	32 37 00	Picnic Tables	each	2		
33.	32 14 13	Concrete Unit Paving	Square metre	120		
34.1	32 93 10	Shrub Planting - Spiraea Japonica "Pink Princess" 60cm HT - #2 Container	each	36		
34.2	32 93 10	Shrub Planting - Rosa Pavement "Pink" #1 Grade - #2 Container	each	16		
34.3	32 93 10	Shrub Planting - Rosa Pavement "White" #1 Grade - #2 Container	each	10		
35.1	10 14 53	Signage - Sign 1	each	8		
35.2	10 14 53	Signage - Sign 2	each	9		
35.3	10 14 53	Signage - Sign 3	each	2		
35.4	10 14 53	Signage - Sign 4	each	4		
35.5	10 14 53	Signage - Sign 5	each	3		
35.6	10 14 53	Signage - Sign 6	each	3		

Solicitation No. - N° de l'invitation

EC016-130608/A

Client Ref. No. - N° de réf. du client

R.043943.001

Amd. No. - N° de la modif.

006

File No. - N° du dossier

PWB-2-35019

Buyer ID - Id de l'acheteur

pwb007

CCC No./N° CCC - FMS No/ N° VME

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity (EQ)	Price per Unit GST/HST extra (PU)	Extended amount (EQ x PU) GST/HST extra
35.7	10 14 53	Signage - Sign 7	each	1		
35.8	10 14 53	Signage - Sign 8	each	1		
35.9	10 14 53	Signage - Sign 9	each	1		
35.10	10 14 53	Signage - Sign 10	each	8		
35.11	10 14 53	Signage - Sign 11	each	4		
36.1	10 14 53	Signage Removals - Single Support	each	10		
36.2	10 14 53	Signage Removals - Double Support	each	3		
TOTAL EXTENDED AMOUNT (TEA) Excluding GST / HST						

TOTAL BID AMOUNT

TOTAL BID AMOUNT (LSA +TEA) Excluding GST / HST	
---	--

PWGSC
Parking Expansion
Springhill Institution, NS
Proj. # R.043943.002

MEASUREMENT FOR PAYMENT

Section 01 22 16
Page 1
January 2012

PART 1 - GENERAL

1.1 GENERAL

- .1 Unit prices and Lump Sum prices bid are full compensation for the work necessary to complete each item in the Contract in the Form of Tender. The prices bid are complete and separate from other or related bid items.
- .2 The numbers of the items described below correspond to the numbers of the items in the Tender Form.
- .3 Additional instructions for measurement and/or payment for items of the Work may be contained in specific conditions of the Technical Specifications. In the case of a conflict between the instructions for measurement and payment contained in this specification section (01 22 16) and another section of the specifications, the requirements of this section (01 22 16) shall govern.
- .4 There will be no separate measurement for payment for Mobilization and Demobilization.
 - .1 Mobilization consists of the supply and transport of labour, equipment and material to and from the project site, establishing site field offices and all temporary facilities, security, securing all necessary regulatory permits, insurance and bonding, establishing health and safety protocol, establishing site survey control, construction and maintenance of site access roads and all necessary temporary roads, and cleaning of roads where required. Demobilization includes removal of all Contractor's labour, temporary works including temporary facilities, site field offices, temporary foundations, access roads, ramps, utilities and services upon completion of the Work. It also includes restoration of Fill placement areas and all other Site areas disturbed as a result of the construction, general clean-up and removal of rubbish / garbage.
- .5 There will be no separate measurement for payment for erosion and sediment control.
 - .1 This item includes all costs associated to complete the Environmental Protection Plan (EPP), and Erosion and Sediment Control Plan, to provide proper erosion and sediment

PWGSC
 Parking Expansion
 Springhill Institution, NS
 Proj. # R.043943.002

MEASUREMENT FOR PAYMENT

Section 01 22 16
 Page 2

January 2012

- 1.1 GENERAL .5 (Cont'd)
 (Cont'd) .1 (Cont'd)
 control, and to meet the specifications and
 applicable regulations.

- 1.2 LUMP SUM PRICES .1 The tendered prices for the lump sum work
 items are listed below. Price includes all
 labour, materials and equipment for complete
 supply and installation of the work.

ELECTRICAL

- .2 New parking lot lighting including supply and
 installation of light standards and bases,
 concrete encased ducts including excavation,
 trenching, bedding and backfilling, cabling,
 connection at Bldg. 1 and removal of existing
 light standard and reinforced concrete base.

1.3 UNIT PRICES

- .1 The tendered prices for the unit price work
 items are listed hereunder. Prices include all
 labour, materials and equipment for complete
 supply and installation of the work.

EARTHWORK

- .2 **Common Excavation**
 .1 Unit of Measurement: cubic metre (c.m.)
 .2 Method of Measurement: Departmental
 Representative will take initial cross
 sections before grubbing and stripping
 completed and immediately prior to excavation
 of material to be incorporated into work.
 .3 Item Includes: stripping, clearing and
 grubbing, stockpiling backfill material and
 disposal of excavated material offsite.

STORM SYSTEM

- .3 **Storm Pipe**
 .1 Unit of Measurement: linear metre (l.m.)
 .2 Method of Measurement: along centreline
 of pipe through catchbasins/manholes.
 .3 Item Includes: supply and placement of
 specified pipe along with all fittings,
 excavation and backfilling, granular bedding
 and surround, and testing.

1.2 LUMP SUM PRICES .4
(Cont'd)

Catchbasin/Manholes

- .1 Unit of Measurement: each
- .2 Item Includes: supply and placement of specified catchbasin/manhole, frame and grating, sump, grade adjustment, bedding, excavation and backfilling, and testing.

.5 Catchbasins

- .1 Unit of Measurement: each
- .2 Item Includes: supply and placement of specified catchbasin, frame and grating, grade adjustment, bedding, excavation and backfilling, and testing.

.6 Catchbasin Pipe

- .1 Unit of Measurement: linear metre (l.m.)
- .2 Method of Measurement: slope distance along the centreline of the pipe through catchbasins.
- .3 Item Includes: supply and placement of pipe and gaskets, granular bedding and surround, excavation and backfilling and connection to catchbasin/manholes and pipe and testing.

.7 Culverts

- .1 Unit of Measurement: linear metre (l.m.)
- .2 Method of Measurement: slope distance along the centreline of the pipe.
- .3 Item Includes: supply and placement of the specified pipe and gaskets including, excavation and backfilling, granular bedding and surround, and testing.

.8 Precast Concrete Headwalls

- .1 Unit of Measurement: each
- .2 Item Includes: supply and placement of precast concrete headwalls including connection to culverts and granular bedding.

.9 Metal Grating

- .1 Unit of Measurement: each
- .2 Item Includes: supply and placement of galvanized metal grating system at inlet and outlet storm culverts including anchoring the grate to headwalls.

.10 Rip-Rap Mats

- .1 Unit of Measurement: square metres (s.m.)
- .2 Method of Measurement: slope area of rip-rap rock mat to specified thickness.

PWGSC
Parking Expansion
Springhill Institution, NS
Proj. # R.043943.002

MEASUREMENT FOR PAYMENT

Section 01 22 16
Page 4

January 2012

1.2 LUMP SUM PRICES .10
(Cont'd)

(Cont'd)

.3 Item Includes: supply and placement of rip-rap rock at inlet and outlets to the storm systems.

.11 Geotextile Fabric (at Rip-Rap Mats)

.1 Unit of Measurement: square metres (s.m.)

.2 Method of Measurement: slope area of the geotextile placed under rip-rap mats.

.3 Item Includes: supply and placement of the specified geotextile fabric under the rip-rap mat.

.12 Relocate Hydrant

.1 Unit of Measurement: each

.2 Item Includes: removal of existing hydrant, capping the existing hydrant lead, re-installation of existing hydrant and hydrant valve, new lead, new hydrant tee and thrust blocks for cap, tee and hydrant, bedding and backfilling, and swabbing the new and relocated pieces with chlorine.

.13 Existing Catchbasin Grade Adjustment

.1 Unit of Measurement: each

.2 Item Includes: removal of the existing catchbasin frame, grating and grade adjustment, forming the frame for the new cast-in-place grade adjustment to the new height.

.14 Existing Water Valve Grade Adjustment

.1 Unit of Measurement: each

.2 Item Includes: grade adjustment to the new height.

.15 Removal of existing concrete pipe and headwalls

.1 Unit of Measurement: linear meter (l.m.)

.2 Item Includes: removal and disposal of various size concrete pipe and headwall.

PARKING LOT CONSTRUCTION

.16 Granular Subbase Type 2

.1 Unit of Measurement: metric tonne (m.t.)

.2 Method of Measurement: scale tickets signed by the Departmental Representative.

.3 Item Includes: supply, placement and compaction of gravel as indicated.

PWGSC
 Parking Expansion
 Springhill Institution, NS
 Proj. # R.043943.002

MEASUREMENT FOR PAYMENT

Section 01 22 16
 Page 5

January 2012

1.2 LUMP SUM PRICES .17
 (Cont'd)

Granular Base Type 1

- .1 Unit of Measurement: metric tonne (m.t.)
- .2 Method of Measurement: scale tickets signed by the Departmental Representative.
- .3 Item Includes: supply, placement and compaction of gravel as indicated.

.18 Concrete Curb Removal

- .1 Unit of Measurement: linear metre (l.m.)
- .2 Method of Measurement:
- .3 Item Includes: removal and disposal of existing concrete curbs as indicated.

.19 Cold Milled Asphalt

- .1 Unit of Measurement: square metre (s.m.)
- .2 Method of Measurement: slope measure of indicated area at specified depth.
- .3 Item Includes: removal and salvage, stockpiling, disposal as indicated.

.20 Hot Mix Asphalt Concrete

- .1 Unit of Measurement: metric tonne (m.t.)
- .2 Method of Measurement: scale tickets signed by the Departmental Representative.
- .3 Item Includes: supply, placement and compaction as indicated.

.21 Concrete Curb and Gutter

- .1 Unit of Measurement: linear metre (l.m.)
- .2 Method of Measurement: slope measure.
- .3 Item Includes: supply and placement of concrete, formwork, and backfill as indicated.

.22 Concrete Sidewalk

- .1 Unit of Measurement: square metre (s.m.)
- .2 Method of Measurement: slope measure.
- .3 Item Includes: sidewalk, including supply and placement of concrete, formwork and reinforcement and backfill as indicated.

.23 Pavement Markings

- .1 Unit of Measurement: square metre (s.m.)
- .2 Method of Measurement:
- .3 Item Includes: layout of pavement markings, supply and placement of markings and protection until dry.

.24 Tack Coat

- .1 Unit of Measurement: litres (l)
- .2 Method of Measurement: measured in litres at 15 degrees C of emulsified asphalt actually applied
- .3 Item Includes: supply and placement of tack coat.

PWGSC
Parking Expansion
Springhill Institution, NS
Proj. # R.043943.002

MEASUREMENT FOR PAYMENT

Section 01 22 16
Page 6

January 2012

- 1.2 LUMP SUM PRICES .25 **Geotextile Fabric (at new pavement structure)**
(Cont'd)
- .1 Unit of Measurement: square metre (s.m.)
 - .2 Method of Measurement: slope area of the geotextile placed under new pavement structure.
 - .3 Item Includes: supply and placement of the specified geotextile fabric under new pavement structure.

- .26 **Concrete Bollards**
- .1 Unit of Measurement: each
 - .2 Method of Measurement: units complete
 - .3 Item Includes: excavation, backfill, supply and placement of concrete and steel tube.

LANDSCAPING

- .27 **Topsoil/Hydroseeding**
- .1 Measurement for payment shall be the number of square metres (s.m.) of material acceptably supplied in accordance with the specifications. Measurement will be along the actual surface for a true measure of the surface area.
 - .2 Payment for topsoil/hydroseeding shall be made at the tendered applicable unit price for the unit of measure stated in the Bid Form and shall include: all costs for execution of the work including: supply, delivery, placing of topsoil/hydraulic seeding.

- .28 **Topsoil/Sodding**
- .1 Measurement for payment shall be the number of square metres (s.m.) of material acceptably supplied in accordance with the specifications. Measurement will be along the actual surface for a true measure of the surface area.
 - .2 Payment for topsoil/sodding shall be made at the tendered applicable unit price for the unit of measure stated in the Bid Form and shall include: all costs for execution of the work including: supply, delivery, placement of topsoil/sodding.

- .29 **Flagpole**
- .1 Measurement for payment shall be the lump sum price for supply and installation of the flagpole and concrete base in accordance with the drawings and specification and removal and disposal of existing flagpole and concrete base.

PWGSC
Parking Expansion
Springhill Institution, NS
Proj. # R.043943.002

MEASUREMENT FOR PAYMENT

Section 01 22 16
Page 7

January 2012

1.2 LUMP SUM PRICES .29
(Cont'd)

(Cont'd)

.2 Payment for flagpole supply/installation and removal shall be made at the tendered applicable unit price and shall include all costs for the supply and install of the flagpole and new concrete base in accordance with the specifications and to the limits shown on the drawings.

.30 Benches

.1 Measurement for payment shall be the number of benches supplied/installed in accordance with the drawings.

.2 Payment for bench installation shall be made at the tendered applicable unit price and shall include all costs for the supply/install of benches on new concrete bases in accordance with the specifications and to the limits shown on the drawings.

.31 Garbage Receptacle

.1 Measurement for payment shall be the number of garbage receptacles supplied/installed in accordance with the drawings.

.2 Payment for garbage receptacle supply/installation shall be made at the tendered applicable unit price and shall include all costs for the supply/install of garbage receptacles on new concrete bases in accordance with the specifications and to the limits shown on the drawings.

.32 Picnic Tables

.1 Measurement for payment shall be the number of picnic tables supplied/installed in accordance with the drawings.

.2 Payment for picnic table supply/installation shall be made at the tendered applicable unit price and shall include all costs for the supply/install of picnic tables and new concrete anchor bases in accordance with the specifications and to the limits shown on the drawings.

.33 Concrete Unit Paving

.1 Measurement for payment shall be the number of square metres (s.m.) of material acceptably supplied, placed and compacted in accordance with the specifications.

.2 Payment for shall be made at the tendered applicable unit price for the unit of measure stated in the Bid Form and shall include: all costs for execution of the work

PWGSC
Parking Expansion
Springhill Institution, NS
Proj. # R.043943.002

MEASUREMENT FOR PAYMENT

Revised July 9, 2012

Section 01 22 16
Page 8

January 2012

1.2 LUMP SUM PRICES .33
(Cont'd)

(Cont'd)

.2 (Cont'd)

including: supply, delivery, placing and compaction of granular base and concrete unit paving and edging; in accordance with the specifications and to the limits shown on the drawings.

.34 Shrub Planting

.1 Measurement for payment shall be per unit price supplied and installed in accordance with the drawings.

.2 Payment for tree/shrub/perennial planting supply/installation shall be made at the tendered applicable unit price and shall include all costs for the supply and install of shrubs including excavation, plant material, mulch, support and site reinstatement in accordance with the specifications and to the limits shown on the drawings.

SIGNAGE

.35 Signage

.1 Measurement for supply, installation and painting of signboards and sign supports will be based on each complete sign installation.

.36 Signage Removals

.1 Measurement for supply, installation and painting of signboards and sign supports will be based on each complete sign installation. Removal of existing signs will be based on each complete sign installation.

PART 2 - PRODUCTS

2.1 NOT USED .1 Not Used.

Revised July 9, 2012

PWGSC
Parking Expansion
Springhill Institution, NS
Proj. # R.043943.002

MEASUREMENT FOR PAYMENT

Section 01 22 16
Page 9

January 2012

PART 3 - EXECUTION

3.1 NOT USED .1 Not Used.

END