

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving Public Works & Government Services
Canada/Réception des soumissions Travaux publics et
Services gouvernementaux Canada
1713 Bedford Row
Halifax, N.S./Halifax,(N.E.)
B3J 1T3
Halifax
Bid Fax: (902) 496-5016

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Real Property Contracting
1713 Bedford Row
P.O. Box 2247/C.P.2247
Halifax, N.S./Halifax, (N.E.)
B3J 3C9
Halifax

Title - Sujet KENTVILLE RAVINE BRIDGE #2 REMOVAL	
Solicitation No. - N° de l'invitation E0225-131175/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client 20131175	Date 2012-08-13
GETS Reference No. - N° de référence de SEAG PW-\$PWA-122-4906	
File No. - N° de dossier PWA-2-68048 (122)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2012-08-22	Time Zone Fuseau horaire Atlantic Daylight Saving Time ADT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Chinye, Chukwudi	Buyer Id - Id de l'acheteur pwa122
Telephone No. - N° de téléphone (902) 496-5476 ()	FAX No. - N° de FAX (902) 496-5016
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Due to the technical nature of the following changes, amendment 001 will be available in English only
Amendment 001 is raised to incorporate the following changes:

1. Re-numbering of the following clauses:

OLD	NEW
Section 01 10 10, Page 6	Section 01 10 10, Page 6
Clause 1.3 CODES AND STANDARDS	Clause 1.4 CODES AND STANDARDS
Clause 1.4 INTERPRETATION OF DOCUMENTS	Clause 1.5 INTERPRETATION OF DOCUMENTS
Clause 1.5 TERM ENGINEER	Clause 1.6 TERM ENGINEER
Clause 1.6 SETTING OUT WORK	Clause 1.7 SETTING OUT WORK
Section 01 10 10, Page 7	Section 01 10 10, Page 7
Clause 1.7 COST BREAKDOWN	Clause 1.8 COST BREAKDOWN
Clause 1.8 DOCUMENTS REQUIRED	Clause 1.9 DOCUMENTS REQUIRED

2. In Section 01 10 10, delete Clause 1.1.1.2 and replace with the following.

1.1.1.2 Develop and submit a detailed demolition plan stamped by a Professional Engineer, which shall detail, as example, the suitable equipment and method of demolition of the bridge, the means to access the work site, and means to move the material on and from site, as well as any other requirements set in these specifications and drawings and elsewhere in the Contract Documents.

3. In Section 01 10 10, addition of sub-clauses 1.1.1.2.1 to 1.1.1.2.6

1.1.1.2.1 The Contractor is responsible to take all necessary precautions to ensure safe passage of the Contractor's equipment, material and personnel across the stream.

1.1.1.2.2 The Contractor is responsible to ensure that no damage will be done to the existing Ravine trail access bridges (with the exclusion of Bridge No.2, which is being removed as part of Contract work) during all Work activities.

1.1.1.2.3 The Contractor shall demonstrate that no materials or equipment will enter, or be placed in the stream water.

1.1.1.2.4 The Detailed Demolition Plan shall comply with all requirements set out in these specification and drawings, as well as elsewhere in the Contract Documents.

1.1.1.2.5 The load capacity of each of the five of the ravine trail bridges, shown on drawing S01, are not known.

1.1.1.2.6 If Any damage occurs to any part of the property as a result of Contractor's work, the Contractor is responsible to immediately restore such damaged areas to original or better condition, and to the satisfaction of the Departmental Representative or designate.

4. In Section 01 14 10, addition of sub-clause 1.1.2.2

1.1.2.2 The review of submitted documents by the Departmental Representative or by an authorized Consultant or designate is for sole purpose of ascertaining conformance with general concept. This review shall not mean that Canada approves the detail design inherent in the documents, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of

responsibility for errors or omissions in documents or of responsibility for meeting all requirements of the construction and Contract Documents. Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains to techniques of construction and installation and for co-ordination of Work of all sub-trades.

5. In Section 01 33 00, delete Clause 1.1 and replace with the following.

Clause 1.1 RELATED SECTIONS

- .1 Section 01 14 10 - Scheduling and Management of Work
- .2 Section 01 78 00 - Closeout submittals

6. In Section 02 41 16, delete Clause 1.3 and replace with the following

Clause 1.3 RELATED SECTIONS

- .1 Section 01 14 10 - Scheduling and Management of Work.
- .2 Section 01 33 00 - Submittal Procedures.
- .3 Section 01 35 29 - Site-Specific Health and Safety Requirements.
- .4 Section 01 35 43 - Environmental Procedures.
- .5 Section 31 23 33 - Excavating, Trenching and Backfilling.

7. In Section 02 41 16, addition of Sub-clause 1.5.2.2

1.5.2.2 The Demolition Plan is to be stamped by a Professional Engineer.

8. In Section 02 41 16, addition of Sub-clause 1.5.1.9

1.5.1.9 Methods and/ or means to ensure that no materials or equipment will enter, or be placed in the stream water.

9. In Section 02 41 16, addition of Clause 1.6.1.3 to 1.6.1.5

1.6.1.3 The load capacity of each of the five of the ravine trail bridges, shown on drawing S01, are not known. The Contractor is responsible to ensure that no damage will be done to the existing Ravine trail access bridges (with the exclusion of Bridge No.2, which is being removed as part of Contract work) during all Work activities.

1.6.1.4 If Any damage occurs to any part of the property as a result of Contractor's work, the Contractor is responsible to immediately restore such damaged areas to original or better condition, and to the satisfaction of the Departmental Representative or designate.

1.6.1.5 If Contractor fails to repair damage to the satisfaction of the Department Representative, the Department Representative may complete repairs at the Contractor's expense.

10. In Section 02 41 16, Part 3 - Execution, delete Clauses .2 and .3, and replace with the following

.2 The contractor is to adhere to the submitted Demolition Plan.

.3 Appropriate notification must be given to the Departmental Representative if any deviation is intended to be implemented to the previously submitted Demolition Plan. The proposed deviation must

be submitted to the Departmental Representative in writing; the Contractor must receive written confirmation of receipt of the same, by the Departmental Representative.

11. Delete the "Notes" on Drawing S02, and Replace with the following:

1. The Contractor shall develop and submit a detailed demolition plan stamped by a Professional Engineer, which shall detail, as example, the suitable equipment and method of demolition of the bridge, the means to access the work site, and means to move the material on and from site, as well as any other requirements set in these specifications and drawings and elsewhere in the Contract Documents.
2. The Contractor is responsible to take all necessary precautions to ensure safe passage of the Contractor's equipment, material and personnel across the stream.
3. The Contractor is responsible to ensure that no damage will be done to the existing Ravine trail access bridges (with the exclusion of Bridge No.2, which is being removed as part of Contract work) during all Work activities.
4. The Contractor shall demonstrate that no materials or equipment will enter, or be placed in the stream water.
5. The Detailed Demolition Plan shall comply with all requirements set out in these specification and drawings, as well as elsewhere in the Contract Documents.
6. The load capacity of each of the five of the ravine trail bridges, shown on drawing S01, are not known.
7. If Any damage occurs to any part of the property as a result of Contractor's work, the Contractor is responsible to immediately restore such damaged areas to original or better condition, and to the satisfaction of the Departmental Representative or designate.
8. If Contractor fails to repair damage to the satisfaction of the Department Representative, the Department Representative may complete repairs at the Contractor's expense.
9. The Contractor shall develop and submit an Environmental Protection Plan (EPP). Either as part of the EPP, or as a stand alone document, the Contractor must also submit an Erosion and Sedimentation Control Plan.

All Other Terms and Conditions Remain the Same.