

Project No.: R.050172.001

July 27, 2012

The following changes to the tender documents are effective immediately and will form part of the contract documents:

Item 1) **INSERT** the following:

Item No.	Question or Clarification	Answer
3.1	Who carries the control pricing? The General or the Mechanical contractor?	The controls pricing will be included in the Mechanical scope of work.
3.2	Re – Construction Hoarding. It says to use salvaged vinyl covered drywall but existing walls are field applied drywall? What do we use?	The contractor can utilize all salvaged drywall material whether painted or with vinyl covering for the temporary hoarding provided the material salvaged is not small pieces which cause an unsightly appearance. The contractor shall supply and install all additional material necessary for all hoarding to complete the work.
3.3	Drawing A0.2 Door Schedule – the notes refer to access controls, keypad, doorbell - who supplied & installs? Not spec'd in finish Hardware.	Reference electrical drawings – contractor shall install all rough ins noted and Client will install access controls and keypad. Doorbell to be supplied and installed by the electrical contractor. Doorbell shall be Edwards C210-W series or equal c/w transformer, white finish and one non illuminated pushbutton. Connect chime for single door operation. Confirm chime unit and pushbutton locations on site prior to installation
3.4	Is there glycol in the existing mechanical system piping?	There is no glycol in the mechanical system piping.

END OF ADDENDUM 3