

## **1. ARCHITECTURAL**

### **1.1 SPECIFICATIONS**

No items.

### **1.2 DRAWINGS**

- .1 Architectural Drawing 1/A2.01 Main Floor Dimension Plan
  - .1 Refer to drawing ASK-04 (attached)
  - .2 Delete interior screen adjacent to door #7101.
  - .3 Add partition type P8A adjacent to door #7101.
- .2 Architectural Drawing 11/A6.17 Section Details - 6
  - .1 Refer to drawing ASK-05 (attached)
  - .2 Revise corner guard note to read:  
51mm x 51mm x 1220mm stainless steel corner guard with rounded corner. Refer to specification.
- .3 Architectural Drawing 1/A0.04 Door & Frames Schedule
  - .1 Refer to drawing ASK-06 (attached)
  - .2 Delete: Frame type F2 from door #1103 & #1104.
  - .3 Add: Frame type A to door #1103 & #1104.
- .4 Reference Drawing A0.06 Materials & Room Finishes Schedule
  - .1 Refer to attached full-drawing re-issued
  - .2 Add: RS1 – Roller shade to Interior Materials Schedule:
    - Code: RS1
    - Type: Roller Shade
    - Colour: -
    - Finish: -
    - Size: Refer to specifications
    - Location: Window shade on each window
    - Remarks: -
  - .3 Add to Room Finish Schedule Window Finishes as indicated on drawing A0.06 under category Wndw: Finish.
- .5 Architectural Drawing 1/A9.01 Second Floor Furniture Plan
  - .1 Refer to drawing ASK-07 (attached)
  - .2 Room #7105: Delete workstation tag 3000-01. Add tag 7105-01.
  - .3 Room #7106: Delete workstation tag 3000-01. Add tag 7106-01.
  - .4 Room #7107: Delete workstation tag 3000-01. Add tag 7107-01.
  - .5 Room #7108: Delete workstation tag 3000-01. Add tag 7108-01.
  - .6 Room #7109: Delete workstation tag 3000-01. Add tag 7109-01.

- .7 Room #7110: Delete workstation tag 3000-01. Add tag 7110-01.
- .8 Room #7111: Delete workstation tag 3000-01. Add tag 7111-01.