	SELUX	S453–W–3M–H15–BK–RBY														SHROUD
'S'	BEACON TRAVERSE	TRVD–36G–90W–T3–347–BB								LED		●		ACCEPTABLE ALTERNATIVE	WALL MOUNTED LED FIXTURE AT APPROX. 14' AFF. BLACK FINISH REFER TO ARCHITECTURAL ELEVATIONS FOR EXACT MOUNTING HEIGHT
	WIDELITE	ASW–8015–4K–3–6–S–B													
	ACCULITE	AW2–A050–4K–E34–WT–BL													
'S1'	BEACON CRUZER	CRZ–60G–150W–T4–BS347–BB							60	LED		●		ACCEPTABLE ALTERNATIVE	POLE MOUNTED SINGLE HEAD LED FIXTURE, BLACK C/W MATCHING 4500mmH ALUMINUM POLE, 100mmDIA. STRAIGHT, ON 600DIA x450H DECORATIVE CONCRETE BASE
	WIDELITE	ASA–8015–4K–3–6–S–B							64						
	ACCULITE	AP2–90L–57K–E34–3–HT–BL							90						
'S2'	BEACON CRUZER	CRZ–2x60G–150W–T5R–347–BB							2x 60	LED		●		ACCEPTABLE ALTERNATIVE	POLE MOUNTED DOUBLE HEAD LED FIXTURE, BLACK C/W MATCHING 7600mm ALUMINUM POLE, 100mmDIA. STRAIGHT, ON 600DIA x450H DECORATIVE CONCRETE BASE
	WIDELITE	ASA–2x12817–4K–5–6–S–B							2x 128						
	ACCULITE	AP2–2x150L–57K–E34–3–HT–BL							2x 150						
'S3'	BEACON CRUZER	CRZ–60G–150W–T5R–347–BB							60	LED		●		ACCEPTABLE ALTERNATIVE	POLE MOUNTED SINGLE HEAD LED FIXTURE, BLACK C/W MATCHING 7600mm ALUMINUM POLE, 100mmDIA. STRAIGHT, ON 600DIA x450H DECORATIVE CONCRETE BASE
	WIDELITE	ASA–12817–4K–5–6–S–B							128						
	ACCULITE	AP2–150L–57K–E34–3–HT–BL							150						
'S4'	KIM	BOLLARD VSB1–LED–20L–BL							20	LED		●		ACCEPTABLE ALTERNATIVE	1092mm HIGH 200mm SQUARE BOLLARD, BLACK
	HADCO	SF8–A–KF–20–N							20						
	LEO (SALEX)	LEO 160 123242117–12490							16						

REF. DWG. NO. E8–06

DWG. NO. RE–E86–ADD2–3

ISSUED WITH ADD 002

PROJECT: NIAGARA OFFICE ADMINISTRATION FACILITY

ARCHITECT: REBANKS PEPPER LITTLEWOOD

DRAWN BY: K.S.

DATE: MAY 30, 2012

MCW Consultants Ltd.
1185 West Georgia St, Suite 1400, Vancouver, BC, V6E 4E6