

Solicitation No. - N° de l'invitation

EC015-132181/A

Client Ref. No. - N° de réf. du client

R.050327.002

Amd. No. - N° de la modif.

001

File No. - N° du dossier

PWD-2-35115

Buyer ID - Id de l'acheteur

pwd005

CCC No./N° CCC - FMS No./N° VME

## ADDENDUM #1

\*\*\*\*\*  
 THE FOLLOWING AMENDMENT TO THE BID DOCUMENTS IS EFFECTIVE IMMEDIATELY. THE ADDENDUM SHALL FORM A PART OF THE CONTRACT DOCUMENTS.  
 \*\*\*\*\*

Q1 - Drawing E-2: New steel cover for trench - advise type of steel (ex: plate, chechered. Etc.).

A1 - Use checkered plate.

Q2 - Drawing E-2: Note on detail " arrangement of new regulations" indicates "existing control cable in new 38mm RGS conduit". Please advise routing (length of run) for new conduit to control tower.

A2 - RGS conduit length is approximately 1,500 mm from Remote Control Cable Termination to the floor trench steel cover plate. The remaining existing control cable to the control tower is in the floor trench and existing duct and it does not require any conduit.

By submission of its bid, the Bidder confirms that it has read and understands the requirements expressed in all addenda and has included all costs of these requirements in its Total Bid Amount.

**All other terms & conditions remain unchanged.**

\*\*\*\*\*