

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Public Works Government Services Canada- Bid
Receiving / Réception des soumissions
189 Prince William Street
Room 421
Saint John
New Brunswick
E2L 2B9

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works Government Services Canada- Bid
Receiving / Réception des soumissions
189 Prince William Street
Room 421
Saint John
New Bruns
E2L 2B9

Title - Sujet General Purpose Bldg-N.B./N.S.	
Solicitation No. - N° de l'invitation EC016-123090/A	Amendment No. - N° modif. 019
Client Reference No. - N° de référence du client R.043958.001	Date 2012-05-25
GETS Reference No. - N° de référence de SEAG PW-\$PWB-007-3063	
File No. - N° de dossier PWB-1-34209 (007)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2012-06-05	Time Zone Fuseau horaire Atlantic Daylight Saving Time ADT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Ellis-Herring , Alison PWB	Buyer Id - Id de l'acheteur pwb007
Telephone No. - N° de téléphone (506) 636-3908 ()	FAX No. - N° de FAX (506) 636-4376
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This Solicitation Amendment Number Nineteen (19) is raised to include the following addendum.

The following Addendum to the tender documents is effective immediately. This Addendum shall form part of the contract documents.

All other terms and conditions remain the same.

Addendum No. 19

1. EXTENSION

Notice is hereby given that the time for the reception of tenders previously due May 31, 2012 is hereby extended to 14:00 hours, June 5, 2012.

2. QUESTIONS AND ANSWERS

Q1

In Amendment #004, Q14, we were to be provided the required information and scope for the EMCS. Please advise the schedule for release of this information.

A1

The TAC Vista Building Automation System is at Springhill Penitentiary and has been upgraded in the last year and has the latest version of software.

The Alerton BACTalk Building Automation System is at the Atlantic Institution has been upgraded in the last year and has the latest version of software.

Q2

We refer you to Q11-A11 of Amendment #4 whereby information was to be provided for connections to the central heating system. This information still has not been provided. Are we to assume that the heating will be 1.5 metres outside of the new building footprint and the remainder of the required installation/hookup will be performed by others or as additional work to the Contract?

A2

The work is not to be done by others. The intent of the value as set by PWGSC is that mechanical design naturally works from the inside of the building to hook ups relatively 1.5m outside the building. CIVIL design then takes lead on service connections, design. The design build team is responsible for all design and all construction.

Q3

On Page 114 of 188 of the Terms of Reference, the floor to floor travel for the Elevator is set at 3700 mm. Is this the floor to floor height required and expected by the Owner for the Project?

A3

Yes. Lower floor: 3700 mm finish floor to finish floor and Upper floor: 3700 mm finish floor to underside of lowest roof structural member.

Q4

Can we use 6 high 9 Ga. X 2 chain link construction panels for the laydown areas at both institutions as well as the work site perimeter in Renous? (Is this considered minimum/medium as we are outside the perimeter wall/fence?)

A4

This can be used at Atlantic Institution, Renous.

Q5

Clarification for the temp. fence security in Springhill or Renous - See addendum #6, item 3.3.3.5 The fence is closer than 12m in some areas please clarify.

A5

Section 3.3 does not apply for the GI projects. Only 3.2 Temporary Construction fences for Medium and Maximum institutions applies. As well as the new qualities for the fences as outlined in Addendum 015.

Q6

Are we to install rough-in (conduit) only for CCTV and security systems? Card reader at the door? Are all devices, wiring and termination by owner please confirm.

A6

See Spec and Drawings for details. Conduits to be provided as part of this contract. Devices and wiring etc. are by Owner.

Q7

Given the extensions made to the RFP, the milestone dates as detailed in the RFP are not reasonable and need to be revised. Based on a tender closing date of May 31, 2012 and subsequent award in a two or three week timeframe, the January 31st Substantial Completion date is not achievable. Annex C on page 33 of 95 of the RFP states that we are to be complete in 42 weeks which will be required to execute the design and construction of these two buildings. Please advise that Annex C is correct and the Project Milestone dates are to be revised accordingly based on the contract Award Date.

A7

Project Milestones are to be revised accordingly to the 42 week completion requirements outlined.

Q8

Is a fire pump required for the sprinkler system?

A8

This would be part of the design build requirement.

Q9 In the Terms of Reference, page 65, item 4.3.16.6 indicates a Health & Safety Coordinator to be onsite for the projects. Can this individual be our Site Superintendents at each site, or is it a requirement for another individual to the H&S Coordinator? If it has to be another individual from our Superintendent, will this person be expected to be onsite full time for the duration of the project?

A9

It is not required to be separate person.