

**RETURN BIDS TO:**  
**RETOURNER LES SOUMISSIONS À:**  
**Public Works and Government Services Canada**  
**Telus Plaza North/Plaza Telus Nord**  
**10025 Jasper Ave./10025 ave. Jaspe**  
**5th floor/5e étage**  
**Edmonton**  
**Alberta**  
**T5J 1S6**  
**Bid Fax: (780) 497-3510**

## **SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

### **Comments - Commentaires**

**Vendor/Firm Name and Address**  
**Raison sociale et adresse du**  
**fournisseur/de l'entrepreneur**

**Issuing Office - Bureau de distribution**  
**Public Works and Government Services Canada**  
**Telus Plaza North/Plaza Telus Nord**  
**10025 Jasper Ave./10025 ave. Jasper**  
**5th floor/5e étage**  
**Edmonton**  
**Alberta**  
**T5J 1S6**

<b>Title - Sujet</b> Bowden Demarcation Fence	
<b>Solicitation No. - N° de l'invitation</b> EW038-131625/A	<b>Amendment No. - N° modif.</b> 001
<b>Client Reference No. - N° de référence du client</b> EW038-131625	<b>Date</b> 2012-10-17
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWU-909-9560	
<b>File No. - N° de dossier</b> PWU-2-35244 (909)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2012-10-25</b>	<b>Time Zone</b> <b>Fuseau horaire</b> Mountain Daylight Saving Time MDT
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Mayhew (RPC), Sylvia	<b>Buyer Id - Id de l'acheteur</b> pwu909
<b>Telephone No. - N° de téléphone</b> (780) 497-3645 ( )	<b>FAX No. - N° de FAX</b> (780) 497-3510
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b>	

**Instructions: See Herein**

**Instructions: Voir aux présentes**

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

---

## ADDENDUM NUMBER ONE (1)

### 1. General

- 1.1 This Addendum is issued prior to Tender closing to identify the revisions as noted herein.
- 1.2 All such revisions will become part of the Work and the effects shall be included in the Tender Price.
- 1.3 All work shall be performed in accordance with the Contract Documents.

### 2. Drawings

- 2.1 Drawings B-C10 and B-C21: Add Sentence 10 to General Notes as follows: "Cable Tray – include the removal and replacement of the cable tray support bracket at each post that is required to be removed or repositioned as a part of this work. Cable tray is to be supported when the post is removed or repositioned, in order to protect the existing communications, fibre optic cables and 110V power lines within the tray." The present cable tray support brackets are currently welded to the fence posts at approximately 900 mm above grade, with welds approximately 125mm long.
- 2.2 Drawing B-C11, Note 12, sixth sentence: Revise the sentence to read "Install new gate. Installation to be coordinated with the Electrical sub-trade for conduit and gate operator."
- 2.3 Drawing B-C13: Replace the word "MAIN GATE" with "GATE".
- 2.4 Drawing B-C19, Detail 6: Revise the depth of the anti-tunnelling wall from 2800mm min. to 1200mm. Revise note from "300 THK anti-tunnelling wall" to "300 THK anti-tunnelling wall. Tie to existing wall."
- 2.5 Drawing EB-1, Note 4. Replace "Site Staff" with "Departmental Representative".
- 2.6 Drawing B-C22, Note 4: Revise last sentence to read "Total number of ties is estimated at 2500."
- 2.7 Drawing B-C22: Delete in entirety Notes 7, 8 and 9. Delete references to these notes on Drawings B-C25, B-C27 and B-C28 accordingly.
- 2.8 Drawing B-C23, Note 13: Revise spelling in last sentence "ADUSTIN" to "ADJUST".

---

### 3. Specifications

- 3.1 Section 03 30 00 Cast-in-Place Concrete: add sentence .3 to Article 1.04 Quality Assurance as follows: "Contractor to retrain a concrete testing agency. Concrete testing agency is to report directly to the Departmental Representative. Contractor to advise the Departmental Representative of the name and contact information of the testing agency at the Start-up Meeting."
- 3.2 Section 03 30 00 Cast-in-Place Concrete: Article 3.03, first part of sentence 2 to be revised to read "Departmental Representative may request additional test cylinders during cold weather Concreting."
- 3.3 Section 28 05 00 Electronic Safety and Security: Revise the term "Electrical Contractor" to "Electrical Sub-trade" in Article 2.01 Execution, Article 2.05 Re-Installation, and Article 2.06 Testing.
- 3.4 Section 31 23 33.01 Excavating, Trenching and Backfilling: Article 1.02 Definitions: Delete Sentence 1.1 (Excavation classes....), Sentence 1.2 (Common excavation.....) And Sentence 2 (Unclassified Excavation...)
- 3.5 Section 32 91 19.03 Topsoil Stripping, Replacement and Seeding: Delete in entirety Article 1.02 Measurement for Payment.

### End of Addendum No. 1