

INTERIOR MATERIALS SCHEDULE

INTERIOR MATERIAL NOTES

- M1. REFER TO ENLARGED FLOOR PLANS FOR LOCATIONS
- M2. REFER TO INTERIOR ELEVATIONS FOR FINISH LOCATIONS & EXTENTS
- M3. REFER TO MILLWORK DRAWINGS FOR FINISH LOCATIONS & EXTENTS
- M4. REFER TO REFLECTED CEILING PLANS FOR LOCATIONS.
- M5. REFER TO ROOM FINISH SCHEDULE FOR LOCATIONS.
- M6. TILE TO BE DOUBLE-LOADED THROUGH-BODY RECTIFIED PORCELAIN.

Material		Colour	Finish/Pattern	Size	Description	Location	Remarks
Code	Type						
ACT1	Acoustic Ceiling Tile	White	Smooth	610mm x 610mm		Work areas, offices, meeting rooms, lunch room and others	Note #M4
BB1	Bulletin Board	Beige	Textured	1220mm x 2430mm		Business Centers, Staff Areas	Note #M2
CP11	Carpet Tile	Dark Grey	Geometric	610mm x 610mm		Office areas and theater work area, meeting room, conference room	Note #M1
CP12	Carpet Tile	Dark Grey	Accent	610mm x 610mm		Accent Areas	Note #M1
EG1	Entry Grille	Grey/Black	N/A			Refer to specification Entry #7001 & Vestibule #7008	Note #M1
HC11	Homogeneous Conductive Tile	Cream		610mm x 610mm		Rooms #0119, #6107	Note #M1
LC11	Linoleum Tile	Grey / Beige		305mm x 305mm		Business Centers, others	Note #M1
ML1	Melamine	Cherry				Interiors of cabinets, coordinators with WV1 and PL1	Note #M3
ML2	Melamine	Maple				Interiors of cabinets, coordinators with WV2 and PL2	Note #M3
PAR1	Partition	Beige/Cream				Mens & Womens Washrooms	Painted metal partition
PAR2	Partition	Beige/Beige				Mens & Womens Showers	Solid phenolic partition
PC1	Concrete		Polished			Corridors, washrooms, lobby	
PL1	Plastic Laminata	Walnut				Millwork in shared staff areas	Note #M2, #M3
PL2	Plastic Laminata	Maple				Millwork in office areas	Note #M2, #M3
PL3	Plastic Laminata	Dark Grey				Counters in shared staff areas	Note #M2, #M3
PL4	Plastic Laminata	Copper				Millwork in shared staff areas	Note #M2, #M3
PL5	Plastic Laminata	Dark Green				Millwork in office areas	Note #M2, #M3
PT1	Paint	Green				Field Colour	Note #M2, #M5
PT2	Paint	Green				Field Colour, Trim and Accents	Note #M2, #M5
PT3	Paint	Warm Grey				Field Colour, Trim and Accents	Note #M2, #M5
PT4	Paint	Dark Red				Accents	Note #M2, #M5
PT5	Paint	Dark Brown				Accents	Note #M2, #M5
PT6	Paint	Yellow				Accents	Note #M2, #M5
PT7	Paint	Charcoal Grey				Accents	Note #M2, #M5
RB1	Rubber Base	Grey				Exercise Room	Integrated toe
RB2	Rubber Base	Warm Grey				Business Centers and IT Areas	Integrated toe
RB3	Rubber Base	Dark Grey				Work areas and offices	Integrated toe
RS1	Roller Shade					Refer to specification Window shade on each window	
SC1	Concrete		Sealed			Refer to specification	
SP11	Sport Flooring	grey	Textured			Refer to specification Exercise Room	Note #M1
SP12	Sport Flooring	Yellow	Textured			Refer to specification Exercise Room	Note #M1
SS1	Solid Surface	Dark Grey	Matte			Refer to specification Public Areas	Note #M2, #M3
SS2	Solid Surface	Dark Green	Matte			Refer to specification Washrooms and Locker Rooms	Note #M2, #M3
TL1	Ceramic Tile	Cream	Satin			305mm x 610mm x 9.5mm thickness	Walls and Floors
TL2	Ceramic Tile	Cream	Polished			305mm x 610mm x 9.5mm thickness	Walls
TL3	Ceramic Tile	Cream	Satin			25mm x 25mm x 9.5mm thickness	Walls and Floors
TL4	Ceramic Tile	Dark Grey	Satin			305mm x 610mm x 9.5mm thickness	Walls and Floors
TL5	Ceramic Tile	Dark Grey	Polished			305mm x 610mm x 9.5mm thickness	Walls
TL6	Ceramic Tile	Dark Grey	Metallic			305mm x 610mm x 12.5mm thickness	Walls, lobby, reception
TL7	Ceramic Tile	Rust/Copper	Metallic			305mm x 610mm x 12.5mm thickness	Walls, lobby
TL8	Glass Tile	Cream/Green	Mosaic with Copper Metal			25mm x 25mm	Walls, backplash
VW1	Vinyl Wall Covering	Image	Image			Refer to spec. Owner supplied Image	Note #M2, #M5
WD1	Solid Wood	Cherry	N/A			Refer to specification Public Areas	Note #M2, #M3
WD2	Solid Wood	Maple	N/A			Refer to specification User Suites/Work Areas	Note #M2, #M3

ROOM FINISH SCHEDULE

MATERIALS & FINISHES LEGEND

- | | | | | | |
|-----|-----------------------------|-----|-------------------------|-----|----------------------|
| ACT | ACOUSTICAL CEILING TILE | APT | ALUMINUM SLAZING SYSTEM | BB | BULLETIN BOARD |
| CNC | CONCRETE | CPS | CARPET TILE | CS | CONCRETE STAIR |
| CUR | CURTAIN WALL SYSTEM | EG | ENTRY GRILLE | GWB | GYPSUM WALL BOARD |
| HCT | HOMOGENEOUS CONDUCTIVE TILE | LCT | LUNULEAM COMPOSITE TILE | ML | MELAMINE |
| PL | PLASTIC LAMINATE | PT | PAINT | PAR | PARTITION |
| RB | RUBBER | SC | SHOWER CURTAIN | SPT | SPOOT FLOORING |
| SS | SOLID SURFACE | TL | TILE | VW | VINT. WALL COVERINGS |
| WD | SOLID WOOD | WL | WOOD VENEER | | |

[illegible]

ROOM FINISH SCHEDULE

ROOM FINISH NOTES

- R1. REFER TO INTERIOR ELEVATIONS FOR MATERIAL LOCATIONS & EXTENTS.
- R2. CEILING HEIGHT DETERMINED BY EXPOSED STRUCTURE OVERHEAD.
- R3. INTERIOR FINISHES & MATERIALS PER ELEVATOR MANUFACTURER. REFER TO SPECIFICATION
- R4. CEILING HEIGHT VARIES. REFER TO REFLECTED CEILING PLAN.
- R5. REFER TO REFLECTED CEILING PLAN FOR FINISHES, LOCATIONS & EXTENTS.
- R6. PROVIDE CARPET TILES (1/4" X 5" TILES) IN THE CENTER OF ROOM

00 - Theatre Suite																	
Room No.	Room Name	Floor	Base	North	East	Walls	South	West	Ceiling	Window	Remarks						
01	Entry	Finish	Matl	Height	Matl	Finish	Matl	Finish	Matl	Finish	Height	Finish					
02	Work Area	CP11	R83	100	GW8	PT1	GW8	PT1	GW8	PT1	GW8	PT1	2750	-	N/A		
01	Meeting Room	CP11	R83	100	GW8	PT1	GW8	PT1	GW8	PT1	#R5	#R4	-	NOTE #R1			
02	Washroom	SC1	R83	100	GW8	PT1	GW8	PT1	GW8	PT1	ACT	-	3050	RS1	NOTE #R1		
03	Kitchen	LC11	R83	100	GW8	PT6	GW8	PT1	GW8	PT6	ACT	-	3050	RS1	N/A		
04	Janitor	SC1	T14	100	GW8	TL/PT	GW8	TL/PT	GW8	TL/PT	GW8	PT1	2750	-	NOTE #R1		
05	Quiet Room	LC11	R83	100	GW8	PT3	GW8	PT3	GW8	PT3	ACT	-	3050	-	N/A		
06	Business Center	LC11	R83	100	GW8	PT1	GW8	PT1	GW8	PT1	ACT	-	3050	RS1	N/A		
07	Equipment Room	HCT1	R82	100	GW8	PT1	GW8	PT1	GW8	PT1	EXP	PT1	#R2	-	N/A		
00 - Shared Spaces																	
Room No.	Room Name	Floor	Base	North	East	Walls	South	West	Ceiling	Window	Remarks						
01	Reception	Finish	Matl	Height	Matl	Finish	Matl	Finish	Matl	Finish	Height	Finish					
02	Corridor	PC1	T14	300	AGS	-	GW8	PT	GW8	PT	ACT	-	3050	-	NOTE #R1		
03	Lobby	PC1	T14	300	GW8	PT	GW8	PT	GW8	PT	ACT	-	3050	-	NOTE #R1		
04	Corridor	PC1	T14	300	#R1	#R1	#R1	#R1	#R1	#R1	#R5	#R4	-	NOTE #R1			
05	Lockers	PC1	T14	300	#R1	#R1	#R1	#R1	#R1	#R1	#R5	#R4	-	NOTE #R1			
06	Corridor	PC1	T14	300	GW8	PT	GW8	PT	GW8	PT	GW8	PT1	3050	-	NOTE #R1		
07	Corridor	PC1	T14	300	GW8	VW/PT	GW8	VW/PT	GW8	VW/PT	#R5	#R4	-	NOTE #R1			
08	Vestibule	PC1	T14	300	AGS	-	GW8	TL/PT	AGS	-	GW8	TL/PT	GW8	PT1	2800	-	N/A
09	Desk	PC1	R82	100	GW8	PT	GW8	PT	GW8	PT	ACT	-	3050	RS1	NOTE #R1		
02	Conference	CP11/2	R83	100	GW8	PT	GW8	PT	GW8	PT	ACT	-	3050	RS1	NOTE #R1		
03	Training	CP11/2	R83	100	GW8	PT	GW8	PT	GW8	PT	ACT	-	3050	-	NOTE #R1		
04	Meeting	CP11/2	R83	100	GW8	PT	GW8	PT	GW8	PT	ACT	-	3050	-	NOTE #R1		
00 - Shared Spaces																	
Room No.	Room Name	Floor	Base	North	East	Walls	South	West	Ceiling	Window	Remarks						
01	Room Name	Finish	Matl	Height	Matl	Finish	Matl	Finish	Matl	Finish	Height	Finish					
05	Admin	CP11	R83	100	GW8	PT6	GW8	PT1	GW8	PT6	GW8	VW1	ACT	-	3050	RS1	N/A
06	Meeting Room	CP11/2	R83	100	GW8	PT1	GW8	PT1	GW8	PT1	ACT	-	3050	-	NOTE #R6		
07	Office Room	CP11	R83	100	GW8	PT1	GW8	PT1	GW8	PT1	ACT	-	3050	-	N/A		
08	Office Room	CP11	R83	100	GW8	PT1	GW8	PT1	GW8	PT1	ACT	-	3050	-	N/A		
09	Office Room	CP11	R83	100	GW8	PT1	GW8	PT1	GW8	PT1	ACT	-	3050	-	N/A		
10	Office Room	CP11	R83	100	GW8	PT1	GW8	PT1	GW8	PT1	ACT	-	3050	-	N/A		
11	Office Room	CP11	R83	100	GW8	PT1	GW8	PT1	GW8	PT1	ACT	-	3050	-	N/A		
00 - Staff Amenity																	
Room No.	Room Name	Floor	Base	North	East	Walls	South	West	Ceiling	Window	Remarks						
01	Room Name	Finish	Matl	Height	Matl	Finish	Matl	Finish	Matl	Finish	Height	Finish					
02	Storage	PC1	T14	100	GW8	PT	GW8	PT	GW8	PT	#R5	#R4	-	NOTE #R1			
03	Canteen	PC1	T14	300	GW8	PT	GW8	PT	GW8	PT	#R5	#R4	-	NOTE #R1			
04	Mens Washroom	PC1	T14	100	GW8	TL/PT	GW8	TL/PT	GW8	TL/PT	#R5	#R4	-	NOTE #R1			
05	Mens Lockers	PC1	T14	100	GW8	PT1	GW8	PT1	GW8	PT1	ACT	-	3050	-	N/A		
06	Mens Shower	T14	T14	100	GW8	TL/PT	GW8	TL/PT	GW8	TL/PT	#R5	#R4	-	NOTE #R1			
07	Exercise	SP11/2	R81	100	GW8	TL	GW8	MIR	GW8	TL	GW8	MIR	#R5	#R4	RS1	NOTE #R1	
08	Women's Washroom	SP11/2	R81	100	GW8	TL	GW8	MIR	GW8	TL	GW8	MIR	#R5	#R4	RS1	NOTE #R1	
09	Women's lockers	PC1	T14	100	GW8	PT1	GW8	PT1	GW8	PT1	ACT	-	3050	-	N/A		
10	Women's Shower	PC1	T14	100	GW8	TL/PT	GW8	TL/PT	GW8	TL/PT	#R5	#R4	-	NOTE #R1			
11	Kitchen	PC1	T14	300	GW8	PT	GW8	TL/PT	GW8	VW/PT	GW8	PT	#R5	#R4	RS1	NOTE #R1	
12	Mens Washroom	PC1	T14	100	GW8	TL/PT	GW8	TL/PT	GW8	TL/PT	GW8	TL/PT	#R5	#R4	-	NOTE #R1	
13	Women's Washroom	PC1	T14	100	GW8	TL/PT	GW8	TL/PT	GW8	TL/PT	GW8	TL/PT	#R5	#R4	-	NOTE #R1	
00 - User 9000 Suite																	
Room No.	Room Name	Floor	Base	North	East	Walls	South	West	Ceiling	Window	Remarks						
01	Work Area	Finish	Matl	Height	Matl	Finish	Matl	Finish	Matl	Finish	Height	Finish					
		CP11	R83	100	GW8	PT1	GW8	PT1	GW8	PT1	#R5	#R4	-	NOTE #R1			

**Littlewood
Architects Inc.**
402 - 1491 Yonge Street, Toronto, Ontario, M4T 1Z4
Tel: (416) 964-7163 Fax: (416) 964-5817 www.rebanks.ca

This drawing as an instrument of service, is provided by and is the property of A/E/Cube/Paper/Retitled/old Architects Inc. The contractor must verify and accept responsibility for all dimensions shown on drawings. It is the responsibility of the contractor and architects inc. of any variations from the supplied information. This drawing is not to be scaled. The architect is not responsible for the accuracy of survey, structural, mechanical, electrical, etc., information shown on this drawing. Refer to the appropriate consultant's drawings before proceeding with the work.

The contractor shall be responsible for obtaining all permits and requirements of authorities having jurisdiction. The contractor working from drawing not specifically marked "For Construction" must assume full responsibility and bear costs for any corrections or damages resulting from his work.

PRELIMINARY
NOT FOR CONSTRUCTION

North:	
Seal:	

7	SITE PLAN AGREEMENT - 2	2012 / 03 / 22
#	REVISION	DATE

 Government of Canada
Gouvernement du Canada

<p>NIAGARA OFFICE ADMINISTRATION FACILITY</p>	<p>Location: Niagara-on-the-Lake, Ontario</p>
--	--

MATERIAL & ROOM FINISHES SCHEDULE

A0.06