

ADDENDUM No.01, dated 2012-08-14.

This Addendum shall form part of documents referred to in "Articles of Agreement" as "Plans and Specifications".

The Plans and Specifications are amended as follows:

SPECIFICATIONS

ARCHITECTURAL:

	CONSTRUCTION PROGRESS SCHEDULE - BAR (GANTT) CHART	Sect 01 32 16.07 2012-07-13
--	--	------------------------------------

<u>1.2 CONSTRUCTION WORK SCHEDULE</u>	1. Item 1.2.1: Delete reference to "forty (40) weeks" and replace with "fifty two (52) weeks".
---	--

	MASONRY	Section 04 04 99 2012-07-13
--	---------	------------------------------------

<u>2.2 REINFORCEMENT AND CONNECTORS</u>	1. Item 2.2.6: Delete reference to "CAN/CSA-A370" and replace with "CAN/CSA-A370, minimum Level 2 corrosion protection". 2. Add new item 2.2.7: ".7 Corrosion protection: to Clause 5 and Table 5.1 and 5.2 of CAN/CSA-A370, for metal ties and horizontal reinforcing in exterior walls, walls in shower areas wet areas."
---	---

<u>2.7 REINFORCING AND TYING</u>	1. Delete article 2.7 in its entirety and replace with the following:
--------------------------------------	---

<u>"2.7 PRECAST CONCRETE SILLS AND HEADERS</u>	.1 Precast concrete sills and headers: .1 Cement: to CAN/CSA-A3000, Type GU.
--	---

- .2 Compressive strength: 30 MPa at 28 Days.
- .3 Exposure class: F-1 to CSA A23.1/A23.2.
- .4 Aggregate size: 10 mm maximum size To CSA A23.1/A23.2.
- .5 Air content: 6%.
- .6 Water: potable.
- .7 Finish: acid washed.
- .8 Sizes:
 - .1 Sills: lug sills, dimensions and shapes as indicated.
 - .2 Headers: dimensions as indicated on the drawings."

Insert a new article 3.21:

"3.21 PRECAST
CONCRETE SILLS AND
HEADERS

- .1 Install precast concrete sills and headers as indicated on the drawings."

ELECTRICAL:

ACCESS CONTROL

Section 28 13 00

2012-07-13

Delete Section 28 13 00 - Access Control, dated 2012-07-13, in its entirety and replace with the attached Section 28 13 00, dated 2012-08-14.

DRAWINGS

ARCHITECTURAL:

NEW SKETCH ADD-01-SK-A01 - PRECAST HEADER

Add new Sketch ADD-01-SK-A01, dated 2012-08-14, as attached at the end of Addendum No.1.

PWGSC Ontario	FRONTENAC INSTITUTION	Addendum No.01
Region Project	NEW 50 BED LIVING UNIT	Page 3
Number R.045083.001		2012-08-14

NEW SKETCH ADD-01-SK-A02 - PRECAST SILL WITH LUGS

Add new Sketch ADD-01-SK-A02, dated
2012-08-14, as attached at the end of
Addendum No.1.

CIVIL:

REFERENCE DWG.OPSD 3120.100 - WALLS, RETAINING, CONCRETE TOE WALL,

Add reference Dwg.OPSD 3120.100, showing
details of retaining wall construction, as
attached at the end of Addendum No.1.

End of Addendum No.01 dated 2012-08-14
consisting of 3 pages and the attached following documents:

Specification Sections:

Section 28 13 00 - Access Control, dated 2012-08-14 (14 pages)

Drawings:

New Sketch ADD-01-SK-A01 - PRECAST HEADER

New Sketch ADD-01-SK-A02 - PRECAST SILL WITH LUGS

Reference Dwg.OPSD 3120.100 - WALLS, RETAINING, CONCRETE TOE WALL