
AMENDMENT TO TENDER # 1

Tender Form

Clarification: A new Appendix 1 - Combined Price Form will be issued to reflect the changes to the revised work summary tables from Appendix I & II.

Clarification: New security features as detailed and specified are to be included in the price for item 2.7 'Installation of new cover c/w new security features' for the amended Appendix 1 – Combined Price Form of the Tender Form. Both concrete surround as per detail F/C3 and the new security covers as per details D/C3 are to be included. This item is now item 2.9 on the revised Appendix 1 - Combined Price Form

Summary of Work (Division 01 11 00)

Section 1.1: Contract Method

Add: .1.17 New 2400mm diameter manhole: \$/EACH

Add: .1.18 New 1200mm diameter manhole: \$/EACH

Sewer Main, Lateral and Manhole Rehabilitation (Division 33 15 00)

Section 1.3: Supporting Documents

Clarification: Existing CCTV footage will only be provided to the awarded contractor and made available in accordance with Section 1.3.1

Appendix I: Pipe Work Summary

Delete: Appendix I: Pipe Work Summary Table

Replace with: Attached Revised Appendix I: Pipe Work Summary Table

Clarification: Material abbreviations:
CO and CP: concrete
VCP: vitrified clay pipe
AC: asbestos cement
CSP: Corrugated steel pipe
PVC: Polyvinyl chloride

CI: Cast iron

Clarification: Lump sum items listed on the Revised Appendix II: Pipe Summary Table are priced as part of the lump sum amount on the amended Appendix 1 - Combined Price Table on the tender form.

Appendix II: Manhole Work Summary

Delete: Appendix II: Manhole Work Summary Table

Replace with: Attached Revised Appendix II: Manhole Work Summary Table

Clarification: Lump sum items listed on the Revised Appendix II: Manhole Summary Table are priced as part of the lump sum amount on the amended Appendix 1 - Combined Price Table on the tender form.

Drawing C1: Storm Sewer Repair Works

Delete: Drawing C1: Storm Sewer Repair Works

Replace with: Attached Revised Drawing C1: Storm Sewer Repair Works

Clarification: Pipe depth and footing detail below building C29 is unknown. The drawings C1 and C3 have been revised to reflect the amended work summary tables in Appendix I & II. Only trenchless sewer rehabilitation work is required for pipe sections located under building C29.

Drawing C2: Sanitary Sewer Repair Works

Delete: The note: "SCALE 1:150"

Replace with: The note: "SCALE 1:750"

Drawing C3: Storm Sewer Plan and Profile and Details

Delete: Drawing C3: Storm Sewer Plan and Profile and Details

Replace with: Attached Revised Drawing C3: Storm Sewer Plan and profile and Details

Clarification: The scale of this drawing is as indicated for each individual detail. Profiles are H 1:1000 and V 1:100.

General

Clarification: The contractor is responsible for protecting all security fencing and perimeter walls affected by work and to make good on any damages. Trenches under perimeter walls are to be filled with unshrinkable fill as indicated. If support, bracing, or extra measures are requested or required; shop drawings are to be submitted to the departmental representative for review prior to any work in accordance to Section's 01 33 00 & 02 41 23 of the contract specifications.

Clarification: Due to the current state of the piping, accurate information on existing sewer flows is unavailable. The contractor must assume bypass pumping requirements as required for all sewers on a case by case basis since flows will fluctuate due to the time of day, storms and infiltration into deteriorated pipes.

Clarification: The weight lifting equipment located near the east perimeter wall of Collins Bay Institute is to be moved by others prior to work in this area. Work scheduling is to be coordinated with departmental representative.

END OF ADMENDMENT #1