

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving - PWGSC / Réception des soumissions -
TPSGC
11 Laurier St. / 11, rue Laurier
Place du Portage, Phase III
Core 0A1 / Noyau 0A1
Gatineau, Québec K1A 0S5
Bid Fax: (819) 997-9776

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Vehicles & Industrial Products Division
11 Laurier St./11, rue Laurier
7A2, Place du Portage, Phase III
Gatineau, Québec K1A 0S5

Title - Sujet Pre-purchase Cooling Towers	
Solicitation No. - N° de l'invitation EP119-132112/A	Amendment No. - N° modif. 005
Client Reference No. - N° de référence du client 20132112	Date 2012-11-23
GETS Reference No. - N° de référence de SEAG PW-\$\$HP-912-61480	
File No. - N° de dossier hp912.EP119-132112	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2012-11-28	Time Zone Fuseau horaire Eastern Standard Time EST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Pearson, Neil	Buyer Id - Id de l'acheteur hp912
Telephone No. - N° de téléphone (819) 956-3976 ()	FAX No. - N° de FAX (819) 953-2953
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This solicitation amendment 005 is raised to amend solicitation and to amend Annex "B" Purchase Description.

1. At PART 6 - RESULTING CONTRACT, Article 14 Shipping Instructions - Delivery at Destination (For Firm quantities);

Delete: The following;

- 14.1 The Contractor must ship the goods prepaid DDP - Delivered Duty Paid (as detailed at Annex "A" - Pricing). Unless otherwise directed, delivery must be made by the most economical means. The Contractor is responsible for all delivery charges, administration, costs and risks of transport and customs clearance, including the payment of customs duties and taxes.
- 14.2 The Contractor must deliver the goods by appointment only. The Contractor or its carrier must arrange delivery appointments by contacting the contacts specified in Annex "A" - Pricing. The consignee may refuse shipments when prior arrangements have not been made.
- 14.3 The Cooling Tower module (s) must arrive as single, fully assembled and wired components, on a flatbed trailer. The Sub-Structure legs, sump, and sump hardware shall be shipped on a separate pallet on the same trailer. When provided, Motor Control Panel and/or Basin Heater Panel shall also ship on separate pallet on same trailer.
- 14.4 Upon arrival of Cooling Tower module(s) (prior to any lifting operation), the tower must be inspected on the truck by the Department Representative for general acceptance. Any items of concern related to damage or lifting operations shall be documented and reported (in writing) to the manufacturer's representative.
- 14.5 Prior to lifting and off loading Cooling Tower(s) , all excess water must be removed from basin.
- 14.6 Cooling Tower(s) will be temporarily placed and stored on the ground prior to its final installation. The Cooling Tower(s) shall be stored on sound and level surface. Care shall be taken at all times not to distort or rack the tower modules envelope. Provide temporary weather protection for all material shipped.
- 14.7 Upon delivery to the designated site provide suitable pressure treated wood sleepers for equipment placing and storage on the flat surface.

Insert: The following;

14.1 The Contractor must ship the goods prepaid DDP - Delivered Duty Paid (as detailed at Annex "A" - Pricing). Unless otherwise directed, delivery must be made by the most economical means. The Contractor is responsible for all delivery charges, administration, costs and risks of transport and customs clearance, including the payment of customs duties and taxes.

14.2 The Contractor must deliver the goods by appointment only. The Contractor or its carrier must arrange delivery appointments by contacting the contacts specified in Annex "A" - Pricing. The consignee may refuse shipments when prior arrangements have not been made.

14.3 Upon arrival of Cooling Tower module(s) (prior to any lifting operation), the tower must be inspected on the truck by the Department Representative for general acceptance. Any items of concern related to damage shall be documented and reported (in writing) to the manufacturer's representative.

2. At PART 6 - RESULTING CONTRACT, Article 17 Packaging;

Delete: The following;

The methods used for preservation and packaging must be in conformity with the Contractor's normal standard for domestic shipment or, if necessary, with standards for overseas shipment as below deck cargo. Provide heavy duty "winterized" shrink wrap for all shipped components.

Insert: The following;

The methods used for preservation and packaging must be in conformity with the Contractor's normal standard for domestic shipment or, if necessary, with standards for overseas shipment as below deck cargo.

3. At Annex "B" Purchase Description, revision 2, paragraph 1.3.3;

DELETE: Prior to lifting and off-loading Cooling Tower(s), all excess water must be removed from basin.

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME