

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving - PWGSC / Réception des soumissions -
TPSGC
11 Laurier St./11 rue Laurier
Place du Portage, Phase III
Core 0A1 / Noyau 0A1
Gatineau, Québec K1A 0S5

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires
This Document contains a Security Requirement

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Construction Services Division/Division des services de
construction
11 Laurier St./11 Rue Laurier
3C2, Place du Portage
Phase III
Gatineau, Québec K1A 0S5

Title - Sujet FIRE ALARM SYSTEM REPLACEMENT	
Solicitation No. - N° de l'invitation EP067-133136/A	Amendment No. - N° modif. 006
Client Reference No. - N° de référence du client 20133136	Date 2013-04-16
GETS Reference No. - N° de référence de SEAG PW-\$\$\$FG-355-62441	
File No. - N° de dossier fg355.EP067-133136	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2013-04-23	
Time Zone Fuseau horaire Eastern Daylight Saving Time EDT	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: D'Aoust, Luc	Buyer Id - Id de l'acheteur fg355
Telephone No. - N° de téléphone (819) 956-6149 ()	FAX No. - N° de FAX (819) 956-3160
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: Place du Centre Tower 200 Promenade du Portage Gatineau Qc. K1A 0S5	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation

EP067-133136/A

Amd. No. - N° de la modif.

006

Buyer ID - Id de l'acheteur

fg355

Client Ref. No. - N° de réf. du client

20133136

File No. - N° du dossier

fg355EP067-133136

CCC No./N° CCC - FMS No/ N° VME

This amendment 006 replaces amendment 005
Attachment ATT 6 replaces ATT 5

Solicitation No. - N° de l'invitation

EP067-133136/A

Amd. No. - N° de la modif.

006

Buyer ID - Id de l'acheteur

fg355

Client Ref. No. - N° de réf. du client

20133136

File No. - N° du dossier

fg355EP067-133136

CCC No./N° CCC - FMS No/ N° VME

The following changes in the bid documents are effective immediately. This addendum will form part of the contract documents.

GENERAL

1. FLOOR HEIGHTS

1. Floor heights provided below are applicable to all drawings included in the contract.

Floors	Level (m)
Roof	107.82
13 th (penthouse)	102.57
12 th	98.76
11 th	95.25
10 th	91.75
9 th	88.24
8 th	84.73
7 th	81.23
6 th	77.72
5 th	74.22
4 th	70.71
3 rd (ground floor)	65.83
2 nd	60.96
1 st	54.86

SPECIFICATIONS

1. MECHANICAL

1. Section 21 13 13
 - i. Remove item 3.5
 - ii. Replace item 3.8.2 with the following:
"Installer Field Services"
 - iii. Replace item 3.8.2.1 with the following:
"Obtain written letter from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Installer Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS".
 - iv. Replace item 3.8.2.2 with the following:
"Provide installer field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions."
 - v. Remove item 3.8.3
2. Section 21 31 13.01
 - i. Replace item 2.10 with the following:

2.10 FIRE RATED DUCT WORK

- | | |
|----|--|
| .1 | Duct Work |
| .1 | Duct shall be conform to ULC; |
| .2 | 2 hours fire resistance rating in accordance with ISO 6944 |
| .3 | Duct work shall be provided complete with: |
| .1 | Insulation material; |
| .2 | Reinforcing angles; |
| .3 | Inner Liner; |
| .4 | Exterior casing; |
| .5 | Flange; |
| .6 | Corners; |
| .7 | Edge Coping. |
| .2 | Fire rated duct wrap accepted |
| .1 | Shall be conform to ULC; |
| .2 | 2 hours fire resistance rating in accordance with ISO 6944 |

2. ELECTRICAL

1. Section 28 31 00.02

- i. Replace item 2.20.4.2 with the following:

“Workstation Display Filter: The GW shall be able to be configurable to filter events that would be displayed or not displayed at the workstation. Shall be able to select between; Alarms, Supervisory, Monitor, and Troubles events to be viewed.”

DRAWINGS**1. ARCHITECTURAL**1. A600 - Sections \ **Refer to sketch CA-01**

- i. Delete all slab elevations indicated on detail 2/A600 and substitute with the elevations found in item 1.1 of GENERAL section above.
- ii. Add detail 3/A600. Refer to CA-01, issued as part of this addendum.

2. A900 - Door & Frame Schedule and Room Finish Schedule \ **Refer to sketch CA-02**

- i. Delete detail in its entirety and substitute with revised detail 3/A900 on CA-02, issued as part of this Addendum.

3. A102 - 4th to 12th floor - Demolition & New Work Plan \ **Refer to revised drawing A102**

- i. Modification to Demotion & New Work Note 302.
- ii. Modifications in detail 1-A102.

2. MECHANICAL

1. M006 - Level 3 - Ventilation

- i. Dimensions of mechanical Duct work above the grid line Gx/7 is 350x300mm.
- ii. Dimensions of mechanical Duct work under the grid line Gx/7 is 750x300mm.

3. ELECTRICAL1. E303 - Fire Alarm Riser - Federal Tower \ **Refer to revised drawing E303**

- i. Adjustments to the fire alarm device and speaker wiring between Fire Alarm Control Panel (3
- rd
- floor) and D.G.P (13
- th
- floor).