

The following changes to the tender documents are effective immediately and will form part of the contract documents:

**SPECIFICATION**

- 1) Section 01 11 00 – Page 5 of 10, Item 1.9.1.12.3

**Delete:** “Importing and placing approximately 420 m<sup>3</sup> of 200 mm diameter rip rap to line the base and swale in Reach 2 and Reach 3 as specified in the swale design provided above.”

**Add:** “Importing and placing approximately 420 m<sup>3</sup> of 200 mm diameter rip rap or 50 mm (2 inch) to 150 mm (6 inch) diameter river stone to line the base and swale in Reach 2 and Reach 3 as specified in the swale design provided above”.

- 2) Section 01 11 00 – Page 6 of 10, Item 1.9.1.13

**Delete:** “It is required that an additional 10 m<sup>3</sup> of 200 mm diameter rip rap will be required to construct the rock check dam.”

**Add:** “It is required that an additional 10 m<sup>3</sup> of 200 mm or 50 mm (2 inch) to 150 mm (6 inch) diameter river stone rip rap will be required to construct the rock check dam.

- END -