



Stantec

Geotechnical Survey and Utilities Capacity Study

PWGSC Reference: R.058448.002

STANTEC FILE: 115447450

DATE: FEBRUARY 26, 2013

Prepared By:

Stantec Architecture Ltd.
905 Waverley Street Winnipeg MB R3T 5P4
Tel: (204) 489-5900, Fax: (204) 453-9012

Contact: Bruce Haugh, P.Eng.
Email: Bruce.Haugh@stantec.com
Direct telephone: 204-928-8800

TABLE OF CONTENTS

| | |
|---|----|
| EXECUTIVE SUMMARY | 4 |
| 1 PROJECT DESCRIPTION..... | 5 |
| 1.1 General..... | 5 |
| 1.1.1 Services and Scope | 5 |
| 1.2 Background Information | 5 |
| 2 Site Studies | 6 |
| 2.1 Geotechnical Investigation..... | 6 |
| 2.1.1 Testhole Drilling and Soil Sampling..... | 6 |
| 2.1.2 Laboratory Testing..... | 6 |
| 2.1.3 Soil Profile | 7 |
| 2.3 Groundwater..... | 8 |
| 2.4 Geotechnical Considerations..... | 8 |
| 2.5 Design Recommendations and Comments..... | 8 |
| 2.5.1 Foundations..... | 8 |
| 2.5.2 Timber Piles | 9 |
| 2.5.3 Precast Concrete Piles..... | 10 |
| 2.5.4 Floor Slab..... | 11 |
| 2.5.5 Drainage..... | 13 |
| 2.5.6 Foundation Concrete..... | 13 |
| 2.5.7 Concrete Sidewalks..... | 13 |
| 2.6 Site Seismic Classification..... | 14 |
| 3 SITE SURVEY | 15 |
| 3.1 Mechanical Site Observations..... | 15 |
| 3.1.1 General Information..... | 15 |
| 3.1.2 Sources of Information | 15 |
| 3.1.3 Water..... | 15 |
| 3.1.4 Storm and Sewer System | 17 |
| 3.1.5 Natural Gas Distribution | 18 |
| 3.2 Electrical Site Observations | 20 |
| 3.2.1 Summary | 20 |
| 3.2.2 Sources of Information | 20 |
| 3.2.3 Power Distribution | 20 |
| 3.2.4 Telecommunication..... | 21 |
| 3.2.5 Fire Alarm System | 22 |
| 4 MISCELLANEOUS TEST REPORTS | 23 |
| 4.1 Fire Hydrant Test Report | 23 |
| 5 LIMITATIONS..... | 24 |
| 5.1 Geotechnical, Mechanical, and Electrical Assessments..... | 24 |

List of Tables

| | |
|--|----|
| Table 1 - Particle Size and Atterberg Limits Test Data | 6 |
| Table 2 - Sulphate Content, Chloride Content, and pH Test Data | 7 |
| Table 3 - Standard Proctor and CBR Test Data | 7 |
| Table 4 - ULS Design Values for Timber Piles | 10 |
| Table 5 - ULS Design Values for Precast Concrete Piles | 11 |
| Table 6 - Granular Fill Requirements for Floor Slab | 12 |
| Table 7 - Foundation Concrete Requirements | 13 |
| Table 8 - Water Fixture Unit (WFU) | 16 |
| Table 9 - Drainage Fixture Unit (DFU) | 17 |
| Table 10 – Natural Gas Load | 19 |

List of Appendices

| |
|---|
| Appendix A - Site Photographs |
| Appendix B - Testhole Location Plan |
| Appendix C - Testhole Logs and CBR Report |
| Appendix D - Laboratory Test Reports |
| Appendix E1 – Morden Research Centre Site Plan C-101 |
| Appendix E2 – Morden Research Centre Utilities Site Plan ME-101 |
| Appendix F1 – Hydrant Flow Test Map Locations |
| Appendix F2 – Hydrant Flow Test Results |
| Appendix F3 – Hydrant Flow Test Equipment |

EXECUTIVE SUMMARY

The geotechnical investigation was conducted to provide foundation recommendations for a future greenhouse and header house at the Morden Research Centre. A total of eight (8) testholes were drilled on the project site on November 15, 2012. The general soil stratigraphy at the site, as interpreted from the testhole logs, consists of topsoil, silty clay, sand, silt, and clay to the depths explored in the testholes. Based on the soil and groundwater conditions encountered at the testhole locations, timber or precast concrete friction piles could be used to support the structures.

The assessment of the suitability of the existing mechanical infrastructure is limited due to the lack of exact data on the utility requirements of the proposed building and renovations. However, water and sewer appear to be adequate for typical new construction. A limiting factor of the adequacy depends in part on the size and depth of the new building as well as internal process requirements. The natural gas service pressure to the site needs to be increased or a new line from the main to the new building must be installed.

The electrical service to the site appears to be adequate; however, serving power to a new building at the proposed site would require an upgrade to the existing nearby transformer TR#1 or a new dedicated pad mounted transformer be provided. The emergency electrical service to the site appears to be adequate for the current needs. Serving power to a new building at the proposed site would require an upgrade of the existing generator diesel unit or new dedicated diesel generator unit be provided. The incoming telephone services to the facility are sufficient. Additional telephone lines to the new building at the proposed site would have to be coordinated with MTS. The existing fire alarm control panel is a conventional system and has limited zones of initiating devices. Provision of a fire alarm system to the new building would require upgrading the existing fire alarm control panel or a new stand alone addressable panel located in the new building and interconnected to the existing system.

1 PROJECT DESCRIPTION

1.1 General

1.1.1 Services and Scope

Public Works and Government Services Canada (PWGSC) retained the services of Stantec Consulting Ltd., which offered a multi-disciplinary team of specialists required for this project. Services included the provision of a geotechnical report and land topographical and underground surveys in a defined area allocated for a future building. Mechanical and electrical utility service capacity reviews of the site were also required to help determine the possible need for utility and infrastructure upgrades.

1.2 Background Information

AAFC is proposing to design and construct the following:

- .1 A new greenhouse / header house

The project is intended to identify action items for site upgrades to allow for the relocation of the Cereal Research Centre in Winnipeg to the Morden Research Centre and to accommodate a laboratory modification to Building #72. The laboratory project will include provisions for new freezers.

2 SITE STUDIES

2.1 Geotechnical Investigation

2.1.1 Testhole Drilling and Soil Sampling

The subsurface drilling and sampling program was conducted on November 15, 2012 under the supervision of our geotechnical field personnel. Drilling services were provided by Kletke Environmental Drilling Ltd. Eight (8) testholes were drilled to a depth of 10 m at the locations shown on the Testhole Location Plan provided in Appendix B.

Representative soil samples were obtained directly from the auger flights at depths ranging from 0.3 to 1.5 m. The soil samples were visually classified in the field and returned to Stantec's soils laboratory for additional examination and testing. Upon completion of drilling, the testholes were examined for evidence of sloughing and groundwater seepage. A stand pipe was installed in Testhole TH 04 during the geotechnical field investigation. The testholes were backfilled with auger cuttings upon completion of the site investigation.

2.1.2 Laboratory Testing

Water content tests were conducted on the soil samples recovered from the testholes and the results are shown in the testhole logs provided in Appendix C. Selected soil samples were tested for the following:

- .1 particle size (ASTM D422)
- .2 Atterberg limits (ASTM D4318)
- .3 water-soluble sulfate in soil (CSA A23.2-3B)
- .4 water-soluble chloride in soil (AAHSTO T291)
- .5 pH of soil (ASTM D4972)
- .6 standard Proctor (ASTM D698)
- .7 California Bearing Ratio (ASTM D1883)

The test results for particle size, Atterberg limits, water-soluble sulfate, water-soluble chloride, pH, standard proctor and CBR are summarized in Tables 1-3.

Table 1 - Particle Size and Atterberg Limits Test Data

| Testhole no. | Sample Depth (m) | Soil Type | Particle Size | | | | Atterberg Limits | | |
|--------------|------------------|------------|--------------------------------|----------------------------------|-----------------------------------|-----------------------|------------------|---------------|------------------|
| | | | Gravel (%) 75 to 4.75 mm | Sand (%) <4.75 to 0.075 mm | Silt (%) <0.075 to 0.005 mm | Clay (%) <0.005 mm | Liquid Limit | Plastic Limit | Plasticity Index |
| TH 04 | 0.8 | Silty Clay | 0.1 | 6.9 | 30.4 | 62.6 | 65 | 23 | 42 |
| TH 04 | 2.3 | Silty Clay | 0 | 9.7 | 31.8 | 58.5 | 55 | 23 | 32 |
| TH 04 | 4.6 | Sand | 6.9 | 75.0 | 9.1 | 9.0 | nonplastic | | |

Table 2 - Sulphate Content, Chloride Content, and pH Test Data

| Testhole no. | Sample Depth (m) | Soil Type | Water-Soluble Sulphate Content (%) | Water-Soluble Chloride Content (mg/kg) | pH |
|--------------|------------------|------------|------------------------------------|--|-----|
| TH 04 | 0.3 | Silty Clay | 0.38 | 10 | 7.9 |
| TH 04 | 3.0 | Silty Clay | 0.56 | 11 | 8.3 |
| TH 04 | 7.6 | Clay | 0.07 | 41 | 8.7 |

Table 3 - Standard Proctor and CBR Test Data

| Testhole no. | Sample Depth (m) | Soil Type | Maximum Dry Density (kg/m ³) | Optimum Moisture Content (%) | CBR Soaked (%) |
|------------------|------------------|------------|--|------------------------------|----------------|
| Composite Sample | 0.0 - 0.8 | Silty Clay | 1477 | 25.5 | 2.1 |

Note: Composite sample obtained from silty clay samples from Testholes TH 01, TH 03, and TH 04.

The laboratory test reports are provided in Appendix D.

2.1.3 Soil Profile

The typical soil stratigraphy at the Morden Research Center site, as interpreted from the testhole logs, consists of topsoil, silty clay, sand, silt and clay to the depths explored in the testholes. Granular fill was found below the topsoil in Testhole TH 06. A description of the soil types is provided below.

.1 Topsoil: Topsoil was encountered at the surface of all testholes. The thickness of the topsoil was approximately 0.1 m.

.2 Granular Fill: Granular fill was encountered below the topsoil in Testhole TH 06. The granular fill extended to a depth of 1.2 m. The granular fill was brown, loose, moist and of low plasticity with some clay and trace fine to coarse gravel. The thickness of the granular fill was approximately 1.1 m. Water contents of the granular fill ranged from 7 to 12%.

.3 Silty Clay: Silty clay was typically encountered below the topsoil. The silty clay extended to depths ranging from 1.6 to 3.7 m. The silty clay was black to grey, soft to firm, moist and of high plasticity with trace organics, trace fine sand and trace gravel. Water contents of the silty clay ranged from 19 to 41%.

.4 Sand: Sand was typically encountered below the silty clay. Sand was also encountered below clay in Testhole TH 06. The sand extended to depths ranging from 4.6 to 5.5 m. The sand was tan, loose to dense, and moist, with trace coarse gravel, trace silt and trace clay. Water contents of the sand ranged from 12 to 34%.

.5 Silt: Silt was typically encountered below the sand. The silt extended to depths ranging from 5.9 to 7.0 m. Silt was not encountered in Testhole TH 02. The silt was grey to tan, compact and moist with trace clay. Water contents of the silt ranged from 20 to 29%.

.6 Clay: Clay was typically encountered below the silt. Clay was also encountered below the sand in testhole TH 02. The clay extended to the maximum depths explored in the testholes. The clay was grey, soft to firm, moist and of high plasticity with trace to some silt. Water contents of the clay ranged from 22 to 59%.

2.3 Groundwater

Groundwater conditions were observed immediately after completion of drilling of the testholes. Minor to moderate groundwater seepage and sloughing was observed in the sand layers in the testholes at depths between 3.0 to 4.7 m. All observations of groundwater conditions are shown in the testhole logs provided in Appendix C. It should be noted that only short-term seepage and sloughing conditions were observed in the testholes. Groundwater levels will normally fluctuate during the year and will be dependent on precipitation and surface drainage. Groundwater seepage and soil sloughing should be expected from the sand and silt layer encountered in the testholes during periods of snow melt and heavy precipitation.

A standpipe piezometer was installed in Testhole TH 04 to a depth of 5.6 m and was slotted from 3.0 to 5.6 m. The water level in the standpipe piezometer on November 24, 2012, 9 days after completion of drilling, was 3.1 m below existing grade.

2.4 Geotechnical Considerations

Based on our current understanding of the proposed development and the results of our geotechnical investigation, the primary geotechnical concerns on the project site are:

- .1 groundwater seepage and sloughing in the sand layer, and
- .2 high volume change potential of high plasticity silty clay soil.

These issues will be discussed in the following section.

2.5 Design Recommendations and Comments

2.5.1 Foundations

Based upon the soil and groundwater conditions encountered at the testhole locations, the proposed greenhouse and header house may be supported on timber or precast concrete friction piles. Other foundation options considered for the proposed greenhouse and header house included shallow footings, cast-in-place concrete friction piles, and precast concrete end-bearing piles. Shallow footings are not considered suitable for this project due to anticipated poor foundation performance related to volume change within the high plasticity silty clay. Cast-in-place concrete piles are not considered suitable for this project due to groundwater seepage and sloughing conditions in the sand layer. Precast concrete end-bearing piles are not considered suitable for this project as refusal depth was not established during our field investigation.

In accordance with the 2010 National Building Code of Canada (NBCC), the use of Limit States Design (LSD) is required for the design of buildings and their structural components including foundations. The limit states of LSD design are classified into two groups; the Ultimate Limit States (ULS) and the Serviceability Limit States (SLS).

The Ultimate Limit States case is primarily concerned with collapse mechanisms for the structure and hence, safety. For foundation design, ultimate limit states consist of:

- .1 Exceeding the load-carrying capacity of the foundation
- .2 Sliding
- .3 Uplift
- .4 Large deformation of foundation, leading to an ultimate limit state being induced in the .5 superstructure or building
- .5 Overturning, and
- .6 Loss of overall stability

The factored resistance at the ULS is the ultimate geotechnical resistance multiplied by the appropriate resistance factor.

The Serviceability Limit States (SLS) case considers mechanisms that restrict or constrain the intended use or occupancy of the structure. They are typically associated with movements that interrupt or hinder the purpose of the structure. For foundation design, serviceability limit states can be categorized as:

- .1 Excessive movements, and
- .2 Unacceptable vibrations

The SLS case is addressed by determining the maximum available resistance to keep the foundation under service loads within tolerable limits as provided by the structural engineer. Un-factored permanent and transitory loads are used for calculating total deformation in non-cohesive soils. Permanent loads and appropriate portions of transitory loads are used for the initial and time-dependent final deformations of cohesive soils. Therefore, the foundation loads and serviceability tolerances have to be known to properly determine the SLS resistance values. In cases where tolerable movements are not provided by the structural engineer, the tolerable limit of total settlement for foundations subject to compression is assumed to be 25 mm.

2.5.2 Timber Piles

A foundation system suitable to support the proposed lightly-loaded structures is a system of driven timber piles. These units, when driven to a depth of 10 m with a hammer capable of delivering a minimum rated energy of 40 KJ per blow, may be designed based on the factored shaft friction resistance values shown in Table 4.

Table 4 - ULS Design Values for Timber Piles

| Depth Range below Grade | Factored Shaft Friction |
|------------------------------------|---|
| 0 m to 1.5 m | 0 kPa |
| 1.5 m to 10 m | increases linearly from 6 kPa at 1.5 m to 24 kPa at 10 m |

For friction piles, less than 15 mm of settlement is required to mobilize skin friction and consequently, the SLS case does not govern pile design. Although higher pile capacities will be achieved for pile lengths greater than 10 m, soil conditions below a depth of 10 m were not evaluated during our site investigation. Our office should be contacted if pile lengths greater than 10 m are being considered for the proposed structures. The structural engineer must check the properties of the timber pile and confirm that the structural capacity of the pile is not exceeded.

Due to the presence of silty clay at a shallow depth and the potential for soil drying and shrinkage near the ground surface, the frictional support should be excluded in the calculation of the pile capacity as follows:

- .1 For piles inside heated buildings (not perimeter piles), the depth to ignore for frictional support should be the upper 1.5 m below the adjacent ground surface
- .2 For perimeter piles, the depth to ignore for frictional support should be the upper 2.5 m below the adjacent ground surface

The contribution from end bearing should be ignored in pile capacity calculations. Pile spacing should not be less than 3 pile diameters, measured center to center. Pile heave for piles within 5 pile diameters should be monitored and redriving done where pile heave occurs. Timber piles are subject to decay above the zone of saturation and must therefore be treated with a wood preservative. Pre-boring to a depth of approximately 2 m should be considered for all driven piles to enhance pile alignment and to limit vibrations for existing structures. The prebored hole diameter should be slightly larger than the nominal pile diameter. All piles should be driven continuously to their required depth once driving is initiated. If pile groups are required for the proposed greenhouse and header house, we should be contacted to review the requirement for a group reduction factor.

A minimum void space of 150 mm should be provided beneath all structural elements to accommodate potential heave of the high plasticity silty clay. To ensure that the piles achieve their design capacities, full time inspection by qualified geotechnical personnel is recommended during pile installation.

2.5.3 Precast Concrete Piles

A foundation system suitable to support the proposed lightly-loaded structures is a system of driven precast concrete friction piles. These units, when driven to a depth of 10 m with a hammer capable of delivering a minimum rated energy of 40 KJ per blow, may be designed based on the factored shaft friction resistance values shown in Table 5.

Table 5 - ULS Design Values for Precast Concrete Piles

| Depth Range below Grade | Factored Shaft Friction |
|------------------------------------|---|
| 0 m to 1.5 m | 0 |
| 1.5 m to 10 m | increases linearly from 3 kPa at 1.5 m to 13 kPa at 10 m |

For friction piles, less than 15 mm of settlement is required to mobilize skin friction and consequently, the SLS case does not govern pile design. Although higher pile capacities will be achieved for pile lengths greater than 10 m, soil conditions below a depth of 10 m were not evaluated during our site investigation. Our office should be contacted if pile lengths greater than 10 m are being considered for the proposed structures.

Due to the presence of silty clay at a shallow depth and the potential for soil drying and shrinkage near the ground surface, the frictional support should be excluded in the calculation of the pile capacity as follows:

- .1 For piles inside heated buildings (not perimeter piles), the depth to ignore for frictional support should be the upper 1.5 m below the adjacent ground surface
- .2 For perimeter piles, the depth to ignore for frictional support should be the upper 2.5 m below the adjacent ground surface

The contribution from end bearing should be ignored in pile capacity calculations. Pile spacing should not be less than 3 pile diameters, measured center to center. Pile heave for piles within 5 pile diameters should be monitored and redriving done where pile heave occurs. Pre-boring to a depth of approximately 2 m should be considered for all driven piles to enhance pile alignment and to limit vibrations for existing structures. The prebored hole diameter should be slightly larger than the nominal pile diameter. All piles should be driven continuously to their required depth once driving is initiated. If pile groups are required for the proposed greenhouse and header house, we should be contacted to review the requirement for a group reduction factor.

A minimum void space of 150 mm should be provided beneath all structural elements to accommodate potential heave of the high plasticity silty clay. To ensure that the piles achieve their design capacities, full time inspection by qualified geotechnical personnel is recommended during pile installation.

2.5.4 Floor Slab

Due to the presence of high plasticity silty clay at this site, the potential exists for heave of a soil-supported floor slab. Soil moisture contents will typically increase after construction, which causes swelling of clay soils. The magnitude of heave for soil-supported floor slabs is typically in the range of 20 to 50 mm, but can be as high as 100 mm. Heave is generally higher on sites where trees are removed prior

to construction or in areas where leaking water supply or sewer lines or poor drainage lead to increased moisture contents in the silty clay soil after construction. Based upon the soil conditions encountered on the project site, the maximum heave of a soil-supported floor slab is estimated to be in the range of 35 to 50 mm. To minimize potential heave of a soil-supported floor slab, measures must be taken to prevent drying of the subgrade soils during construction. The magnitude of slab heave can be reduced by removal of the high plasticity silty clay soils near the ground surface and replacement with granular fill. Removal of the expansive clay soils to a depth of 0.75 m and replacement with granular fill will reduce the maximum predicted slab heave to 10 to 15 mm. Construction of a soil-supported floor slab should proceed as follows:

- .1 Remove topsoil
- .2 Proof roll exposed silty clay subgrade to identify areas with low strength soils.
- .3 Excavate low strength soils identified during proof rolling and replace with granular sub-base material.
- .4 Place and compact granular sub-base, as required, to raise the existing grade to achieve the design elevation for the floor slab
- .5 Place and compact granular base course

The minimum thickness of granular base course beneath the concrete floor slab should be 150 mm. All granular fill materials should be placed in 150 mm thick lifts and compacted to at least 100% of Standard Proctor Density.

The granular base and sub-base materials for floor slab construction should comply with the requirements for Manitoba Infrastructure and Transportation Class A and Class C Base Course respectively. The requirements for the granular fill materials are shown in Table 6.

Table 6 - Granular Fill Requirements for Floor Slab

| Sieve Size | Base Course | Sub-Base |
|-------------------|--------------------|-----------------|
| 37.5 mm | | 100% |
| 25 mm | | 85 to 100% |
| 19 mm | 100% | — |
| 16 mm | 80 to 100% | — |
| 4.75 mm | 45 to 70% | 25 to 80% |
| 2.00 mm | 25 to 55% | — |
| 425 | 15 to 30% | 15 to 40% |
| 75 | 8 to 15% | 8 to 18% |
| Crush content | 35% min. | 15% min. |
| Shale content | 12% max. | 15% max. |
| LA abrasion | 35% max. | 40% max. |

Sieve analysis and compaction testing of the granular fill material should be conducted to ensure that the materials and compaction comply with the design specifications.

2.5.5 Drainage

All roof downspouts should be directed away from the greenhouse and header house and the ground surface should be graded to promote drainage away from the foundations. Final site grading should ensure that all surface runoff is directed away from the greenhouse and header house using a minimum gradient of 2%. To compensate for potential settlement of backfill materials adjacent to the greenhouse and header house, the grade should be increased to 10% for the first 2 m from the buildings. A clay cap should be provided at the ground surface to minimize water infiltration adjacent to the structures.

2.5.6 Foundation Concrete

Based on the water-soluble sulfate test results, and our experience in Morden, the class of exposure for concrete in contact with clay soil at the Morden Research Centre is considered to be severe (S-2 in CSA A23.1-09 Table 3). The requirements for concrete exposed to severe sulfate attack are provided in Table 7.

Table 7 - Foundation Concrete Requirements

| Parameter | Design Requirement |
|------------------------------------|---------------------------|
| class of exposure | S-2 |
| compressive strength | 32 MPa at 56 days |
| air content | 4 to 7% |
| water-to-cementing materials ratio | 0.45 max. |
| cement | Type HS or HSb |

Concrete in contact with native soils should meet the above requirements.

2.5.7 Concrete Sidewalks

Silty clay was typically encountered at a shallow depth in the testholes drilled on the project site. Silty clay is considered to be a highly frost-susceptible soil and therefore, measures must be taken to prevent frost-related movements of exterior slabs at building entrances. Frost heave of exterior concrete slabs in front of building entrances is a common problem in Manitoba. Unprotected sidewalks dowelled into the grade beam often tip up due to rotation around the dowel connection, resulting in cracking of the sidewalk and blocking of entrance doors. Unprotected sidewalks that are not dowelled into the grade beam may heave adjacent to the exterior wall resulting in blocking of entrance doors and crushing of exterior wall facing with insufficient clearance above the exterior slab. The magnitude of heave is dependent upon several factors including the soil type, soil moisture content, climatic conditions, and heat loss from the structure. Due to the many factors that play a role in frost heave, the magnitude of heave is very difficult to predict. Maximum heave in the range of 40 to 60 mm has been observed for exterior concrete slabs at building entrances with similar soil conditions.

The use of a slab warming system is recommended to prevent frost penetration below exterior concrete slabs at building entrances. This system may also be used to melt snow and ice that might otherwise accumulate on the surface of the concrete slab at the building entrances. Other options that may be considered to prevent frost heave of exterior concrete slabs are the use of rigid insulation or construction of a structural slab at the building entrances. The exterior slabs should be sloped away from the building and the exterior slab/building interface should be sealed to prevent seepage of surface runoff into the subgrade soils. In areas where frost protection is not provided, the exterior wall facing should not project beyond the face of the grade beam or there should be adequate clearance to accommodate frost heave of the exterior concrete slab.

2.6 Site Seismic Classification

Table 4.1.8.4.A. in the National Building Code of Canada (NBCC) presents Soil Site Class Definitions based on various criteria, including the shear wave velocity, standard penetration resistance and undrained shear strength. The table provides correlations for Soil Site Classes C, D, and E with various ranges of standard penetration resistance and undrained shear strength to be calculated for the top 30 m of the subsurface materials at a site. Based on our review of the undrained shear strength test data for this project and our knowledge of the soil conditions in the general site vicinity, it is our judgment that the project site can be classified as Soil Site Class E for seismic design considerations. It should be noted that the Province of Manitoba has repealed the seismic classification requirement from the National Building Code and consequently, there is no current requirement to incorporate seismic design into this project.

3 SITE SURVEY

A survey of the site was conducted on November 5th, 2012. The results can be seen on the survey drawing shown in Appendix E1. This site drawing was used to create a mechanical and electrical utility service drawing which can be seen in Appendix E2.

The survey was limited to an area surrounding the proposed location of the new greenhouse building.

From the geophysical survey, the EM data suggests that the “old building foundation” depth is greater than at least 0.5 m below grade and possibly as much as 1.0 m. The foundation width could not be deduced based on the scan data but, a 6-inch wide rectangular outline on the ground surface can be seen. Discussion with the site manager indicate the substructure of the demolished building belonged to an old greenhouse. Also, there is an electrical utility buried near the northwest corner of the building foundation so care should be taken at this location in the event any digging is to occur.”

3.1 Mechanical Site Observations

3.1.1 General Information

This section of the report covers the mechanical utilities capacity study portion of the project. It is written in accordance with the terms of reference with the goal of determining the reserve capacity of the Centre and Building #72.

The recommendations pertaining to the suitability of current utilities to the new developments are limited due to the lack of exact data on the utility requirements of the proposed building and renovations. However, water and sewer systems appear to be adequate for new construction depending on the size and depth of the new building. Natural gas services may need to be increased depending on the needs of the building processes, in addition to the building heating requirements.

3.1.2 Sources of Information

Information used to describe and analyze existing systems included the following:

- .1 Site Visits/Site Investigations
- .2 Information requests
- .3 Interviews
- .4 Existing drawings

3.1.3 Water

Water supply for the Centre is provided by the City of Morden water utility. From the street, there is an incoming underground 150 mm (6”) metered water main serving the fire protection and domestic water systems of the whole compound.

Like the existing system, it is anticipated that the biggest demand on the system will be the fire protection requirements of the new building. There are fire hydrants throughout the compound and there is one just east of the proposed location of a new greenhouse. This hydrant would most likely be served by a 150 mm (6") water main, which would be the recommended connection point for the future building. If this pipe is not 150 mm (6") and the fire protection system of the new building requires this size, there is a 150 mm (6") water main to the north west. It is highly likely that the current water distribution is sufficient for the new building.

With regards to any renovations to Building #72, there is adequate surplus capacity for the renovation. The building's main water service pipe is 150 mm (6"). There is also a current project that eliminates city water use for cooling, which has historically been the largest contributor to water consumption. The renovation as described indicates no major change in water demand, but if there are new substantial water loads, it is recommended that the greenhouse/header house be connected to the main water service to make sure that there are no adverse effects on current plumbing fixtures and/or equipment.

There is convenience in having one water meter for the whole center, but it is not optimal where fire protection systems exist downstream of the meter. This type of installation for a water meter is not normally done. The fire protection system does not regularly consume water except for regular testing, leaks and perhaps accidental discharges. The operating cost for those flows does not justify changing the current configuration. However, if fire protection does get used then it does impact the systems. The water meter is substantially undersized (3" or 4"), which may not affect low demand flows but it will affect high demand flows like fire hydrants or standpipe use. Water consumption for the fixtures in the buildings can be seen in Table 8.

Table 8 - Water Fixture Unit (WFU)

| Building | Current WFU Load | WFU Capacity Approx. |
|-----------------------------|-------------------------|-----------------------------|
| #50 Public Washrooms | 85 | 90 |
| #6 Special Crop's Office | 40 | 151 |
| #64 Seed Laboratory Bldg. I | 53 | 88 |
| #73 Maintenance shop | 40 | 151 |
| #72 Main Building | 340 | 4000 |
| Research Station | 558 | 5000 |

With regards to service water, the system pressure is high. Currently, it is around 620 kPa (90 psi). This pressure is good if there is a tall building to supply, when certain equipment requires a higher pressure, or when we have undersized pipes (which is not the case here). When not needed, it does increase the potential for water consumption and increases the likelihood of leaks and breakage.

This high static system pressure is not a guarantee that system pressure is adequate for a fire protection system. If the new building requires a standpipe system it is almost certain that it will require a 150 mm (6") connection (which is available) and a fire pump. Water supply testing and hydraulic calculations of the new building will confirm this.

3.1.4 Storm and Sewer System

There is separate land drainage system for rain water serving the Centre. There will be changes to this system to accommodate the new building connection point or vehicle traffic flow. Putting a building on a grass area will increase run-off. However, the size of the new development is not enough to impact the existing system.

For the waste water system, the Centre is connected to the City's sewer system by a 250 mm (10") sewer pipe. There is a lift station near the front entrance of the Centre using two 850 L/min (225 gpm) submersible pumps. Currently, the estimated peak service water usage for the whole Centre is just over 380 L/min (100 gpm). This estimated peak water usage does not include the use of City water for direct cooling which is assumed to be removed. The difference between the lift station capacity and current peak usage indicates that there is a lot of extra capacity downstream of the system. The current anticipated drain load and system capacities for normal usage are shown in Table 9.

Table 9 - Drainage Fixture Unit (DFU)

| Building | Current DFU Load | Approx. DFU Capacity |
|---------------------------|-------------------------|-----------------------------|
| #50 Public Washrooms | 52 | 700 |
| #6 Special Crop's Office | 22 | 180 |
| #64 Seed Laboratory Bldg. | 31 | 180 |
| #73 Maintenance shop | 25 | 180 |
| #72 Main Building | 139 | 2000 |
| Research Station | 269 | 2500 |

There is a sewer pipe serving Building #73, which is close to the proposed location of the future building. There appears to be ample depth of the existing sewer line available to tie into this manhole as there are other buildings further upstream connected to this manhole. However, if the new buildings will have a basement with washrooms or other equipment requiring drains, then the available depth should be reviewed further.

With regards to the renovation at Building #72, there is a 250 mm (10") sewer line serving the building with capacity that should be more than enough to handle future renovations.

3.1.5 Natural Gas Distribution

Gas is being distributed throughout the complex by a 50 mm (2") gas main. There is one gas meter near the entrance gates. An interview with Hydro informed the study of the distribution pressure having been increased to 15 psi in 2009 from 10 psi. The gas pressure is lowered to 5 psi before it enters each building.

Summation of all gas burning equipment in the Centre (Table 10) shows that the current mainline is already carrying the maximum prescribed load. If the system pressure can be raised, the current size may meet the future loads. Hydro will decide if this is possible. Currently, they can't make the decision until they know how much load will exactly be added. If this is not possible, a new line may be needed from the gas meter to the new building.

Table 10 – Natural Gas Load

| Building | Current Load ft³/h | Current ft³/h Capacity |
|---------------------------|--------------------------------------|--|
| #72 Main Building | | 15,000 |
| Boiler | 6,000 | |
| Boiler | 6,000 | |
| Boiler 2, 2a | 3,000 | |
| Steam Boiler | 3,000 | |
| Hot Water tank | 400 | |
| #73 Maintenance shop | | 3,000 |
| Boiler | 300 | |
| Hot Water tank | 40 | |
| W-bay Heater | 100 | |
| Radiant Heater | 60 | |
| #64 Seed Laboratory Bldg. | | 500 |
| Radiant Heater | 60 | |
| Radiant Heater | 60 | |
| Radiant Heater | 60 | |
| Radiant Heater | 60 | |
| Dryer | 100 | |
| #34 Dryer Bldg. | | 500 |
| Dryer | 100 | |
| Site Estimated Total | 19,340 | 1900 |

3.2 Electrical Site Observations

3.2.1 Summary

This section of the report covers the electrical utilities capacity study portion of the project. It is written in accordance with the terms of reference with the goal of determining the reserve capacity of the Centre and Building #72.

3.2.2 Sources of Information

Information used to describe and analyze existing systems included the following:

- .1 Site Visits/Site Investigations
- .2 Information requests
- .3 Interviews
- .4 Existing drawings

3.2.3 Power Distribution

Normal electrical service:

The electrical service for Morden Research Centre is provided and maintained by Manitoba Hydro through the high voltage line along Route 100.

The electrical service is metered by MB Hydro through a single meter and is located by the utility pole along Route 100. Based on utility data from the facility, for the last twelve months the maximum power consumption of the facility was 275 kW in the month of October 2011.

There are two incoming service entrances from Manitoba Hydro, both located on the west side of the property along Route 100.

After the utilities incoming service demarcation point, all equipment thereafter are customer owned.

The following transformer power consumption estimates are based on the connected building loads as determined from the electrical panels. The first service entrance serves customer transformer TR#1 750 kVA 25KV-347/600V transformer through an underground direct buried 3-1/0 25KV primary conductors and provides power to Buildings 69, 72 and 73. The transformer has reached its 80% capacity, it has 20% spare left to accommodate another building.

The second service entrance serves customer transformers TR#2 – 300kVA 12470-120/208V; TR#3 – 50kVA 7200-120/208V and TR#4 – 50kVA 7200-120/208V through an underground direct buried 3-1/0KV primary conductors.

Transformer TR#2 provides power to Buildings #38, 39, 64, 67, and 75; TR#3 provides power to Buildings #6, 7, and 33; and TR#4 provides power to previously existing Building #51.

Transformer TR #2 has 20% spare capacity, transformer TR#3 has 20% spare capacity and transformer TR#4 has 100% spare capacity.

All of the customer-owned transformers, complete with their associated primary and secondary conductors, were installed in the year 2003 and appear to be in good condition.

The main distribution panel (MDP) in Building #72 is a 1600A 347/600V 3-phase 4-wire 22kA with a main breaker made by Westinghouse LSIG 1600A 600V 3-phase, and appears to be in good condition.

The panel in Building #72 currently supplies power to Building #73 and crosses the site of the proposed greenhouse/header house as can be seen in Appendix E.

Emergency electrical service:

The existing diesel generator set in the facility, located in Building #72, is 80kW with a system voltage of 600V. The manufacturer is Cummins and it appears to be in good condition. The unit is serving panels E-100, E-200, E-300, E-400, EA, MCC, and maintenance shop. It appears that, from the connected electrical loads based on panel directories, around 60% of the generator capacity has been utilized by these existing electrical panels. The standby unit has a 20% spare capacity for future load.

The existing automatic transfer switch is a Eaton Cutler-Hammer ATH series 600V 3-Phase 150A manufactured in December 2008, has limited expansion capacity and may not meet current code standards.

The generator unit has an existing day tank located in the same room.

3.2.4 Telecommunication

The telephone service in Morden Research Centre is provided by MTS through the pedestal along Route 100. That service has been extended to the facility and terminated in another pedestal located adjacent to transformer TR#1. The existing MTS service lines are routed underground from the pedestal. The cable present in this pedestal is a 50-pair cable and currently 8 are in use.

If required in the proposed new greenhouse and header house, telephone service may be provided through this same pedestal. There is capacity in the pedestal, but pending MTS requirements may have to extend from site entrance demark location or to suit MTS requirements.

AAFC are in the process of upgrading their incoming telephone system with voice over the internet.

Re-route existing underground cables and conduit runs in the area of the new building location.

3.2.5 Fire Alarm System

The existing fire alarm control panel for the facility is located in the electrical room in Building #72. The control panel is a Simplex 4002 conventional system with 28 alarm zones and two spare zones. There is a room to expand the system, however it is very difficult to obtain parts and an expansion most likely will require replacement of the panel.

4 MISCELLANEOUS TEST REPORTS

4.1 Fire Hydrant Test Report

Fire hydrant flow tests were conducted to establish existing water main flow rates and pressure.

Tests were performed by Deblo Industries Ltd. on November 5th, 2012 between the hours of 1:30pm and 3:00pm. The technician used a Hydropro 100 Diffuser flow measuring device manufactured by Pollard Water. The device did not contain a serial number.

The test locations, flow test results, and test equipment information can be seen in Appendix F. Each hydrant was opened for about five minutes to clear the line prior to taking flow measurements. Pressure measurements are recorded in pounds per square inch.

5 LIMITATIONS

5.1 Geotechnical, Mechanical, and Electrical Assessments

Professional judgments and recommendations are presented in this report. They are based on an evaluation of the technical information gathered during the site investigation. We do not guarantee the performance of the project in any respect other than that our engineering work and judgment rendered meet the standards and care of our profession.

Geotechnical testholes and associated test results may not represent potentially unfavourable subsurface conditions between the testholes. If during construction soil conditions are encountered that vary from those discussed in this report, we should be notified immediately in order that we may evaluate the impact, if any, on the recommendations provided in this report. The recommendations presented in this report are applicable only to this specific site. The data herein should not be used for other purposes.

The mechanical capacity assessments are limited to typical building construction and cannot guarantee adequate capacity for all possibilities. The designers of new buildings on site must exercise professional judgment based on the type and size of building to be constructed.

The electrical assessments comment on capacity but do not guarantee the quality of power.

APPENDIX A

SITE PHOTOGRAPHS



Photo 1 - Project site looking north from southwest corner



Photo 2 - Project site looking southwest from northeast corner



Photo 3 - Standpipe piezometer installed in Testhole TH 04



Photo 4 - Drilling Testhole TH 08



Photo 5 - Electrical main service entrance



Photo – 6 Telephone main service entrance



Photo – 7 Transformer TR#1 – 750Kva 12470-347/600V





Photo – 8 Transformer TR#2 – 300Kva 12470-347/600V



Photo – 9 Transformer TR#4 – 50Kva 7200-347/600V (Identical to transformer TR#3)

APPENDIX B

TESTHOLE LOCATION PLAN



Testhole Location Plan
Morden Research Centre
Morden, Manitoba

Scale: NTS

APPENDIX C


TESTHOLE LOGS AND CBR REPORT

TESTHOLE TH 01



Project Name: Morden Research Centre
Project Location: Morden, Manitoba
Client: Public Works and Government Services Canada
Drilling Contractor: Kletke Enviro Drilling Ltd.
Drilling Method: 125 mm Solid Stem Auger
UTM Coordinates: 14U 566489 m E, 5448960 m N

Date Drilled: November 15, 2012
Depth of Testhole: 10.0 m
Logged by: Trevor Schellenberg
Reviewed by: German Leal
Testhole Elevation: 298.35 m




TESTHOLE TH 02



Project Name: Morden Research Centre
Project Location: Morden, Manitoba
Client: Public Works and Government Services Canada
Drilling Contractor: Kletke Enviro Drilling Ltd.
Drilling Method: 125 mm Solid Stem Auger
UTM Coordinates: 14U 566514 m E, 5448951 m N

Date Drilled: November 15, 2012
Depth of Testhole: 10.0 m
Logged by: Trevor Schellenberg
Reviewed by: German Leal
Testhole Elevation: 298.45 m




TESTHOLE TH 03



Project Name: Morden Research Centre
Project Location: Morden, Manitoba
Client: Public Works and Government Services Canada
Drilling Contractor: Kletke Enviro Drilling Ltd.
Drilling Method: 125 mm Solid Stem Auger
UTM Coordinates: 14U 566477 m E, 5448952 m N

Date Drilled: November 15, 2012
Depth of Testhole: 10.0 m
Logged by: Trevor Schellenberg
Reviewed by: German Leal
Testhole Elevation: 298.32 m




TESTHOLE TH 04



Project Name: Morden Research Centre
Project Location: Morden, Manitoba
Client: Public Works and Government Services Canada
Drilling Contractor: Kletke Enviro Drilling Ltd.
Drilling Method: 125 mm Solid Stem Auger
UTM Coordinates: 14U 566464 m E, 5448954 m N

Date Drilled: November 15, 2012
Depth of Testhole: 10.0 m
Logged by: Trevor Schellenberg
Reviewed by: German Leal
Testhole Elevation: 298.03 m




TESTHOLE TH 05



Project Name: Morden Research Centre
Project Location: Morden, Manitoba
Client: Public Works and Government Services Canada
Drilling Contractor: Kletke Enviro Drilling Ltd.
Drilling Method: 125 mm Solid Stem Auger
UTM Coordinates: 14U 566458 m E, 5448934 m N

Date Drilled: November 15, 2012
Depth of Testhole: 10.0 m
Logged by: Trevor Schellenberg
Reviewed by: German Leal
Testhole Elevation: 297.70 m




TESTHOLE TH 06



Project Name: Morden Research Centre
Project Location: Morden, Manitoba
Client: Public Works and Government Services Canada
Drilling Contractor: Kletke Enviro Drilling Ltd.
Drilling Method: 125 mm Solid Stem Auger
UTM Coordinates: 14U 566461 m E, 5448919 m N

Date Drilled: November 15, 2012
Depth of Testhole: 10.0 m
Logged by: Trevor Schellenberg
Reviewed by: German Leal
Testhole Elevation: 297.84 m




TESTHOLE TH 07



Project Name: Morden Research Centre
Project Location: Morden, Manitoba
Client: Public Works and Government Services Canada
Drilling Contractor: Kletke Enviro Drilling Ltd.
Drilling Method: 125 mm Solid Stem Auger
UTM Coordinates: 14U 566484 m E, 5448921 m N

Date Drilled: November 15, 2012
Depth of Testhole: 10.0 m
Logged by: Trevor Schellenberg
Reviewed by: German Leal
Testhole Elevation: 298.18 m




- Minor groundwater seepage was observed at a depth of 3.3 m.
- Groundwater level was observed at a depth of 3.3 m upon completion of drilling.
- Soil sloughing was observed in the sand layer at a depth of 3.3 m.
- Testhole terminated at a depth of 9.2 m.

TESTHOLE TH 08



Project Name: Morden Research Centre
Project Location: Morden, Manitoba
Client: Public Works and Government Services Canada
Drilling Contractor: Kletke Enviro Drilling Ltd.
Drilling Method: 125 mm Solid Stem Auger
UTM Coordinates: 14U 566483 m E, 5448936 m N

Date Drilled: November 15, 2012
Depth of Testhole: 10.0 m
Logged by: Trevor Schellenberg
Reviewed by: German Leal
Testhole Elevation: 298.49 m




CBR Report

(ASTM D 1883)



| | | | |
|------------------|------------------------|------------|-----------------------|
| Client: | The National Test Labs | Sample ID: | Road Subgrade 0 to 3' |
| Project: | Morden Research Center | | |
| Date: | 09 January 2013 | Test Date: | 02 January 2013 |
| Sample Received: | 28 December 2012 | AMEC ID: | WX10300-10 |
| Attention: | Mr. German Leal | | |

| Compaction Method: | ASTM D698 | Moisture as compacted: | | 28.60% |
|--------------------------|-------------------|------------------------------------|------------------|---------------|
| Soaked: | Yes | Moisture Top 25.4mm after loading: | | 29.70% |
| Percent Swell: | 0.63% | Dry Density before testing: | | 1471 kg/m3 |
| Bearing Ratio (Soaked): | 2.54 pen top | 2.19% | Sample ID: | CBR |
| | 5.08 pen top | 2.28% | | |
| | 12.7 pen top | 1.91% | | |
| Time Interval Seconds | Penetration MM | Dial Reading | Force Newtons | Stress Mpa |
| 0 | 0 | 0 | 0 | 0.00 |
| 43 | 0.635 | 125 | 167 | 0.09 |
| 76 | 1.270 | 183 | 240 | 0.12 |
| 107 | 1.905 | 224 | 293 | 0.15 |
| 138 | 2.540 | 257 | 337 | 0.17 |
| 251 | 5.080 | 347 | 456 | 0.23 |
| 362 | 7.620 | 405 | 531 | 0.27 |
| 474 | 10.160 | 468 | 610 | 0.31 |
| 584 | 12.700 | 511 | 665 | 0.34 |



Comments:

AMEC Environment & Infrastructure

Per _____
 Contact: Trevor Gluck, P. Eng.
 Manager; Technical Services

Reporting of these results constitutes a testing service only. Engineering interpretation or evaluation of the test results is provided only on written request.

APPENDIX D

LABORATORY TEST REPORTS

PARTICLE SIZE ANALYSIS ASTM D422

PWGSC
Western Region
167 Lombard Avenue
Winnipeg, Manitoba
R3C 2Z1


PROJECT: Morden Research Centre

Attention: Steve Miville

PROJECT NO.: STA-1259

SAMPLED BY: Trevor Schellenberg
SAMPLE ID: TH4 at 0.8 m

DATE RECEIVED: November 22, 2012
TESTED BY: Larry Presado



| PARTICLE SIZE | | PERCENT PASSING | |
|---------------|--|-----------------|--|
| 37.50 mm | | 100.0 | |
| 25.00 mm | | 100.0 | |
| 19.00 mm | | 100.0 | |
| 16.00 mm | | 100.0 | |
| 12.50 mm | | 100.0 | |
| 9.50 mm | | 100.0 | |
| 4.75 mm | | 99.9 | |
| 2.00 mm | | 99.8 | |

| PARTICLE SIZE | | PERCENT PASSING | |
|---------------|--|-----------------|--|
| 1.18 mm | | 99.5 | |
| 0.425 mm | | 98.9 | |
| 0.250 mm | | 97.9 | |
| 0.150 mm | | 96.7 | |
| 0.075 mm | | 93.0 | |
| 0.005 mm | | 62.6 | |
| 0.002 mm | | 51.0 | |
| 0.001 mm | | NT* | |

| Gravel, % 75 to 4.75 mm | Sand, % | | | Silt, % <0.075 to 0.005 mm | Clay, % <0.005 mm | Colloids, % < 0.001 mm |
|----------------------------|---------------------------|----------------------------|----------------------------|-------------------------------|----------------------|---------------------------|
| | Coarse <4.75 to 2.0 mm | Medium <2.0 to 0.425 mm | Fine <0.425 to 0.075 mm | | | |
| 0.1 | 0.1 | 0.9 | 5.9 | 30.4 | 62.6 | NT* |

NT* Sample not tested for colloids

November 28, 2012

REVIEWED BY: Trevor Schellenberg, B.Sc., EIT

PARTICLE SIZE ANALYSIS ASTM D422

PWGSC
Western Region
167 Lombard Avenue
Winnipeg, Manitoba
R3C 2Z1


PROJECT: Morden Research Centre

Attention: Steve Miville

PROJECT NO.: STA-1259

SAMPLED BY: Trevor Schellenberg
SAMPLE ID: TH4 at 2.3 m

DATE RECEIVED: November 22, 2012
TESTED BY: Larry Presado



| PARTICLE SIZE | PERCENT PASSING | PARTICLE SIZE | PERCENT PASSING |
|---------------|-----------------|---------------|-----------------|
| 37.50 mm | 100.0 | 1.18 mm | 99.9 |
| 25.00 mm | 100.0 | 0.425 mm | 99.4 |
| 19.00 mm | 100.0 | 0.250 mm | 98.3 |
| 16.00 mm | 100.0 | 0.150 mm | 95.6 |
| 12.50 mm | 100.0 | 0.075 mm | 90.3 |
| 9.50 mm | 100.0 | 0.005 mm | 58.5 |
| 4.75 mm | 100.0 | 0.002 mm | 4.3 |
| 2.00 mm | 99.9 | 0.001 mm | NT* |

| Gravel, % 75 to 4.75 mm | Sand, % | | | Silt, % <0.075 to 0.005 mm | Clay, % <0.005 mm | Colloids, % < 0.001 mm |
|----------------------------|---------------------------|----------------------------|----------------------------|-------------------------------|----------------------|---------------------------|
| | Coarse <4.75 to 2.0 mm | Medium <2.0 to 0.425 mm | Fine <0.425 to 0.075 mm | | | |
| 0.0 | 0.1 | 0.5 | 9.1 | 31.8 | 58.5 | NT* |

NT* Sample not tested for colloids

November 28, 2012

REVIEWED BY: Trevor Schellenberg, B.Sc., EIT

PARTICLE SIZE ANALYSIS ASTM D422

PWGSC
Western Region
167 Lombard Avenue
Winnipeg, Manitoba
R3C 2Z1


PROJECT: Morden Research Centre

Attention: Steve Miville

PROJECT NO.: STA-1259

SAMPLED BY: Trevor Schellenberg
SAMPLE ID: TH4 at 4.6 m

DATE RECEIVED: November 22, 2012
TESTED BY: Larry Presado



| PARTICLE SIZE | PERCENT PASSING |
|---------------|-----------------|
| 37.50 mm | 100.0 |
| 25.00 mm | 100.0 |
| 19.00 mm | 100.0 |
| 16.00 mm | 100.0 |
| 12.50 mm | 99.5 |
| 9.50 mm | 97.4 |
| 4.75 mm | 93.1 |
| 2.00 mm | 85.3 |

| PARTICLE SIZE | PERCENT PASSING |
|---------------|-----------------|
| 1.18 mm | 78.3 |
| 0.425 mm | 47.5 |
| 0.250 mm | 28.8 |
| 0.150 mm | 21.1 |
| 0.075 mm | 18.1 |
| 0.005 mm | 9.0 |
| 0.002 mm | 6.7 |
| 0.001 mm | NT* |

| Gravel, % 75 to 4.75 mm | Sand, % | | | Silt, % <0.075 to 0.005 mm | Clay, % <0.005 mm | Colloids, % < 0.001 mm |
|----------------------------|---------------------------|----------------------------|----------------------------|-------------------------------|----------------------|---------------------------|
| | Coarse <4.75 to 2.0 mm | Medium <2.0 to 0.425 mm | Fine <0.425 to 0.075 mm | | | |
| 6.9 | 7.8 | 37.8 | 29.4 | 9.1 | 9.0 | NT* |

NT* Sample not tested for colloids

November 28, 2012

REVIEWED BY: Trevor Schellenberg, B.Sc., EIT

CERTIFICATE OF ANALYSIS

**CLIENT****National Testing Laboratories Ltd.**

199 Henlow Bay

Winnipeg MB

R3Y 1G4

TEL (204) 488-6999

FAX (204) 488-6947

ATTENTION**German Leal****RECEIVED / TEMP**

Nov-29-12 12:03 / NA

REPORTED

Dec-04-12

COC #(s)

40837.5581

WORK ORDER

2111457

PROJECT

STA-1259

PROJECT INFO

Morden Research Centre

General Comments:

CARO Analytical Services employs methods which are based on those found in "Standard Methods for the Examination of Water and Wastewater", 21st Edition, 2005, published by the American Public Health Association (APHA); US EPA protocols found in "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods, SW846", 3rd Edition; protocols published by the British Columbia Ministry of Environment (BCMOE); and/or CCME Canada-wide Standard Reference methods.

Methods not described in these publications are conducted according to procedures accepted by appropriate regulatory agencies, and/or are done in accordance with recognized professional standards using accepted testing methodologies and quality control efforts except where otherwise agreed to by the client.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety. CARO is not responsible for any loss or damage resulting directly or indirectly from error or omission in the conduct of testing. Liability is limited to the cost of analysis. Samples will be disposed of 30 days after the test report has been issued unless otherwise agreed to in writing.

- All solids results are reported on a dry weight basis unless otherwise noted
- Units:
 - mg/kg = milligrams per kilogram, equivalent to parts per million (ppm)
 - mg/L = milligrams per litre, equivalent to parts per million (ppm)
 - ug/L = micrograms per litre, equivalent to parts per billion (ppb)
 - ug/g = micrograms per gram, equivalent to parts per million (ppm)
 - ug/m3 = micrograms per cubic meter of air
- "RDL" Reported detection limit
- "<" Less than reported detection limit
- "AO" Aesthetic objective
- "MAC" Maximum acceptable concentration (health-related guideline)
- "LAB" RMD = Richmond location, KEL = Kelowna location, EDM = Edmonton location, SUB = Subcontracted

Please contact CARO if more information is needed or to provide feedback on our services.

CARO Analytical Services

Final Review Per:

Cecil Chiu, B.Sc., PChem

Inorganics Coordinator, Richmond

Locations:

#110 4011 Viking Way

Richmond, BC V6V 2K9

Tel: 604-279-1499 Fax: 604-279-1599

#102 3677 Highway 97N

Kelowna, BC V1X 5C3

Tel: 250-765-9646 Fax: 250-765-3893

www.caro.ca

17225 109 Avenue

Edmonton, AB T5S 1H7

Tel: 780-489-9100 Fax: 780-489-9700

SAMPLE DATA**CLIENT
PROJECT**National Testing Laboratories Ltd.
STA-1259**WORK ORDER #
REPORTED**2111457
Dec-04-12**TP 4 @ 0.3 m (2111457-01) Matrix: Soil Sampled: Nov-29-12 12:03**

| Analyte | Result | RDL | Units | Prepared | Analyzed | Notes |
|---------|--------|-----|-------|----------|----------|-------|
|---------|--------|-----|-------|----------|----------|-------|

General Parameters

| | | | | | | |
|-------------------------|------|------|-----------|-----------|-----------|--|
| Sulfate, Water Soluble | 0.38 | 0.05 | % | Nov-29-12 | Dec-04-12 | |
| pH | 7.9 | 0.1 | pH units | Dec-01-12 | Dec-01-12 | |
| Chloride, Water Soluble | 10 | 10 | mg/kg dry | Nov-30-12 | Dec-03-12 | |

TP 4 @ 3.0 m (2111457-02) Matrix: Soil Sampled: Nov-29-12 12:03

| Analyte | Result | RDL | Units | Prepared | Analyzed | Notes |
|---------|--------|-----|-------|----------|----------|-------|
|---------|--------|-----|-------|----------|----------|-------|

General Parameters

| | | | | | | |
|-------------------------|------|------|-----------|-----------|-----------|--|
| Sulfate, Water Soluble | 0.56 | 0.05 | % | Nov-29-12 | Dec-04-12 | |
| pH | 8.3 | 0.1 | pH units | Dec-01-12 | Dec-01-12 | |
| Chloride, Water Soluble | 11 | 10 | mg/kg dry | Nov-30-12 | Dec-03-12 | |

TP 4 @ 7.6 m (2111457-03) Matrix: Soil Sampled: Nov-29-12 12:03

| Analyte | Result | RDL | Units | Prepared | Analyzed | Notes |
|---------|--------|-----|-------|----------|----------|-------|
|---------|--------|-----|-------|----------|----------|-------|

General Parameters

| | | | | | | |
|-------------------------|------|------|-----------|-----------|-----------|--|
| Sulfate, Water Soluble | 0.07 | 0.05 | % | Nov-29-12 | Dec-04-12 | |
| pH | 8.7 | 0.1 | pH units | Dec-01-12 | Dec-01-12 | |
| Chloride, Water Soluble | 41 | 10 | mg/kg dry | Nov-30-12 | Dec-03-12 | |

ANALYSIS / REPORT INFORMATION

CLIENT National Testing Laboratories Ltd.
PROJECT STA-1259

WORK ORDER # 2111457
REPORTED Dec-04-12

| Analysis Description | Method Reference(s) (* = modified from) | | LAB |
|----------------------------------|---|----------------|-----|
| | Preparation | Analysis | |
| Sulfate (CSA A23.2) | N/A | CSA A23.2-2B | RMD |
| pH in Concrete (ASTM D4972) | N/A | ASTM D4972 | RMD |
| Chloride, Water Soluble (AASHTO) | N/A | AASHTO T291-94 | RMD |

QUALITY CONTROL DATA



**CLIENT
PROJECT**

National Testing Laboratories Ltd.
STA-1259

**WORK ORDER #
REPORTED**

2111457
Dec-04-12

The following section reports quality control (QC) data that is associated with your sample data. Groups of samples are prepared in "batches" and analyzed in conjunction with quality control samples that ensure your data is of the highest quality. Common QC types include:

- Method Blank (Blk): Laboratory reagent water is carried through sample preparation and analysis steps. Method Blanks indicate that results are free from contamination, i.e. not biased high from sources such as the sample container or the laboratory environment
- Duplicate (Dup): Preparation and analysis of a replicate aliquot of a sample. Duplicates provide a measure of the analytical method's precision, i.e. how reproducible a result is. Duplicates are only reported if they are associated with your sample data.
- Blank Spike (BS): A known amount of standard is carried through sample preparation and analysis steps. Blank Spikes, also known as laboratory control samples (LCS), are prepared from a different source of standard than used for the calibration. They ensure that the calibration is acceptable (i.e. not biased high or low) and also provide a measure of the analytical method's accuracy (i.e. closeness of the result to a target value).
- Standard Reference Material (SRM): A material of similar matrix to the samples, externally certified for the parameter(s) listed. Standard Reference Materials ensure that the preparation steps in the method are adequate to achieve acceptable recoveries of the parameter(s) tested for.

Reference

Each QC type is analyzed at a 5-10% frequency, i.e. one blank/duplicate/spike for every 10 samples. For all types of QC, the specified recovery (% Rec) and relative percent difference (RPD) limits are derived from long-term method performance averages and/or prescribed by the reference method.

| Analyte | Result | Reporting Limit Units | Spike Level | Source Result | % REC % REC | % REC Limits | % RPD % RPD | % RPD Limit | Notes |
|---------|--------|--------------------------|----------------|------------------|----------------|-----------------|----------------|----------------|-------|
|---------|--------|--------------------------|----------------|------------------|----------------|-----------------|----------------|----------------|-------|

General Parameters, Batch B2K1118

| | | | | | | | | | |
|---------------------------------|--------|--|--|--|--|--|-----|----|--|
| Blank (B2K1118-BLK1) | | Prepared: Nov-29-12, Analyzed: Dec-04-12 | | | | | | | |
| Sulfate, Water Soluble | < 0.05 | 0.05 % | | | | | | | |
| Blank (B2K1118-BLK2) | | Prepared: Nov-29-12, Analyzed: Dec-04-12 | | | | | | | |
| Sulfate, Water Soluble | < 0.05 | 0.05 % | | | | | | | |
| Duplicate (B2K1118-DUP2) | | Source: 2111457-02 | | Prepared: Nov-29-12, Analyzed: Dec-04-12 | | | | | |
| Sulfate, Water Soluble | 0.56 | 0.05 % | | 0.56 | | | < 1 | 25 | |

General Parameters, Batch B2K1146

| | | | | | | | | | |
|-----------------------------|------|--|-----|--|----|--------|--|--|--|
| Blank (B2K1146-BLK1) | | Prepared: Nov-30-12, Analyzed: Dec-03-12 | | | | | | | |
| Chloride, Water Soluble | < 10 | 10 mg/kg dry | | | | | | | |
| LCS (B2K1146-BS1) | | Prepared: Nov-30-12, Analyzed: Dec-03-12 | | | | | | | |
| Chloride, Water Soluble | 485 | 10 mg/kg dry | 500 | | 97 | 80-120 | | | |

General Parameters, Batch B2L0003

| | | | | | | | | | |
|---------------------------------|-----|---------------------------|--|--|--|--|---|----|--|
| Duplicate (B2L0003-DUP2) | | Source: 2111457-02 | | Prepared: Dec-01-12, Analyzed: Dec-01-12 | | | | | |
| pH | 8.4 | 0.1 pH units | | 8.3 | | | 1 | 20 | |

MOISTURE - DENSITY RELATIONSHIP REPORT

TO
Public Works & Government Services
Canada
100-167 Lombard Ave.
Winnipeg, MB
R3C 2Z1

CLIENT Public Works & Government Services
C.C.

ATTN: Steve Miville


PROJECT Morden Research Centre

PROCTOR NO. 1

PROJECT NO. STA-1259

DATE SAMPLED 2012.Nov.15
SAMPLED BY T.Schellenberg
MATERIAL IDENTIFICATION
MATERIAL USE Subgrade
MAX. NOMINAL SIZE
MATERIAL TYPE Clay
SUPPLIER
SOURCE Existing Material

DATE RECEIVED 2012.Nov.23
DATE TESTED 2012.Nov.27
COMPACTION STANDARD Standard Proctor,
ASTM D698
COMPACTION PROCEDURE A: 101.6mm Mold,
Passing 4.75mm
OVERSIZE CORRECTION METHOD None
RETAINED 4.75mm SCREEN



| TRIAL NUMBER | WET DENSITY (kg/m3) | DRY DENSITY (kg/m3) | MOISTURE CONTENT (%) |
|-----------------|---------------------------|---------------------------|----------------------------|
| 1 | 1710 | 1445 | 18.3 |
| 2 | 1773 | 1462 | 21.3 |
| 3 | 1829 | 1473 | 24.2 |
| 4 | 1872 | 1475 | 26.9 |
| 5 | 1867 | 1444 | 29.3 |

| | MAXIMUM DRY DENSITY (kg/m3) | OPTIMUM MOISTURE CONTENT (%) |
|----------------------------------|--------------------------------------|---------------------------------------|
| CALCULATED OVERSIZE CORRECTED | 1477 | 25.5 |

COMMENTS

Material tested was identified as a composite sample of 0 to 0.8 m from testholes TH01, TH03 and TH04.

APPENDIX E1

**MORDEN RESEARCH CENTRE
SITE PLAN C-101**

PRELIMINARY
NOT FOR CONSTRUCTION

| EXISTING | LEGEND |
|-------------|-------------------------|
| WATER | WATERMAN |
| WASTE WATER | WASTE WATER SEWER |
| SEWER | GAS |
| POWER | HIGH VOLTAGE |
| DATA/COM | M.T.S. |
| ② | TREES |
| ① | TREE LINE |
| ③ | SUN |
| ④ | MANHOLE |
| ⑤ | HYDRANT |
| ⑥ | VALVE |
| ⑦ | LIGHT STAND |
| ⑧ | CULVERT |
| ⑨ | CONCRETE DRAINAGE SWALE |
| ⑩ | ELECTRICAL PNEUMATIC |
| 31-34 | ELEVATION |
| ⑪ | ROADWAY |

DO NOT SCALE DRAWINGS

[illegible]

AGRICULTURE
AND
AGRI-FOOD CANADA


| | |
|-----------------------------|------------|
| Projet 8386/Titre du projet | MORDEN, MB |
|-----------------------------|------------|

MORDEN RESEARCH CENTRE
NEW GREENHOUSE AND
HEADER HOUSE BUILDING

| | |
|--------------------------------|--|
| Approved by/Approve par BUR | |
| Designed by/Concept par | |

Written by/Dassina per
 R
 Project Manager/Administrateur de Projets TPSGC

PRCSC, Architectural and Engineering Resources Manager/
Ressources Architecturales et de Directeur d'Ingénierie, PRCSC



APPENDIX E2

**MORDEN RESEARCH CENTRE
UTILITIES PLAN ME-101**

APPENDIX F1


HYDRANT FLOW TEST MAP LOCATIONS

BUILDING INDEX

| | |
|----|-----------------------------|
| 1 | OFFICIAL CROSS OFFICE & LAB |
| 2 | POTATO BUILDING |
| 3 | |
| 4 | |
| 5 | |
| 6 | |
| 7 | |
| 8 | |
| 9 | |
| 10 | |
| 11 | |
| 12 | |
| 13 | |
| 14 | |
| 15 | |
| 16 | |
| 17 | |
| 18 | |
| 19 | |
| 20 | |
| 21 | |
| 22 | |
| 23 | |
| 24 | |
| 25 | |
| 26 | |
| 27 | |
| 28 | |
| 29 | |
| 30 | |
| 31 | |
| 32 | |
| 33 | |
| 34 | |
| 35 | |
| 36 | |
| 37 | |
| 38 | |
| 39 | |
| 40 | |
| 41 | |
| 42 | |
| 43 | |
| 44 | |
| 45 | |
| 46 | |
| 47 | |
| 48 | |
| 49 | |
| 50 | |
| 51 | |
| 52 | |
| 53 | |
| 54 | |
| 55 | |
| 56 | |
| 57 | |
| 58 | |
| 59 | |
| 60 | |
| 61 | |
| 62 | |
| 63 | |
| 64 | |
| 65 | |
| 66 | |
| 67 | |
| 68 | |
| 69 | |
| 70 | |

LEGEND

| | |
|----------------------------|---|
| HYDRO AND TELEPHONE POLES | ○ |
| WATER VALVES | ⊕ |
| MANHOLES | ⊙ |
| FIRE HYDRANTS | ⊗ |
| STREET LIGHTS | ⊕ |
| HYDRO & TELEPHONE LINES | — |
| C.P.R. TELEGRAPH LINES | — |
| 2" GAS LINES | — |
| 3/4" GAS LINES TO BUILDING | — |
| BURIED HYDRO CABLES | — |
| SEWER LINES | — |
| DEEP WATER LINES | — |
| SHALLOW WATER LINES | — |
| N.T.S. BURIED CABLE | — |
| FENCE | — |



APPENDIX F2

HYDRANT FLOW TEST RESULTS

Supplying & Servicing the
Water & Waste Industry



Since 1989

Industries Ltd.

557 Marjorie St.
Winnipeg, MB R3H 0S8

Fax: (204) 334-5588

Phone: (204) 334-4477

www.deblo.net

Email: kurtis1@mts.net

tkonchuk@mts.net

INSPECTED AT:

AGRICULTURE CANADA

INSPECTED BY:

KURTIS

CONTACT PERSON:

P.O.

BRUCE HAUGH.

COMPLETION DATE:

NOV 5, 2012

INVOICE#


| # | LOCATION OF HYDRANT | MAKE OF HYDRANT | FLOW TEST RESULTS | | | | | | STATIC |
|---|-----------------------|-----------------|-------------------|-----|--|--|--|--|--------|
| | | | RESIDUAL: | | | | | | |
| 1 | BLDG #73 | 9658 | RESIDUAL: | 24 | | | | | 86. |
| | | | PITOT READING: | 20 | | | | | |
| | | | US/GPM: | 750 | | | | | |
| 2 | BLOG #74 | MUELLER | RESIDUAL: | 20 | | | | | 85 |
| | | | PITOT READING: | 15 | | | | | |
| | | | US/GPM: | 650 | | | | | |
| 3 | N.W CORNER BLDG 72 | 9658 | RESIDUAL: | 35 | | | | | 89 |
| | | | PITOT READING: | 27 | | | | | |
| | | | US/GPM: | 880 | | | | | |
| | | | RESIDUAL: | | | | | | |
| | | | PITOT READING: | | | | | | |
| | | | US/GPM: | | | | | | |
| | | | RESIDUAL: | | | | | | |
| | | | PITOT READING: | | | | | | |
| | | | US/GPM: | | | | | | |
| | | | RESIDUAL: | | | | | | |
| | | | PITOT READING: | | | | | | |
| | | | US/GPM: | | | | | | |
| | | | RESIDUAL: | | | | | | |
| | | | PITOT READING: | | | | | | |
| | | | US/GPM: | | | | | | |

APPENDIX F3


HYDRANT FLOW TEST EQUIPMENT

PRODUCT DATA SHEET

NOTE: Dual function Gauge measures Pressure (0-100 psi) and Flow (0-1680 gpm)



Diffuser Baffle



FRONT END VIEW

THIS DRAWING AND ALL INFORMATION THEREON IS THE PROPERTY OF THE POLLARDWATER.COM COMPANY AND SHALL NOT BE USED, COPIED, OR REPRODUCED WITHOUT WRITTEN CONSENT. ALL DESIGN AND INVENTION RIGHTS ARE RESERVED.

| | | | | | |
|--|----------------------|------------------|-----------------|------|--------------------------|
| REV | REVISION DESCRIPTION | | | | DATE |
| PollardWater.com 200 Atlantic Avenue • New Hyde Park, NY 11040 | | | | | |
| TITLE HYDPRO100 DIFFUSER | | | | | |
| SIZE B | DRAFTSMAN DMB | DATE 06/08/10 | APPROVAL | DATE | DRAWING NO. JGPS0002f |
| SCALE NTS | SUPERSEDES N/A | | SHEET 1 OF 1 | | |