

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving - PWGSC / Réception des soumissions -
TPSGC
11 Laurier St./11 rue Laurier
Place du Portage, Phase III
Core 0A1 / Noyau 0A1
Gatineau, Québec K1A 0S5

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Construction Services Division/Division des services de
construction
11 Laurier St./11 Rue Laurier
3C2, Place du Portage
Phase III
Gatineau, Québec K1A 0S5

Title - Sujet S.J.C. Building Deconstruction	
Solicitation No. - N° de l'invitation EP076-131647/A	Amendment No. - N° modif. 004
Client Reference No. - N° de référence du client R.010592.002	Date 2012-12-13
GETS Reference No. - N° de référence de SEAG PW-\$\$\$FG-345-61469	
File No. - N° de dossier fg345.EP076-131647	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2012-12-20	Time Zone Fuseau horaire Eastern Standard Time EST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Nealon, Shawn	Buyer Id - Id de l'acheteur fg345
Telephone No. - N° de téléphone (819) 956-3391 ()	FAX No. - N° de FAX (819) 956-8335
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: Sir John Carling Building, Central Experimental Farm, 930 Carling Avenue, Ottawa, Ontario.	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation

EP076-131647/A

Client Ref. No. - N° de réf. du client

R.010592.002

Amd. No. - N° de la modif.

004

File No. - N° du dossier

fg345EP076-131647

Buyer ID - Id de l'acheteur

fg345

CCC No./N° CCC - FMS No/ N° VME

THE PURPOSE OF THIS AMENDMENT IS TO ISSUE ADDENDUM # 2.

End of Amendment.

Solicitation No. - N° de l'invitation

EP076-131647/A

Client Ref. No. - N° de réf. du client

R.010592.002

Amd. No. - N° de la modif.

004

File No. - N° du dossier

fg345EP076-131647

Buyer ID - Id de l'acheteur

fg345

CCC No./N° CCC - FMS No/ N° VME

Addendum No. 2

The following changes in the bid documents are effective immediately. This addendum will form part of the contract documents.

1 SPECIFICATIONS

.1 Section 01 11 00 - Summary of Work

- .1 Change Article 1.1.1.8 to read as follows: "Demolished materials may be used as backfill for the former basement areas of the Tower, East Annex and East Link provided they are processed to remove foreign materials and reduced to an acceptable size. These materials include cast-in-place reinforced concrete, precast concrete, concrete block, unit pavers, granular stone base courses and other materials that may be approved by the Departmental Representative. Backfill materials must comply with Section 31 23 33.01."

.2 Section 01 14 25 – Designated Substances Report

- .1 Add Subsection 1.1.14 with heading "ASBESTOS: Presumed", and with paragraphs to read as follows:

"Removal of mechanical duct systems and air handling units, with no fireproofing overspray on systems, follow Type 3 (Intermediate) asbestos abatement work procedures in accordance with Section 02 82 00.02.

Visually similar fireproofing in room spaces adjoining those with asbestos containing fireproofing (50-75% Chrysotile Asbestos) are to be treated as Presumed Asbestos Containing Materials (PACMs) with the same asbestos type and content. Removal of fireproofing to follow Type 3 (Maximum) asbestos abatement procedures in accordance with Section 02 82 00.03.

Spray material applied within floor slab spaces, reference Section 01 14 25 Table 1 samples Z6913-017 and Z6913-018, as such to be handled as a Friable Amosite containing (ranging from 50 to >75%) with removal following Type 3 (Maximum) asbestos abatement work procedures in accordance with Section 02 82 00.03, with appropriate respiratory protection.

Fireproofing material presumed to be present in exterior soffits of the Tower, were not sampled, and as such are to be handled as a Friable PACM, Amphibole Form with removal following Type 3 (Maximum) asbestos abatement work procedures in accordance with Section 02 82 00.03, with appropriate respiratory protection.

Fireproofing to be presumed on deck and structural building features at an average depth of 30 mm. Soffit spaces to be included in scope of work and any asbestos containing fireproofing materials to be removed before demolition.

Spray material applied within floor slab spaces, not sampled, as such to be handled as a Friable PACM as an Amphibole Form with removal following Type 3 (Maximum) asbestos abatement work procedures in accordance with Section 02 82 00.03, with appropriate respiratory protection.

All layers of mastic applied to Styrofoam to be presumed asbestos containing (5 to 10% Chrysotile). Steel can be cleaned and removed as scrap. In terms of quantities, use the larger estimated amount for costing purposes."

.3 Section 01 52 00 - Construction Facilities

- .1 Add new Subsection 1.6.2 as follows: "The load limit of the service elevator is 2,721 kg."

.4 Section 02 41 21 - Deconstruction of Structures

- .1 Add new Subsection 3.3.18 as follows: "Demolition work, if employed, may utilize any method or combination of methods including, but not limited to, implosion, explosion, hydraulic or mechanical techniques. Secure the approval of all Authorities Having Jurisdiction for demolition work. Demolition work may only occur after hazardous materials are removed. Demolition work must not compromise the Performance Requirements identified in Subsection 1.5.1. Undertake any demolition work in accordance with the approved deconstruction/disassembly plan as per Section 01 35 73, Subsection 1.4.9."

.5 Section 02 62 00.01 – Schedule A, Hazardous Materials Table A

.1 First Row - Asbestos, add five new items in second column, to read as follows:

"All thermal and mechanical insulation has been tested and is summarized in Section 01 14 25, and all were identified to contain either Chrysotile or Amosite Asbestos (reference Table 1)."

"In the two main stairwells of the Tower, the asbestos containing texture plaster material is only on the east and west wall from the basement to the mechanical penthouse. Estimated 265 m² asbestos containing texture plaster material per wall or an estimated total of 1,060 m² in the two stairwells."

"Removal to follow Type 3 (Maximum) asbestos abatement work procedures in accordance with Section 02 82 00.03 for all layers of plaster materials."

"In the West Annex and West Link, which is not scheduled for demolition, all accessible asbestos containing materials are to be removed, and any observed and not accessible ACM is to be reported to the Departmental Representative."

"All layers of mastic applied to Styrofoam to be presumed asbestos containing (5 to 10% Chrysotile) and removed as asbestos waste."

.6 Section 02 82 00.03 – Asbestos Abatement Maximum Precautions

.1 Change 3.1.1.1.5 to read as follows: "Put negative pressure system in operation and operate continuously from time first polyethylene is installed to seal openings and until final completion of work including final cleanup. Provide continuous monitoring of pressure difference using automatic recording equipment. As per DP-057 pressure differential monitoring required throughout asbestos abatement operations."

.2 Add Subsection 3.3.6 to read as follows: "For removal of friable materials containing Asbestos in Serpentine Form (Chrysotile) use at a minimum a Powered Air Purifying Respirator (PAPR) equipped with P-100 filter(s). For friable materials containing Asbestos in Amphibole Forms use at a minimum Supplied Air Respirators. Reference Table 2 in O.Reg. 278/05 to assist in selection."

END OF ADDENDUM