

**Part 1 General****1.1 INSTALLATION AND REMOVAL**

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.
- .3 Do not bury any foreign materials on site.

**1.2 HOARDING**

- .1 Provide temporary portable metal fence barriers around construction site and excavation area.

**1.3 GUARD RAILS AND BARRICADES**

- .1 Provide secure, rigid guard rails and barricades around deep excavations, open stair wells, and open edges of floors.
- .2 Provide as required by governing authorities.

**1.4 ACCESS TO SITE**

- .1 Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work and as directed by the Departmental Representative.

**1.5 PUBLIC TRAFFIC FLOW**

- .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform Work and protect the public.

**1.6 FIRE ROUTES**

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

**1.7 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY**

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

**1.8 PROTECTION OF BUILDING FINISHES**

- .1 Provide protection for finished and partially finished, new, and existing building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with The Departmental Representative locations and installation schedule three (3) days prior to installation.

- 
- .4 Be responsible for damage incurred due to lack of or improper protection.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**