

PART 1 - GENERAL

- 1.1 Precedence .1 For Federal Government projects, Division 1 Sections take precedence over technical specification sections in other Divisions of this Project Manual.
- 1.2 Related Sections .1 Section 01 52 00 - Construction Facilities.
- 1.3 References .1 Canadian General Standards Board (CGSB)
.1 CGSB 1.189M-84, Primer, Alkyd, Wood, Exterior.
.2 CGSB 1.59-97, Alkyd Exterior Gloss Enamel.
.2 Canadian Standards Association (CSA International)
.1 CSA-0121-M1978, Douglas Fir Plywood.
- 1.4 Installation and Removal .1 Provide temporary controls in order to execute Work expeditiously.
.2 Remove from site all such work after use.
- 1.5 Guard Rails and Barricades .1 Provide secure, rigid guard rails and barricades around deep excavations, open shafts, open stair wells, open edges of floors and roofs.
.2 Provide as required by governing authorities.
- 1.6 Access to Site .1 Provide and maintain access roads, as may be required for access to Work.
- 1.7 Public Traffic Flow .1 Provide Traffic Control in accordance with Section 01 55 26.
- 1.8 Fire Routes .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

<u>1.9 Protection for Off-Site and Public Property</u>	.1	Protect surrounding private and public property from damage during performance of Work.
	.2	Be responsible for damage incurred.

<u>1.10 Construction Site Security Fence</u>	.1	Provide continuous 1.8 meter high chain link fence maintain around construction site as indicated.
	.2	Install/maintain lockable gates as required.

PART 2 - PRODUCTS

<u>2.1 NOT USED</u>	.1	Not Used.
---------------------	----	-----------

PART 3 - EXECUTION

<u>3.1 NOT USED</u>	.1	Not Used.
---------------------	----	-----------