

7	ISSUED FOR TENDER	OCT 31 2012
6	ISSUED FOR TENDER READY - SUBMISSION	SEPT 13 2012
5	ISSUED FOR COORDINATION	SEPT 4 2012
4	ISSUED FOR 99% REVIEW	JULY 24 2012
3	COORDINATION PROGRESS SET	MAY 23 2012
2	ISSUED FOR 50% REVIEW	MAR. 30 2012
1	ISSUED FOR COORDINATION	MAR. 23 2012
Revision/Revision	Description/Description	Date/Date
Client/client		

**CORRECTIONAL
SERVICE OF
CANADA**

Project title/Titre du projet

FRASER VALLEY INSTITUTION
33344 KING ROAD, ABBOTSFORD, BC
**TWENTY BED
LIVING UNIT**

Consultant Approval Box Only

Designed by/Concept par
PHILIP FUNG

Drawn by/Dessiné par
ACE

PWSC Project Manager/Administrateur de Projets TPSCG
Patrick Truong


PWSC, Regional Manager, Architectural and Engineering Services/
Gestionnaire régionale, Services d'architecture et de génie, TPSCG

Drawing title/Titre du dessin

MECHANICAL

**FOUNDATION PLAN
DRAINAGE**

Project No./No. du projet	Sheet/ Feuille	Revision no./ La Révision no.
R.052462.001	M2	



DRAINAGE - FOUNDATION PLAN

SCALE: 1 : 100

SPECIFIC NOTES:

- 1 75# SAN. LINE FROM ABOVE
- 2 100# SAN. LINE FROM ABOVE
- 3 50# SAN. LINE FROM ABOVE
- 4 50# VENT TO ABOVE
- 5 NEW 20MM GAS PIPE DROP FROM ABOVE VALVE BOX. RUN U/G GAS PIPE FROM VERTICAL DROP TO BBQ AREA WITH VALVE CAP AND QUICK CONNECTION ROUGH-IN. LOCATE NEW GAS LINE (COPPER TUBE) APPROX. 750MM BELOW PATIO CONCRETE PAVING WITHOUT PIPE JOINTS. SEE ARCH. DWG A200 FOR GAS OUTLET LOCATION.
- 6 CONNECT RWL TO U/G STORM LINE PROVIDED BY CIVIL TRADE. SEE CIVIL DRAWING C01 & C03 FOR CONTINUATION.

GENERAL NOTES:

1. COORDINATE WITH GENERAL CONTRACTOR FOR EXACT LOCATION AND INVERT OF ALL FLOOR DRAINS, SANITARY WASTES, RWL'S AND VENT PIPES PRIOR TO CONSTRUCTION.
2. COORDINATE WITH GENERAL CONTRACTOR AND CIVIL TRADE FOR EXACT LOCATION AND INVERT OF COMBINED DCW AND FIRE LINE, STORM DRAINAGE, SANITARY DRAINAGE AND GAS SERVICES PRIOR TO CONSTRUCTION.