

**Part 1 General**

**1.1 EXECUTION**

- .1 Dispose of demolished materials except where specifically noted otherwise.
- .2 Where existing materials are to be reused, the Contractor for this division is responsible for their removal, storage, cleaning and reinstallation.
- .3 Where existing materials are to be demolished, the Contractor for this division is responsible to ensure that they have been isolated from the power supply prior to demolition.
- .4 Where existing materials are to be retained in place, it is the responsibility of the Contractor for this division to identify the materials and equipment to remain prior to commencement of demolition.
- .5 Maintain adequate structural support for equipment and material during demolition process.
- .6 Where only a portion of an existing electrical circuit is to be demolished this contractor to ensure that portion to remain is terminated in an electrically safe manner.

**1.2 SCHEDULING**

- .1 All work is to be performed at times arranged in advance with the Departmental Representative. Shutdowns for removal or modification of existing equipment are to be kept to a minimum, and at such times as permitted by the Departmental Representative.

**1.3 MAINTAINUNG SERVICES**

- .1 It is the responsibility of this Contractor to maintain electrical services and systems at all times to areas beyond the construction area.
- .2 Reinstate as soon as possible any existing circuits disrupted during construction not intended to be removed as part of this contract.

**1.4 REMOVAL**

- .1 Remove all wires, conduits, outlets, boxes and other pieces of electrical equipment which have been abandoned or which are becoming obsolete in the execution of this contract.

**END OF SECTION**