


SPECIFICATION

**Pumphouse Upgrades
St. Anthony Airport, NL**

Solicitation No.: EC015-140431/A



<u>Contracting Officer:</u>
Cheryl O'Brien Real Property Contracting 10 Barter's Hill, P.O. Box 4600 St. John's, NL A1C 5T2 Telephone: (709) 772-3460 Facsimile: (709) 772-4603



Stantec

MECHANICAL SPECIFICATION FOR ST. ANTHONY AIRPORT PUMPHOUSE UPGRADES

PREPARED FOR:

PWGSC
P.O. Box 4600
100 New Gower Street
St. John's, NL
A1C 5T2



SCL REF. NO: 134230674

REVISION RECORD				
REV.	DESCRIPTION	PREPARED BY	CHECKED BY	APPROVED BY
A	Issued for Tender	Brent Parsons May 29, 2013	Brad Dawe May 29, 2013	Brad Dawe May 29, 2013

<u>Section</u>	<u>Title</u>	<u>Pages</u>
<u>Division 00 - Procurement and Contracting Requirements</u>		
00 01 12	LIST OF DRAWINGS	1
<u>Division 01 - General Requirements</u>		
01 11 00	SUMMARY OF WORK	4
01 14 00	WORK RESTRICTIONS	2
01 33 00	SUBMITTAL PROCEDURES	4
01 35 13.13	SPECIAL PROJECT PROCEDURES FOR AIRPORT FACILITIES	2
01 35 29.06	HEALTH AND SAFETY REQUIREMENTS	4
01 41 00	REGULATORY REQUIREMENTS	2
01 45 00	QUALITY CONTROL	3
01 51 00	TEMPORARY UTILITIES	3
01 52 00	CONSTRUCTION FACILITIES	2
01 56 00	TEMPORARY BARRIERS AND ENCLOSURES	3
01 61 00	COMMON PRODUCT REQUIREMENTS	6
01 73 00	EXECUTION	3
01 74 11	CLEANING	3
01 77 00	CLOSEOUT PROCEDURES	2
01 78 00	CLOSEOUT SUBMITTALS	10
01 79 00	DEMONSTRATION AND TRAINING	3
01 91 13	GENERAL COMMISSIONING (CX) REQUIREMENTS	10
<u>Division 21 - Fire Suppression</u>		
21 05 01	COMMON WORK RESULTS FOR MECHANICAL	6
21 30 00	FIRE PUMPS AND CONTROLLERS	7
<u>Division 22 - Plumbing</u>		
22 10 10	PLUMBING PUMPS	4
22 11 16	DOMESTIC WATER PIPING	7
<u>Division 23 - Heating, Ventilating and Air-Conditioning (HVAC)</u>		
23 05 01	USE OF HVAC SYSTEMS DURING CONSTRUCTION	2
23 05 05	INSTALLATION OF PIPEWORK	6
23 05 19.01	THERMOMETERS AND PRESSURE GAUGES - PIPING SYSTEMS	3
23 05 23.01	VALVES - BRONZE	6
23 05 23.02	VALVES - CAST IRON	5
23 05 29	HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT	7
23 54 16	FUEL-FIRED FURNACES	5
<u>Division 25 - Integrated Automation</u>		
25 30 02	EMCS: FIELD CONTROL DEVICES	8
<u>Division 26 - Electrical</u>		
26 05 00	COMMON WORK RESULTS - FOR ELECTRICAL	15
26 05 20	WIRE AND BOX CONNECTORS 0-1000 V	2
26 05 21	WIRES AND CABLES (0-1000 V)	2
26 05 29	HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS	2
26 05 31	SPLITTERS, JUNCTION, PULL BOXES AND CABINETS	2
26 05 32	OUTLET BOXES, CONDUIT BOXES AND FITTINGS	2
26 05 34	CONDUITS, CONDUIT FASTENINGS AND CONDUIT FITTINGS	3
26 08 00	COMMISSIONING OF ELECTRICAL SYSTEMS	3

26 28 21	MOULDED CASE CIRCUIT BREAKERS	2
26 28 23	DISCONNECT SWITCHES - FUSED AND NON-FUSED	2
26 29 10	MOTOR STARTERS TO 600 V	4
<u>Division 31 - Earthwork</u>		
31 23 33.01	EXCAVATING, TRENCHING AND BACKFILLING	12
<u>Division 33 - Utilities</u>		
33 05 13	MANHOLES AND CATCH BASIN STRUCTURES	5

<u>DRAWING NO.</u>	<u>TITLE</u>
H1	Legend and List of Drawings
H2	Pumphouse Demolition Floor Plan
H3	Pumphouse New Work Floor Plan
H4	Pumphouse Schematics
H5	Details
E1	Electrical Legend, Subscripts, List of Drawings and Key Site Plan
E2	Pumphouse Existing Power Plan Demolition
E3	Pumphouse Revised Power Plan
E4	Pumphouse Electrical Riser, Panel Schedule and Details