

ADDENDUM NO. 1

Pavement Rehabilitation Terra Nova National Park Newfoundland & Labrador

THE FOLLOWING AMENDMENT TO THE BID DOCUMENTS IS EFFECTIVE IMMEDIATELY. THE ADDENDUM SHALL FORM A PART OF THE CONTRACT DOCUMENTS.

- .1 In the Specifications, remove Section 00 01 11 – List of Contents, and replace with revised Section 00 01 11 – List of Contents, attached herewith.*
- .2 In the Specifications, Section 01 10 10 – General Instructions, add new Clause 1.1.3.14 to read:
.14 Supply and install guide rail, as directed by Departmental Representative.*
- .3 In the Specifications, Section 01 29 00 –Project Particulars and Measurement, add new Clause 1.2.12 to read:
.12 Guide Rail
 - .1 Supply only of roadside steel W-beam guide rail, including posts and necessary hardware, will be measured in lineal metres.*
 - .2 Installation only of roadside steel W-beam guide rail, including posts and necessary hardware, will be measured in lineal metres installed and measured from outer tips of steel W-beam guide rail, including guide rail used in terminal sections.*
 - .3 Supply and installation of reflectorized strips on the guiderail posts shall be incidental to the installation only unit price.**
- .4 In the Specifications, Section 01 29 00 – Project Particulars and Measurement, delete Clause 1.2.5 and replace with a new Clause 1.2.5 to read:
.5 Cold Planing:
 - .1 Measurement for payment shall be on the basis of the required surface area subject to cold planing to the required depth. The area shall be computed in square metres, rounded to on decimal place. Payment at the contract unit price shall be compensation in full for all labour, materials and use of equipment to; carry out the cold planing to the required depth, preparation of local roads including grading, scarifying and compaction,**

sweep the planed surface and load and haul milled material for placement on local gravel roads within the Park boundaries at locations and quantities as follows and as directed by the Departmental Representative:

<i>.1</i>	<i>Golf Course Road</i>	<i>600 m³</i>
<i>.2</i>	<i>Ochre Hill</i>	<i>2,300 m³</i>
<i>.3</i>	<i>Terra Nova Road</i>	<i>5,400 m³</i>
<i>.4</i>	<i>Big Brook Pit Road</i>	<i>900 m³</i>
<i>.5</i>	<i>Newman's Sound Road</i>	<i>3,100 m³</i>
<i>.6</i>	<i>Blue Hill Road</i>	<i>2,100 m³</i>

- .5 In the Specifications, Section 01 29 00 – Project Particulars and Measurement, delete Clause 1.2.10 and replace with new Clause 1.2.10 to read:*

.10 New Culverts and Relining of Existing Culverts:

- .1 Unit of Measurement: metre (m).*
- .2 Method of Measurement: along centreline of new and relined culvert pipe, from end to end of culvert, as laid and as accepted by the Departmental representative.*
- .3 Payment for this item includes:*
 - .1 Dewatering of site.*
 - .2 Cold planing, removal and disposal of existing asphalt concrete, as per Section 32 01 16.*
 - .3 Excavation and removal of existing CSP culverts, and disposal of all old fill and culvert material, as well as any extra excavated material required to install new culvert.*
 - .4 Supply and placement of new culvert or culvert relining.*
 - .5 Supply and placement of clay plug or concrete cut-off walls at inlet and outlet.*
 - .6 Supply and placement of rip rap.*
 - .7 Supply and placement of grout.*
 - .8 All other cost not included with other units in this contract.*

- .6 In the Specifications, Section 31 11 00 – Clearing and Grubbing, delete Clause 3.2.1, and replace with new Clause 3.2.1 to read:*

- .1 Clear all trees and underbrush by saw cutting from areas indicated to within 100 mm of original ground surface. Mechanical brushers are not permitted. Tree sections below 100 mm in diameter, underbrush, as well as all other materials disturbed during this clearing operation are to be chipped and spread evenly over the cleared area.*

- .7 *In the Specifications, remove Section 33 42 13 – Pipe Culverts and replace with revised Section 33 42 13 – Pipe Culverts, attached herewith.*
- .8 *In the Specifications, add new Section 34 71 13 – Steel W-Beam Guide Rail, attached herewith.*
- .9 *In the Specifications, Appendix B, add the following Drawings, attached herewith:*

Culvert #13 Replacement – Sta 9+701

- C1 Existing Plan*
- C2 Section A-A Existing*
- C3 Section A-A New Reliner*
- C4 Details*
- C5 Cut Off Wall for Circular CSP*

Standard Drawing 1401G – Installation of Steel Beam Guide Rail

Standard Drawing 1402A – Steel Beam Guide Rail

By submission of its bid, the Bidder confirms that it has read and understands the requirements expressed in all addenda and has included all costs of these requirements in its Total Bid Amount.
