

Questions and Answers:

Q: Can the ground rods be replaced with ground plates. It is all rock and there is no great amount of ground to drive in 2 - 10 foot rods.

A: Yes, ground plates can be used.

Q: We do not believe the sheet metal covers that are over the gain tubes will fit after heaters are installed. Do they need to be replaced?

A: Yes, the sheet metal covers will fit new heaters.

Q: There is no request or requirement for any type of control of the heaters in the work request.

A: No automated control.

Q: Is a control panel with contactors, relays, remote wiring to either thermostats or thermocouples to be considered as a future installation by others?

A: Yes, the control panel will be installed in the future by others.

Q: Will a generator by others be on site and connected so that testing and commissioning of the system may be done

A: Yes, Contractor shall rent a generator enough capacity for testing and commissioning for one day. Add the rental cost including fuel to the contract.

Q: This across the line, full on, (controlled only by manual breakers) offers no control and very little protection for your new heater elements

A: Control will be done manually by breakers.