

Part 1 General

1.1 SECTION INCLUDES

- .1 Fences and barriers.
- .2 Environmental Controls.
- .3 Access to Work site.
- .4 Fire Routes.

1.2 PRECEDENCE

- .1 Division 1 Sections take precedence over technical specification sections in other Divisions of this Project Manual.

1.3 RELATED SECTIONS

- .1 Section 01 35 55 - Security Requirements Outside the Perimeter
- .2 Section 01 35 56 - Security Requirements Inside the Perimeter
- .3 Section 01 51 00 - Temporary Utilities
- .4 Section 01 52 00 - Construction Facilities

1.4 INSTALLATION AND REMOVAL

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.5 FENCES

- .1 Install 2.4 m high chain link fencing around designated Existing Building shown on Drawing A1.0. To ensure fencing maintains its position throughout Work, install fencing complete with concrete footings.
- .2 As specified in Section 01 11 00 – Summary of Work, an existing snow fence exists on site to keep construction activities and workers away from perimeter security fence.
- .3 Maintain fences in good repair for duration of Work.

1.6 WINDOW COVERING

- .1 To obstruct the view of construction activities by Inmates in existing Bedroom 111 and 141, install removable translucent film over window glazing. Place translucent film on the exterior side of glazing.

- .2 Use a purpose-made film acceptable to Departmental Representative that will mask the view from the windows, without compromising light transmittance, and that which will be readily removable without damaging or marking the glass surface.

1.7 BARRICADES

- .1 Provide secure, rigid barricades around deep excavations.
- .2 Provide as required by governing authorities.

1.8 WEATHER ENCLOSURES

- .1 Provide weather tight closures to unfinished openings.
- .2 Design enclosures to withstand wind pressure and snow loading.

1.9 DUST TIGHT SCREENS

- .1 Provide dust tight screens or partitions to localize dust-generating activities, and for protection of finished areas of Work.
- .2 Maintain and relocate protection until such work is complete.

1.10 ACCESS TO WORK SITE

- .1 Use existing fenced Sally Port to the East of the project site for access. Use and maintain such access as directed by Departmental Representative.
- .2 Maintain access, including roads that are part of access, for duration of Contract and make good damage resulting from Contractors' use.

1.11 PUBLIC TRAFFIC FLOW

- .1 Provide and maintain competent signal flag operators, barricades and flares, lights, or lanterns as required to perform Work and protect the public.

1.12 FIRE ROUTES

- .1 Existing fenced Sally Port is one means of access to site for firefighting purposes. Maintain and keep this access clear at all times.

1.13 PROTECTION FOR SURROUNDING PROPERTY

- .1 Protect surrounding property from damage during performance of Work.
- .2 Be responsible for damage incurred.

1.14 PROTECTION OF BUILDING FINISHES

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.

- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Departmental Representative locations and installation schedule 3 days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION