

**Part 1            General**

**1.1               PRECEDENCE**

- .1       Division 1 Sections take precedence over technical specification sections in other Divisions of this Project Manual.

**1.2               FIRES**

- .1       Fires and burning of rubbish on site is not permitted.

**1.3               DISPOSAL OF WASTES**

- .1       Do not bury rubbish and waste materials on site.
- .2       Do not dispose of waste or volatile materials, such as mineral spirits, oil or paint thinner into storm or sanitary sewers.

**1.4               DRAINAGE**

- .1       Provide temporary drainage and pumping as necessary to keep excavations free from water.
- .2       Do not pump water containing suspended materials into sewer or drainage systems.
- .3       Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authority requirements.

**1.5               SITE CLEARING AND PLANT PROTECTION**

- .1       Protect grassed areas adjacent to Work site from damage.
- .2       Minimize stripping of topsoil and vegetation.

**1.6               POLLUTION CONTROL**

- .1       Maintain temporary erosion and pollution control during performance of Work.
- .2       Control emissions from equipment to local authorities emission requirements.
- .3       Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads.

**Part 2           Products**

**2.1               NOT USED**

- .1       Not Used.

**Part 3            Execution**

**3.1                NOT USED**

.1            Not Used.

**END OF SECTION**