

Part 1 General

1.1 RELATED SECTIONS

- .1 Section 01 33 00 – Submittal Procedures
- .2 Section 01 61 00 – Common Product Requirements
- .3 Section 01 74 19 – Construction/Demolition Waste Management And Disposal
- .4 Section 08 71 10 – Door Hardware: masterkey cylinders for panel locks
- .5 Section 09 29 00 – Gypsum Board: building panels into ceilings
- .6 Section 09 91 00 – Painting

1.2 SUBMITTALS

- .1 Submit product data and shop drawings in accordance with Section 01 33 00.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and data sheets.
- .3 Shop Drawings:
 - .1 Indicate panel construction, anchor method, hardware and finishes.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Comply with requirements specified in Section 01 61 00.

1.4 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate and recycle waste materials in accordance with Section 01 74 19.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper, plastic, polystyrene, corrugated cardboard, and other packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.

Part 2 Products

2.1 ACCESS PANELS

- .1 Type: medium security; acceptable manufacturers:
 - .1 Cendrex.
 - .2 Acudor Acorn Limited.
 - .3 Inryco/Milcor.

- .2 Description (each panel):
 - .1 Non-fire rated.
 - .2 Minimum 14 gauge sheet steel perimeter frame and panel leaf.
 - .3 Frame with integral mounting flange.
 - .4 Panel leaf fitted to frame with continuous steel piano hinge.
 - .5 Fitted with cylinder lock keyed to Departmental Representative's requirements.
 - .6 Phosphate dipped steel with high quality epoxy primer.
- .3 Size: 610 mm wide x 315 mm wide clear opening.

Part 3 Execution

3.1 INSTALLATION

- .1 Install access panels in accordance with manufacturers' printed instructions.
- .2 Install masterkeyed cylinders specified in Section 08 71 00.
- .3 Adjust operable parts for correct function and smooth operation.

3.2 CLEANING

- .1 Upon completion of installation, remove surplus materials, rubbish, tools and equipment barriers.

END OF SECTION