

Part 1 General

1.1 SECTION INCLUDES

- .1 Text, schedules and procedures for systematic Waste Management Program for construction and demolition including:
 - .1 Diversion of Materials.
 - .2 Waste Audit (WA) - Schedule A.
 - .3 Waste Reduction Workplan (WRW) - Schedule B.
 - .4 Demolition Waste Audit (DWA) - Schedule C.
 - .5 Cost/Revenue Analysis Workplan (CRAW) - Schedule D.
 - .6 Materials Source Separation Program (MSSP).
 - .7 Canadian Governmental Responsibility for the Environment Resources - Schedule E.

1.2 RELATED SECTIONS

- .1 Section 01 33 00 – Submittal Procedures

1.3 PRECEDENCE

- .1 Division 1 Sections take precedence over technical specification sections in other Divisions of this Project Manual.

1.4 DEFINITIONS

- .1 Cost/Revenue Analysis Workplan (CRAW): Based on information from WRW, and intended as financial tracking tool for determining economic status of waste management practices.
- .2 Demolition Waste Audit (DWA): Relates to actual waste generated from project.
- .3 Materials Source Separation Program (MSSP): Consists of series of ongoing activities to separate reusable and recyclable waste material into material categories from other types of waste at point of generation.
- .4 Recyclable: Ability of product or material to be recovered at end of its life cycle and re-manufactured into new product for reuse by others.
- .5 Recycle: Process by which waste and recyclable materials are transformed or collected for purpose of being transferred into new products.
- .6 Recycling: Process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for purpose of using in altered form. Recycling does not include burning, incinerating, or thermally destroying waste.

- .7 Reuse: Repeated use of product in same form but not necessarily for same purpose. Reuse includes:
 - .1 Salvaging reusable materials from re-modelling projects, before demolition stage, for resale, reuse on current project or for storage for use on future projects.
 - .2 Returning reusable items including pallets or unused products to vendors.
- .8 Salvage: Removal of structural and non-structural materials from deconstruction/disassembly projects for purpose of reuse or recycling.
- .9 Separate Condition: Refers to waste sorted into individual types.
- .10 Source Separation: Acts of keeping different types of waste materials separate beginning from first time they became waste.
- .11 Waste Audit (WA): Detailed inventory of materials in building. Involves quantifying by volume/weight amounts of materials and wastes generated during construction and demolition. Indicates quantities of reuse, recycling and landfill. Refer to Schedule A.
- .12 Waste Management Coordinator (WMC): Contractor representative responsible for supervising waste management activities as well as coordinating related, required submittal and reporting requirements.
- .13 Waste Reduction Workplan (WRW): Written report which addresses opportunities for reduction, reuse, or recycling of materials. Refer to Schedule B. WRW is based on information acquired from WA (Schedule A).

1.5 DOCUMENTS

- .1 Maintain at job site, one copy of following documents:
 - .1 Waste Audit.
 - .2 Waste Reduction Workplan.
 - .3 Material Source Separation Plan.
 - .4 Schedules A, B, C, D and E completed for project.

1.6 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00.
- .2 Prepare and submit 2 copies of following within 30 days of project start-up:
 - .1 Completed Waste Audit (WA): Schedule A.
 - .2 Completed Waste Reduction Workplan (WRW): Schedule B.
 - .3 Completed Demolition Waste Audit (DWA): Schedule C.
 - .4 Cost/Revenue Analysis Workplan (CRAW): Schedule D.
- .3 Prepare and submit 2 copies of Materials Source Separation Program (MSSP) description prior to project start-up.

- .4 Submit before final payment summary of waste materials salvaged for reuse, recycling or disposal by project using material audit form.
 - .1 Failure to submit could result in hold back of final payment.
 - .2 Provide receipts, scale tickets, waybills, and show quantities and types of materials reused, recycled or disposed of.
 - .3 For each material reused, sold or recycled from project, include quantities by number, type and size of items and the destination.
 - .4 For each material land filled from project, include amount of material and identity of landfill.

1.7 WASTE AUDIT (WA)

- .1 Conduct WA within 30 days of project start-up.
- .2 Prepare WA: Schedule A.
- .3 Record, on WA - Schedule A, extent to which materials or products used consist of recycled or reused materials or products.

1.8 WASTE REDUCTION WORKPLAN (WRW)

- .1 Prepare WRW within 30 days of project start-up.
- .2 WRW should include but not limited to:
 - .1 Destination of materials listed.
 - .2 Deconstruction/disassembly techniques and sequencing.
 - .3 Schedule for deconstruction/disassembly.
 - .4 Location.
 - .5 Security.
 - .6 Protection.
 - .7 Clear labelling of storage areas.
 - .8 Details on materials handling and removal procedures.
 - .9 Quantities for materials to be salvaged for reuse or recycled and materials sent to landfill.
- .3 Structure WRW to prioritize actions and follow 3 R's hierarchy, with Reduction as first priority, followed by Reuse, then Recycle.
- .4 Describe management of waste.
- .5 Identify opportunities for reduction, reuse, and recycling of materials. Based on information acquired from WA.
- .6 Post WRW or summary where workers at site are able to review content.
- .7 Set realistic goals for waste reduction, recognize existing barriers and develop strategies to overcome these barriers.

- .8 Monitor and report on waste reduction by documenting total volume and cost of actual waste removed from project.

1.9 DEMOLITION WASTE AUDIT (DWA)

- .1 Prepare DWA within 30 days of project start-up.
- .2 Complete DWA: Schedule C.
- .3 Provide inventory of quantities of materials to be salvaged for reuse, recycling, or disposal.

1.10 COST/REVENUE ANALYSIS WORKPLAN (CRAW)

- .1 Prepare CRAW: Schedule D.

1.11 MATERIALS SOURCE SEPARATION PROGRAM (MSSP)

- .1 Prepare MSSP and have ready for use prior to project start-up.
- .2 Implement MSSP for waste generated on project in compliance with approved methods and as reviewed by Departmental Representative.
- .3 Provide on-site facilities for collection, handling, and storage of anticipated quantities of reusable and recyclable materials.
- .4 Provide containers to deposit reusable and recyclable materials.
- .5 Locate containers in locations, to facilitate deposit of materials without hindering daily operations.
- .6 Locate separated materials in areas which minimize material damage.
- .7 Collect, handle and transport off-site, salvaged materials in separate condition. Transport to authorized recycling facility.

1.12 STORAGE, HANDLING AND PROTECTION

- .1 Store, materials to be reused, recycled and salvaged in locations as directed by Departmental Representative.
- .2 Unless specified otherwise, materials for removal become Contractor's property.
- .3 Separate non-salvageable materials from salvaged items. Transport and deliver non-salvageable items to licensed disposal facility.
- .4 Protect structural components not removed for demolition from movement or damage. Support affected structures. If safety of building is endangered, cease operations and immediately notify Departmental Representative.
- .5 Protect surface drainage, mechanical and electrical from damage and blockage.

- .6 Separate and store materials produced during dismantling of structures in designated areas.
- .7 Prevent contamination of materials to be salvaged and recycled and handle materials in accordance with requirements for acceptance by designated facilities.
 - .1 On-site source separation is recommended.
 - .2 Remove co-mingled materials to off-site processing facility for separation.
 - .3 Provide waybills for separated materials.

1.13 DISPOSAL OF WASTES

- .1 Do not bury rubbish or waste materials.
- .2 Do not dispose of waste, volatile materials, and other waste materials such as mineral spirits, oil and paint thinner into waterways, storm, or sanitary sewers.
- .3 Keep records of construction waste including:
 - .1 Number and size of bins.
 - .2 Waste type of each bin.
 - .3 Total tonnage generated.
 - .4 Tonnage reused or recycled.
 - .5 Reused or recycled waste destination.
- .4 Remove materials from deconstruction as deconstruction/disassembly Work progresses.
- .5 Prepare project summary to verify destination and quantities on a material-by-material basis as identified in pre-demolition material audit.

1.14 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises.
- .2 Maintain security measures established by existing facility.

1.15 SCHEDULING

- .1 Coordinate Work with other activities at site to ensure timely and orderly progress of Work.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 APPLICATION

- .1 Do Work in compliance with WRW.
- .2 Handle waste materials not reused, salvaged, or recycled in accordance with appropriate regulations and codes.

3.2 CLEANING

- .1 Remove tools and waste materials on completion of Work, and leave work area in clean and orderly condition.
- .2 Clean-up work area as work progresses.
- .3 Source separate materials to be reused/recycled into specified sort areas.

3.3 DIVERSION OF MATERIALS

- .1 From following list, separate materials from general waste stream and stockpile in separate piles or containers, and consistent with applicable fire regulations.
 - .1 Mark containers or stockpile areas.
 - .2 Provide instruction on disposal practices.
- .2 On-site sale of salvaged, recovered, reusable, or recyclable material is not permitted.
- .3 Demolition Waste

Material Type	Recommended Diversion %	Actual Diversion %
Metal doors and frames	[100]	[]
Door hardware	[100]	[]
Electrical components	[50]	[]
Mechanical components	[50]	[]
Metals	[100]	[]
Rubble	[50]	[]
Wood (uncontaminated)	[100]	[]
Concrete and masonry	[100]	[]
Other		[]

.4 Construction Waste

Material Type	Recommended Diversion %	Actual Diversion %
Cardboard	[100]	[]
Plastic Packaging	[100]	[]
Rubble	[50]	[]
Steel	[100]	[]
Wood (uncontaminated)	[50]	[]
Other		[]

3.4 WASTE AUDIT (WA)

.1 Schedule A

(1) Material Category	(2) Material Quantity Unit	(3) Estimated Waste %	(4) Total Quantity of Waste (unit)	(5) Generation Point	(6) % Recycled	(7) % Reused
Wood and plastic material Description:						
Warped pallet forms						
Plastic packaging						
Cardboard packaging						
Other						
Construction material Description:						
Concrete and masonry						
Wood and plywood						
Gypsum board						
Metal cladding						
Misc. metals						
Wiring						
Caulking and adhesive products						
Paint products						
Other						

3.6 DEMOLITION WASTE AUDIT (DWA)

.1 Schedule C

(1) Material Description	(2) Quantity	(3) Unit	(4) Total	(5) Volume (m ³)	(6) Weight (m ³)	(7) Remarks and Assumptions
Wood and plywood						
Concrete and masonry						
Gypsum board						
Steel doors and frames						
Door hardware						
Glazing						
Metal cladding						
Miscellaneous metals						
Wiring						
Other						

3.7 COST/REVENUE ANALYSIS WORKPLAN (CRAW)

.1 Schedule D:

(1) Material Description	(2) Total Quantity (unit)	(3) Volume (m ³)	(4) Weight (m ³)	(5) Disposal Cost/Credit \$(+/-)	(6) Category Sub-Total \$(+/-)	(7) Cost (-)/ Revenue (+)
Wood						
Concrete and masonry						
Gypsum board						
Steel doors and frames						
Door hardware						
Glazing						
Metal cladding						
Miscellaneous metals						
Wiring						
Other						

**3.8 CANADIAN GOVERNMENTAL DEPARTMENTS CHIEF RESPONSIBILITY
FOR THE ENVIRONMENT**

.1 Schedule E:

Province	Address	Inquires
Alberta	Alberta Environmental Protection, Edmonton, AB	http://environment.alberta.ca/02638.html (780) 427-2700
	Alberta Special Waste Management Corporation, Pacific Plaza, Suite 900, 10909 Jasper Avenue, NW Edmonton, AB T5J 3L9	http://wmr.sagepub.com/content/7/1/219.abstract

END OF SECTION