

1.1 GENERAL

- .1 Canada will supply certain materials in the Contract for installation and incorporation into the Work by the Contractor.

1.2 MATERIAL
SUPPLIED

- .1 Canada will supply the new jib cranes and all fixtures and enclosures associated with the new jib crane. Canada will also supply the light fixtures associated with the poles.
- .2 The materials supplied by Canada are to be picked-up by the Contractor and delivered to the site. The location of all Canada supplied materials to be picked-up, is the DFO Storage Facility located on Glencoe Drive, Donovan's Industrial Park, Mount Pearl, NL.

1.3 DELIVERY
REQUIREMENTS

- .1 Materials supplied by Canada will be available for pick-up following acceptance of Bid. Once turned over to the Contractor, the Contractor will be responsible for delivery to the work site.
- .2 The Contractor will become responsible to supply all missing materials and repair or replace damaged items and missing parts discovered during transportation to site.
- .3 Failure of the Contractor to make a complete check of the Canada-supplied material and to acknowledge receipt of same once picked up at the DFO storage facility in Mount Pearl, shall not relieve him of this contractual responsibility to replace or repair any item subsequently found to be missing or damaged.
- .4 Departmental Representative will make

final determination as to whether an item can be repaired or must be replaced.

1.4 CONTRACTOR'S
DUTIES

- .1 Pick-up Canada-supplied material, at the DFO Storage Facility located on Glencoe Drive, Donovan's Industrial Park, Mount Pearl, NL.
- .2 Take possession of Canada-supplied material immediately upon pick-up and be responsible for transportation to site.
- .3 Obtain and pay for services to load and transport to site.
- .4 Unload and handle at site, including lifting, uncrating etc.
- .5 Store material on site at a location approved by Departmental Representative. Provide protection against inclement weather and site damage by use of appropriate covers.
- .6 Be responsible for the protection of such material against damage, loss, theft and fire from date of receipt, during transportation, loading, unloading, temporary storage and until final installation of work is accepted by the Departmental Representative.
- .7 Any damage or loss of such material shall result in the Contractor being responsible for replacement or repair of equipment at no cost to Canada.
- .8 The decision as to whether damaged items may be repaired or must be replaced with new equipment shall be the Departmental Representative's decision.
- .9 Install such material and incorporate into

PWGSC	MATERIAL SUPPLIED BY	Section 01 16 10
Harbour Development - Phase I	CANADA	Page 3
Mary's Harbour, Labrador		
P/N: R.064896.001		2013-06-06

the work. Perform assembly and make all connections as required to make item functional.

- .10 Dispose of containers, crating and protective covering off site as directed by the Departmental Representative.