

Part 1 General

1.1 FIRES

- .1 Fires and burning of rubbish on site are not permitted.
- .2 Take all the necessary measures to insure an appropriate inspection and protection for fire prevention, according to the instructions supplied.

1.2 DRAINAGE

- .1 It is forbidden to pump water containing materials particles in suspension, in the waterways, in the sewer systems, or in the drainage systems.
- .2 Control the evacuation of the water containing materials particles in suspension or any other deleterious substance according to the local authority's requirements.

1.3 WORK ADJACENT TO WATERWAYS

- .1 It is forbidden to use construction materials in the waterways.
- .2 Do not dump waste material or debris in waterways.

1.4 POLLUTION CONTROL

- .1 Properly maintain the temporary installations to prevent erosion and pollution provided in compliance with the present project.
- .2 Insure the control of any gases emitted by the materials and the installations, in accordance with the local authority's requirements.
- .3 Build temporary shelters in order to avoid any sandblasting waste and other foreign materials to contaminate the ambient air beyond the application zone.
- .4 Cover and wet down dry materials and rubbish to prevent blowing dust or debris. Remove the dust on the temporary roads.
- .5 Built temporary shelters to avoid any sandblasting waste or other foreign waste to protect water from contamination. Install dust vacuum cleaner in working area.
- .6 Built temporary shelters to avoid painting contamination in water when painting.
- .7 Plan installation of absorbing material in case of paint, oil or other contaminants in water or working area.
- .8 Prepare a prevention plan in case of spillage. Cleaning equipment's must be ready to use in working area at any time.

Part 2 **Products**

 NOT USED

Part 3 **Execution**

 NOT USED

END OF SECTION