

Part 1 General

1.1 RELATED SECTIONS

- .1 Section 01 51 00 – Temporary utilities.
- .2 Section 01 52 00 – Construction facilities.

1.2 INSTALLATION AND REMOVAL

- .1 Provide, install or build temporary access and protection facilities in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.3 GUARD RAILS AND BARRICADES

- .1 Provide and install secure, rigid guard rails and barricades in the areas where the pedestrians are not protected by guard rails.
- .2 Provide as required by governing authorities.

1.4 PROTECTION OF BUILDING FINISHES

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Be responsible for damage incurred due to lack of or improper protection.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION