



CONTRACTOR TO COORDINATE WITH UTILITY COMPANY NEW SERVICE REQUIREMENTS. ACTUAL MOUNTING HEIGHT OF SERVICE MAST TO BE COORDINATED WITH UTILITY COMPANY. ADJUST CONDUCTOR AND CONDUIT LENGTHS ON THIS DETAIL AS REQUIRED.




SERVICE ENTRANCE ELEVATION DETAIL
N.T.S.

LIGHT FIXTURES TO BE SUPPLIED BY OWNER AND INSTALLED BY ELECTRICAL CONTRACTOR. ELECTRICAL CONTRACTOR SHALL SUPPLY AND INSTALL ALL REQUIRED MOUNTING HARDWARE, WIRING, CONDUIT, LEG BOLTS, ETC. AS REQUIRED. COORDINATE WITH DEPARTMENTAL REPRESENTATIVE.



LIGHT #1 ELEVATION DETAIL
N.T.S.

NOTES:
1.) SEE GENERAL NOTES ON DRAWING E1.




LIGHT #2 ELEVATION DETAIL
N.T.S.


LIGHTING FIXTURE SCHEDULE

TYPE	LIGHT SOURCE	MOUNTING	LAMPS	VOLTS
A	FLUORESCENT	CEILING SURFACE	2 x 32W T8	120
B	HPS	WALL SURFACE	1 x 100W	120


NOTES:
1. CONTRACTOR SHALL AIM LIGHTING FIXTURES FOR OPTIMUM PERFORMANCE IN CONSULTATION WITH DEPARTMENTAL REPRESENTATIVE.



EXTERIOR LIGHTING CONTROL PANEL
N.T.S.





ELECTRICAL SINGLE LINE DIAGRAM
N.T.S.



ELECTRICAL SHED LAYOUT
N.T.S.

NOTES:
1. ALL ELEVATIONS ARE IN METRES UNLESS OTHERWISE NOTED.
2. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE NOTED.



ISSUED FOR TENDER 13/08/08
revisions
project GREENSPOND WHARF ELECTRICAL UPGRADES
GREENSPOND, NL
drawing dessin

ELECTRICAL DETAILS

designed K.N. concou
date JULY 25, 2013
drawn S.S. dessine
date JULY 25, 2013
approved
Tender Paul Curran Soumission
DFO Project Manager
project number 720198 no. du projet
drawing no. E3 no. du dessin