

PART 1 - GENERAL

1.1 GENERAL

- .1 Canada will supply certain material and equipment in the Contract for installation and incorporation into the Work by the Contractor.

1.2 MATERIAL SUPPLIED

- .1 Canada will supply the following materials to the Contract:

- .1 Treated Dimension Timber (for cribwork):
 - 200 mm x 200 mm x 6100 mm - 750 pcs
 - 200 mm x 200 mm x 4270 mm - 60 pcs
 - 200 mm x 200 mm x 3050 mm - 224 pcs
 - 150 mm x 150 mm x 6100 mm - 171 pcs

Note: The Contractor is to be aware that this list of materials for cribwork timber is not all inclusive, and that field cutting will have to take place. Vertical timbers required in lengths greater than 6100 mm will have to be supplied by the contractor.

- .2 Treated Dimension Timber (for coping):
 - 200 mm x 250 mm x 6100 mm - 13 pcs
 - .3 Treated Dimension Timber (for wheelguard):
 - 200 mm x 200 mm x 6100 mm - 13 pcs
 - .4 Treated Dimension Timber (for wheelguard blocking):
 - 75 mm x 200 mm x 3050 mm - 11 pcs
 - .5 Cobra Type Area Lighting Fixture c/w 150W HPS Lamp, HPF Ballast, 1.2m Galvanized Mounting Arm, 120V, c/w Photocell - 8 each
- .2 The above noted items are currently stored at the following address to be picked up by the Contractor:

DFO Storage Facility
121 Glencoe Drive
Donovan's Industrial Park
Mount Pearl, NL A1N 4S7

1.3 DELIVERY REQUIREMENTS

- .1 Materials supplied by the Canada will be turned over to the Contractor.

PART 1 - GENERAL
(CONT'D)

1.3 DELIVERY REQUIREMENTS
(Cont'd)

- .2 Within three (3) calendar days after pick-up of Canada-supplied material, the Contractor must:
 - .1 Conduct a complete and full verification audit of all materials received, including loose parts and individual components associated with a particular item supplied;
 - .2 Acknowledge, in writing, receipt of such items and;
 - .3 Provide copy of any delivery or transportation slips submitted by manufacturer and shipping company.
- .3 Unless shortages of material or damaged items are identified in writing to the Departmental Representative within the above specified verification period, the Contractor will become responsible to supply all missing materials and repair or replace damaged items and missing parts discovered thereafter at own expense.
- .4 Failure of the Contractor to make a complete check of the Canada-supplied material and to acknowledge receipt of same within the specified verification period shall not relieve contractor of this contractual responsibility to replace or repair any item subsequently found to be missing or damaged.
- .5 Departmental Representative will make final determination as to whether an item can be repaired or must be replaced.
- .6 In the event of failure on the part of the Contractor to submit written proof within the specified verification period, Departmental Representative reserves the right to:
 - .1 Proceed with the supply or repair of missing items through independent sources and;
 - .2 Charge costs of such items, including related shipping charges, to Contractor by conduction a financial holdback assessment against the Contract.

1.4 CONTRACTOR'S DUTIES

- .1 Pick-up Canada-supplied material, at location indicated.
- .2 Promptly inspect material. Report missing, damaged or defective items in writing to Departmental Representative in accordance with delivery requirements specified above.
- .3 Obtain and pay for services to load and transport to site.

PART 1 - GENERAL
(CONT'D)

1.4 CONTRACTOR'S DUTIES
(Cont'd)

- .4 Unload and handle at site, including lifting, uncrating, etc.
- .5 Store material on site at a location approved by Departmental Representative. Provide protection against inclement weather and site damage by use of appropriate covers.
- .6 Make all arrangements and pay associated costs to provide temporary storage from date of receipt and until final incorporation into project.
 - .1 Type and location of storage to meet with Departmental Representative's approval.
- .7 Be responsible for the protection of such material against damage, loss, theft and fire from date of receipt, during transportation, loading, unloading, temporary storage and until final installation of work is accepted by the Departmental Representative.
- .8 Any damage or loss of such material shall result in the Contractor being responsible for replacement or repair of equipment at no cost to Canada.
- .9 The decision as to whether damage items may be repaired or must be replaced with new equipment shall be the Departmental Representative's decision.
- .10 Install such material and equipment and incorporate into the work. Perform assembly and make all connections as required to make item functional.
- .11 Dispose of containers, crating and protective covering at an approved disposal site, or as directed by the Departmental Representative,
- .12 All unused timber supplied by Canada to be returned to location as identified by Departmental Representative upon completion of work.