

1.0 Drawing E-2 Demolition Plan – Room 101

1.1 The following is a list of the electrical equipment that shall be removed as per notes 'E' and 'G'.

General area lighting in this area consists of approximately twenty five (25) fluorescent fixtures that are evenly spaced around room. There is approximately five (5) switch legs in this room for the fluorescent fixtures.

Bench mounted receptacles consist of approximately four (4) benches evenly spaced along east side of room with four receptacles per bench feed from a single conduit from overhead.

All quantities and locations are approximate and should be confirmed on site prior to submitting tender.