

ADDENDUM ITEMS

Date:	28 AUGUST 2013
Project File Number:	12-64
Project Title:	<i>PROPOSED CONSTRUCTION TACTICAL TRAINING UNIT RCMP DEPOT REGINA, SASKATCHEWAN</i>

THIS ADDENDUM SUPERCEDES ALL PREVIOUSLY ISSUED DOCUMENTATION AND WILL FORM AN INTEGRAL PART OF THE CONTRACT DOCUMENTS.

THIS ADDENDUM IS COMPRISED OF ONE (1) WRITTEN PAGE only.

ARCHITECTURAL

DRAWINGS

Drawing A-1: Specifications

Drawing A-4, Detail 105 North

Drawing A-6, Detail 5 & C

Under stair doors shall follow the profile and hinge layout as indicated on interior elevations. Confirm exact dimensions on site to suit stair stringer installation.

Door construction to be:

- 19mm fir plywood backing
- 10mm G1S birch plywood facing
- Edge trim all sides with 6mm banding to match face materials.
- Finish hardware to be provided as specified within Millwork section of specifications.

{ END OF WRITTEN PAGES }