


SMALL CRAFT HARBOURS



NOTES:

- CONSTRUCTION OPERATIONS, INCLUDING STORAGE OF MATERIALS, FOR THIS CONTRACT NOT TO INTERFERE WITH THE FISHING ACTIVITY AND/OR THE OPERATIONS AT THIS HARBOUR FACILITY.
- DISCONNECT POWER TO ALL EQUIPMENT BEFORE WORKING ON ELECTRICAL EQUIPMENT.
- CONTRACTOR TO VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS ON SITE. ANY DISCREPANCIES AND/OR UNSATISFACTORY CONDITIONS SHALL BE REPORTED TO THE DEPARTMENTAL REPRESENTATIVE BEFORE PROCEEDING WITH THE WORK.
- DO NOT SCALE FROM DRAWINGS.
- ALL EXISTING CONDUITS FROM WHARFS ARE TO BE EXTENDED TO RELOCATED ELECTRICAL CABINET AS INDICATED ON DRAWING E2.
- CONTRACTOR TO PROVIDE AND INSTALL NEW CONDUIT FROM EXISTING ELECTRICAL SERVICE/ CABINET LOCATION TO NEW LOCATION AS INDICATED ON DRAWING E2.
- CONTRACTOR TO RUN NEW CONDUCTORS FROM RELOCATED ELECTRICAL SERVICE/ CABINET TO EXISTING AND NEW LOADS AS INDICATED.
- EXISTING WIRING AND CONDUIT TO REMAIN FROM LIGHT POLE L3 TO L2 AND L1. CONTRACTOR TO PROVIDE NEW WIRING AND CONDUIT FROM NEW SERVICE LOCATION TO LIGHT POLE L3. REUSE EXISTING CONDUIT IN DECKING TO REACH EXISTING LIGHT POLE L3.
- CONTRACTOR TO LOCATE EXISTING CABLES AND REROUTE TO NEW SERVICE LOCATION. CONTRACTOR IS TO EXCAVATE AS REQUIRED AND REINSTALL EXISTING WIRING AS PER TRENCH DETAIL "B" ON DWG E2 FOR BOTH DEPTH AND MATERIALS REQUIRED.
- CONTRACTOR TO PROVIDE AND INSTALL NEW ONE 2P 30A BREAKER, THREE 1P 15 A BREAKER, ALL IN RELOCATED PANEL. ENSURE THAT BREAKERS MATCH EXISTING CHARACTERISTICS OF PANEL.
- CONTRACTOR TO ENSURE BREAKER FEEDING RECEPTACLE ON JIB CRANE IS 15A 1P. PROVIDE NEW 15A 1P BREAKER AS REQUIRED.



0	ISSUED FOR TENDER	26/08/13
A	ISSUED FOR REVIEW	12/07/13

revisions	project	date
-----------	---------	------

WHARF 402 REPAIRS

BURIN, NL

drawing dessin


EXISTING ELECTRICAL SITE PLAN, DEMOLITION AND ELEVATIONS

designed J. FLYNN	concu
date JULY 2013	
drawn K. SHAPTER	dessine
date JULY 2013	
approved	approuve

Tender	Paul Curran	Soumission
BFO Project Manager		
project number	718885	no. du projet


drawing no. no. du dessin

E1 OF 3



NOTES:


- ALL EXISTING CONDUITS TO BE CUT AND EXTENDED TO NEW LOCATION AS INDICATED ON DRAWING E2.
- ALL EXISTING WIRING TO BE PULLED FROM EXISTING CONDUITS AND REPLACED WITH NEW WIRING.
- EXISTING TECK CABLES FEEDING WHARF RECEPTACLES TO BE REPLACED WITH NEW TECK CABLES.
- ALL EQUIPMENT TO BE REUSED UNLESS NOTED OTHERWISE.
- PROVIDE AND INSTALL ADDITIONAL TECK CABLES TO NEW EQUIPMENT AS INDICATED.



ELECTRICAL SERVICE/CABINET ELEVATION A
 N.T.S.

NOTES:

- ALL EXISTING CONDUITS TO BE CUT AND EXTENDED TO NEW LOCATION AS INDICATED ON DRAWING E2.
- EXISTING WIRING TO PANEL ON WHARF TO BE PULLED FROM CONDUIT AND REPLACED WITH NEW WIRING.
- ALL EQUIPMENT TO BE REUSED UNLESS NOTED OTHERWISE.



ELECTRICAL SERVICE/CABINET ELEVATION B
 N.T.S.

PROVINCE OF NEWFOUNDLAND AND LABRADOR
PEG PERMIT HOLDER
 THIS PERMIT ALLOWS
 PROFESSIONAL ENGINEERING AND SURVEYING
 MADERRA ENGINEERING
 To practice Professional Engineering in Newfoundland and Labrador.
 Permit No. as issued by PEG Y0253 which is valid for the year 2013