

Part 1 General

1.1 REFERENCES

- .1 American Society for Testing and Materials International (ASTM)
 - .1 ASTM E202, Standard Test Methods for Analysis of Ethylene Glycols and Propylene Glycols.

1.2 CLEANING AND START-UP OF MECHANICAL PIPING SYSTEMS

- .1 In accordance with Section 23 08 02 - Cleaning and Start-up of Mechanical Piping Systems.

1.3 HYDRONIC SYSTEMS - PERFORMANCE VERIFICATION (PV)

- .1 Perform hydronic systems performance verification after cleaning is completed and system is in full operation.
- .2 When systems are operational, perform following tests:
 - .1 Conduct full scale tests at maximum design flow rates, temperatures and pressures for continuous consecutive period of 48 hours to demonstrate compliance with design criteria.
 - .2 Verify performance of hydronic system circulating pumps as specified, recording system pressures, temperatures, fluctuations by simulating maximum design conditions and varying.
 - .1 Pump operation.
 - .2 Boiler operation.
 - .3 Pressure bypass open/closed.
 - .4 Maximum heating demand.
 - .5 Boiler failure.

1.4 HYDRONIC SYSTEM CAPACITY TEST

- .1 Perform hydronic system capacity tests after:
 - .1 TAB has been completed
 - .2 Verification of operating, limit, safety controls.
 - .3 Verification of primary and secondary pump flow rates.
 - .4 Verification of accuracy of temperature and pressure sensors and gauges.
- .2 Calculate system capacity at test conditions.
- .3 Using manufacturer's published data and calculated capacity at test conditions, extrapolate system capacity at design conditions.
- .4 When capacity test is completed, return controls and equipment status to normal operating conditions.
- .5 Submit sample of system water to approved testing agency to determine if chemical treatment is correct. Include cost.

- .6 Heating system capacity test:
 - .1 Perform capacity test when ambient temperature is within 10% of design conditions. Simulate design conditions by:
 - .2 Test procedures:
 - .1 Open fully radiation control valves.
 - .2 With boilers on full firing and hot water heating supply temperature stabilized, record flow rates and supply and return temperatures simultaneously.
 - .3 Conduct flue gas analysis test on boilers at full load and at low fire conditions.

1.5 REPORTS

- .1 In accordance with Section 01 91 13 - General Commissioning (Cx) Requirements: Reports, supplemented as specified herein.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION