
TENDER QUESTIONS & RESPONSE

Q1. Confirm extent of cleaning of guano required on each tower.

Reference

a. Section 01 35 29 – 1.7.1 (page 4)

"Guano in crawl spaces, on roof, and on bridge structure beneath the motor and sheave room on both the North and South towers".

Response: Refer to The Project - Specific Designated Substance and Hazardous Materials Survey Report, Section 2.3.5 and Section 3.3 Guano (Bird Droppings) for additional information.

In addition to the area beneath the sheave and mechanical rooms on both the North and South Tower identified in the Specific Designated Substance and Hazardous Materials Survey Report, additional areas may need to be cleaned up for the health and safety of the workers.

b. Section 02 87 00 – 1.3.2 (page 1)

"The work will be conducted in the open space, below the machine rooms on both towers, extended to below the high voltage wire raceway and the catwalk but will also include the vertical surfaces of the side walls protecting this area and any surfaces within this described area.

Response: Refer to The Project - Specific Designated Substance and Hazardous Materials Survey Report, Section 2.3.5 and Section 3.3 Guano (Bird Droppings) for additional information.

In addition to the area beneath the sheave and mechanical rooms on both the North and South Tower identified in the Specific Designated Substance and Hazardous Materials Survey Report, additional areas may need to be cleaned up for the health and safety of the workers.

c. Section 01 11 00 – 1.9.9 (page 4)

"Provide a complete external cleaning of the Bridge structure prior to starting other activities. The purpose is to remove debris and accumulated bird waste".

Response: Refer to The Project - Specific Designated Substance and Hazardous Materials Survey Report, Section 2.3.5 and Section 3.3 Guano (Bird Droppings) for additional information.

In addition to the area beneath the sheave and mechanical rooms on both the North and South Tower identified in the Specific Designated Substance and Hazardous Materials Survey Report, additional areas may need to be cleaned up for the health and safety of the workers.

Q2. Can you please confirm that the guano remediation is to be treated as a type #3 asbestos removal

Response: As stated in the Project Specifications Section 02 87 00, page 2, 1.3.6, "Removal of guano shall follow the Type 3 asbestos removal process in accordance with Ontario Regulation 278/05 under the Occupational Health and Safety Act as modified in this Section."