

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving - PWGSC / Réception des soumissions -
TPSGC
11 Laurier St./11 rue Laurier
Place du Portage, Phase III
Core 0A1 / Noyau 0A1
Gatineau, Québec K1A 0S5

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Construction Services Division/Division des services de
construction
11 Laurier St./11 Rue Laurier
3C2, Place du Portage
Phase III
Gatineau, Québec K1A 0S5

Title - Sujet PANL ELEVATOR MODERNIZATION	
Solicitation No. - N° de l'invitation EP067-140879/A	Amendment No. - N° modif. 003
Client Reference No. - N° de référence du client 20140879	Date 2013-10-16
GETS Reference No. - N° de référence de SEAG PW-\$\$\$FG-349-63512	
File No. - N° de dossier fg349.EP067-140879	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2013-10-23	Time Zone Fuseau horaire Eastern Daylight Saving Time EDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: D'aoust, Jacques	Buyer Id - Id de l'acheteur fg349
Telephone No. - N° de téléphone (819) 956-0616 ()	FAX No. - N° de FAX (819) 956-8335
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: Library and Archives Canada 395 Wellington Street Ottawa, Ontario K1A 0N4	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation

EP067-140879/A

Amd. No. - N° de la modif.

003

Buyer ID - Id de l'acheteur

fg349

Client Ref. No. - N° de réf. du client

20140879

File No. - N° du dossier

fg349EP067-140879

CCC No./N° CCC - FMS No/ N° VME

This amendment is being raised to make the following changes to the Invitation to Tender document: a) to incorporate the Addendum number 02 to the solicitation document.

a) Addendum number 02

This amendment is raised to incorporate the **Addendum number 02** to the solicitation document. This Addendum will form part of the resulting contract.

All other terms and conditions remain the same.

The following changes in the bid documents are effective immediately. This addendum will form part of the contract documents

DRAWINGS

1. Drawings M100 and M101
 - .1 **ADD** - General drawing note # 2: New condensate drains are to run to the nearest floor drain. Existing floor drain locations are to be confirmed on site during construction. Allow for condensate drains of 18.0 metres in length for each wall mounted air conditioning unit.
 - .2 **ADD** - General drawing note # 3: Thermal insulation is not required for new condensate drains.
 - .3 **ADD** - General drawing note # 4: Existing sprinkler heads and piping are to remain. If during construction it is necessary to modify the sprinkler system, to allow for the installation of new equipment, work must conform to specifications section 21 13 13 Wet Pipe sprinkler Systems. All sprinkler and fire protection work is to be carried out by Vipond, who have a maintenance contract with the building.

SPECIFICATIONS

1. Section 01 00 10 - General Instructions
 - .1 **REMOVE** - Item 1.6.2. Fire Safety in its entirety.
 - .2 **REMOVE** - All References to FC standards from items 1.6.3 , 1.6.3.2, 1.6.4.
 - .3 **REMOVE** - From item 1.8.2 "*acceptable to Human Resources and Skills Development Canada (HRSDC), Labour Program.*"
 - .4 **MODIFY** - Item 1.8.3 Hazardous Materials to read: "*For work in occupied buildings, give the Department Representative 1 week notice for work involving designated substances (Ontario Bill 208), and before painting, caulking, installing carpet or using adhesives and other materials, that cause off gassing.*"
 - .5 **REMOVE** - From item 1.8.3 "hazardous substances (Canada Labour Code Part II Section 10)"
2. Section 01 35 29.06 - Health And Safety Requirements
 - .1 **REMOVE** - Item 1.1.1 and 1.1.2 References in their entirety.
 - .2 **MODIFY** - Item 1.1.3 to read: "*Province of Ontario .1 Occupational Health and Safety Act and Regulations for Construction Projects, R.S.O. 1990, c. 0.1, current editions and O. Reg. 213/91, current edition.*"
 - .3 **REMOVE** - Item 1.2.3 in its entirety.
 - .4 **REMOVE** - Territorial from Item 1.2.4.
 - .5 **MODIFY** - Item 1.7.1 to read: Be responsible and assume the role of "*Constructor*" as described in the Ontario Occupational Health and Safety Act and

Regulations for Construction Projects for health and safety of persons on site, safety of property on site and for protection of persons adjacent to site and environment to extent that they may be affected by conduct of Work."

- .6 REMOVE - Item 1.8.1, 1.8. 2, 1.8. 3. and 1.8.4 in their entirety.
 - .7 MODIFY - Item 1.8.1 - Compliance Requirements to read : "***Comply with the Ontario Occupational Health and Safety Act and Regulations for Construction Projects.***"
 - .8 MODIFY - Item 1.10. - Health and Safety Co-ordinator - requirements in its entirety.
3. Section 01 74 11 - Cleaning
- .1 Modify - Item 1.2.3 to read: "***Remove waste materials from site at daily regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site. Carry out work, this job during "regular hours", Monday to Friday from 07:00 to 18:00 hours and on Saturdays, Sundays, and statutory holidays.***"
4. Section 23 05 49 - Seismic Restraint Systems
- .1 MODIFY - Item 3.2.1.1 to read: New piping in the mechanical rooms that are less than 32mm in diameter.
 - .2 MODIFY - Item 3.2.1.2 to read: All other new piping less than 65mm in diameter.
 - .3 MODIFY - Item 3.2.1.3 to read: All new piping suspended by individual hangers 300mm or less as measured from the top of the pipe to the bottom of the support where the hanger is attached, However, if the 300mm limit is exceeded by any hanger in the run, seismic bracing is required for the run.
 - .4 MODIFY - Item 3.2.2 Design and review: Include the design, supply and installation of a complete seismic restraint system for all new equipment and piping. Design to be by a professional engineer registered in the province of Ontario. On completion of the installation, provide a professional engineered sealed and signed letter confirming review of the seismic restraint system installation.
5. Section 23 81 26 - Unitary Air Conditioning Units
- .1 MODIFY - Item 3.1.2 Installation to read: The supports for the roof mounted condensers are provided and installed by others. Refer to Structural Detail # 1, on drawing A103.

- END OF ADDENDUM 01 -